THE ODISHA STATE POLICE HOUSING & WELFARE CORPORATION LTD. JANPATH, BHUBANESWAR-22. Tel: 0674 2541545; Fax: 0674 2541543; E-mail: jmelectricalophwc@gmail.com Web: ophwc.nic.in BID REFERENCE NO: - 08/2015-16/ELECT/OPHWC SCHEDULE OF TENDER FOR EXTERNAL ELECTRIFICATION WORK OF FIRE STATION BUILDING AT PURUNABARIPADA IN THE DIST. OF MAYURBHANJ. **SOLD TO :** M/S _____ MONEY RECEIPT NO:_____ DATE: _____ [SIGNATURE OF ISSUING OFFICER]

THE ODISHA STATE POLICE HOUSING & WELFARE CORPORATION LTD. JANPATH, BHUBANESWAR-22.

Tel: 0674 2541545; Fax: 0674 2541543; E-mail: jmelectricalophwc@gmail.com Web: ophwc.nic.in

TENDER CALL NOTICE BID REFERENCE NO: - 08/ 2015-16/ELECT/ OPHWC

1. Sealed tender in the prescribed form with detailed Tender Call Notice for execution of external electrification and Area illumination work of different projects are invited in single cover system from the enlisted H.T. / M.V.(M.V. Contractors only participated with Area illumination works) electrical contractors/Firms under O.P.H.W.C., Bhubaneswar including supply of materials as per the specification. Tender to be submitted separately for each project.

Sl.No	Name of the Project	Estimated Cost	EMD	Cost of tender paper including vat	Period of comple tion	Eligibility Range
1	External electrification work of D.P.O Building at Chhatrapur in the Dist. of Ganjam.	Rs.6,99,055.00	Rs.6,991.00	Rs.4,200.00	45 days	Up to 10 lakh & above
2	External electrification work of Fire station Building at Puruna Baripada in the Dist. of Mayurbhanj	Rs.4,64,913.00	Rs.4,649.00	Rs.2,100.00	45 days	Up to 10 lakh & above
3	External electrification work of 1-D, 2-E & 6-F type Qtr. at Saraskana Fire station in the Dist. of Mayurbhanj	Rs.6,29,377.00	Rs.6,294.00	Rs.4,200.00	45 days	Up to 10 lakh & above
4	Area Illumination work of 4 th . IR. Battalion Bamrpada in the Dist. of Deogarh.	Rs.3,26,000.00	Rs.3,260.00	Rs.2,100.00	45 days	Upto 10 lakh & above
5	Area Illumination work of Motu Police station in the Dist. of Malkangiri.	Rs.1,36,328.00	Rs.1,363.00	Rs.6,30.00	45 days	Upto 10 lakh & above
6	Area Illumination work of Mudulipada Police station in the Dist. of Malkangiri.	Rs.1,40,828.00	Rs.1,408.00	Rs.6,30.00	45 days	Upto 10 lakh & above

7	External electrification work of Ambabhona Fire station in the Dist. of Bargarh	Rs.1,96,048.00	Rs.1,960.00	Rs.6,30.00	45 days	Upto 10 lakh & above
8	External electrification work of Sahadevakhunta Police Station in the Dist. of Balasore.	Rs.4,39,567.00	Rs.4,396.00	Rs.2,100.00	45 days	Upto 10 lakh & above
9	External electrification work of Out Post-Cum-Barrack at Motto in the Dist. of Balasore.	Rs.6,28,179.00	Rs.6,282.00	Rs.4,200.00	45 days	Upto 10 lakh & above
10	External electrification work of 100 Men Barrack at OSAP 5 th BN., Rangamatia in the dist. of Mayurbhanj.	Rs.5,51,955.00	Rs.5,520.00	Rs.4,200.00	45 days	Upto 10 lakh & above
11	External electrification work of Jamda Fire in the dist. of Mayurbhanj.	Rs.5,08831.00	Rs.5,088.00	Rs.4,200.00	45 days	Upto 10 lakh & above
12	External electrification work of CAPF Hub at Rangamatia in the Dist. of Mayurbhanj.	Rs.8,56,048.00	Rs.8,560.00	Rs.4,200.00	45 days	Upto 10 lakh & above
13	External electrification work of Marine Police Station at Astaranga in the Dist. of Puri.	Rs.8,05,481.00	8,055.00	Rs.4,200.00	45 days	Upto 10 lakh & above
14	External electrification work of Delanga Fire Station in the Dist. of Puri.	Rs.11,40,653.00	Rs.11,407.00	Rs.6,300.00	45 days	10 lakh above
15	External electrification work of 12-F type Qtr. at Reserve Line, Dhenkanal in the Dist. of Dhenkanal.	Rs.4,45,324.00	Rs.4,453.00	Rs.2,100.00	45 days	Upto 10 lakh & above

16	Area Illumination work of Nakamamudi BSF Camp in the Dist. of Malkangiri.	Rs.3,17,600.00	Rs.3,176.00	Rs.2,100.00	45 days	Upto 10 lakh & above
17	Area Illumination work of Kyang BSF Camp in the Dist. of Malkangiri.	Rs.1,90,775.00	Rs.1,908.00	Rs.6,30.00	45 days	Upto 10 lakh & above
18	Area Illumination work of Badapadar BSF Camp in the Dist. of Malkangiri.	Rs.3,17,600.00	Rs.3,176.00	Rs.2,100.00	45 days	Upto 10 lakh & above
19	Area Illumination work of Chintalwada at Tentuliguda BSF Camp in the Dist. of Malkangiri.	Rs.3,17,600.00	Rs.3,176.00	Rs.2,100.00	45 days	Upto 10 lakh & above
20	Area Illumination work of Bhejanwada BSF Camp in the Dist. of Malkangiri.	Rs.3,17,600.00	Rs.3,176.00	Rs.2,100.00	45 days	Upto 10 lakh & above
21	Area Illumination work of Gamphakonda BSF Camp in the Dist. of Malkangiri.	Rs.1,90,775.00	Rs.1,908.00	Rs.6,30.00	45 days	Upto 10 lakh & above
22	External electrification work of 100 Men Barrack at OSAP Koraput in the Dist. of Koraput.	Rs.3,93,983.00	Rs.3,940.00	Rs.2,100.00	45 days	Upto 10 lakh & above
23	External electrification work of BSF Camp at Gamphakonda in the Dist. of Malkangiri	Rs. 5,49,196.00	Rs.5,492.00	Rs.4,200.00	45 days	Upto 10 lakh & above
24	External electrification work of Krishnandpur Out Post in the Dist. of Jajpur	Rs. 4,97,625.00	Rs.4,976.00	Rs.2,100.00	45 days	Upto 10 lakh & above

The tender document may be obtained on payment of the tender paper cost as mentioned in the Column – 5 of the above table [Non refundable] for each project between 10.00 A.M. to 05.00 P.M on each working day from the office of the undersigned at the Address given above of

- O.S.P.H.&WC at Bhubaneswar on or before Dt.03/08/2015 .Tender document can also be obtained through speed post by sending a self addressed envelope of size 35 cm x 25 cm along with Demand Draft Pay Order of the tender paper cost as mentioned in the Column – 5 of the above table and Rs. 200.00 (Rupees two hundred only) extra for purchased by post[Non refundable] each project on any scheduled Bank, payable at Bhubaneswar, drawn in favour of the "The Odisha State Police Housing & Welfare corporation Ltd.". However, such request must be received by the undersigned on or before the last date for issue of tender document. The O.S.P.H.&W.C. authorities shall not be responsible for postal or other delays. The tender document will also available the web site be from www.ophwc.nic.in and the same can be downloaded to be used for tender offer. However in case of downloaded tender documents an amount of the tender paper cost as mentioned in the Column – 5 of the above table refundable] for each project in shape of Demand Draft / Pay Order drawn on any scheduled Bank, is payable at Bhubaneswar in favour of the "The Odisha State Police Housing & Welfare Corporation Ltd." along with the tender, failing which tender shall be liable for rejection.
- 3. The bidders are requested to submit the receipt of showing cost of tender paper along with the attested copies of valid H.T./MV license from ELBO, Income tax return copy, PAN, TIN, up to date VAT clearance certificate along with bid documents otherwise the bid shall be liable for rejection.
- 4. **EMD** The tender shall be accompanied with EMD as mentioned above in shape of D.D. / Pay order drawn on any Nationalized Bank in favour of the "The Odisha State Police Housing &Welfare corporation Ltd.", failing which the tender shall be rejected.
- 5. Other details can be seen in the tender documents.
- 6. Bids submitted otherwise than in the manner prescribed in the tender document shall be rejected.
- 7. The bidding document should be super scribed "Tender for external electrification works, Tender No., Name of the Project etc." / "Tender for internal electrification work, Tender No., Name of the Project etc." / "Tender for area illumination works, Tender No., Name of the Project etc."
- 8. The tender document is available from :10 AM on Dt.23.07 .2015
- 9. Last date for issue of tender document is up to: 05.00 PM on Dt.03.08.2015

- 10. Last date for receipt of tender document is up to: 12.30 PM on Dt.10.08.2015
- 11. Date of opening of bid at : 03.30 PM on Dt.10.08.2015
- 12. The authority reserves the right to reject any or all the bids without assigning any reason thereof.
- 13. An affidavit is to be furnish by the bidder at the time of submitting bid document that he is not blacklisted / defaulter contractor or Firm etc. The authority reserves the right to reject any or all the bids without assigning any reason thereof and can impose any conditions as deemed proper before finalisation of tender.

Sd/-Joint Manager (Elect.)

GENERAL CONDITION OF THE CONTRACT BID REFERENCE NO: - 08/ 2015-16 /ELECT/ OPHWC

- The tender document shall be accompany with the EMD as above only in shape of Demand Draft / Pay Order drawn on any Nationalized Bank payable at Bhubaneswar in favour of the "The Odisha State Police Housing & Welfare Corporation Ltd." failing which the tender shall be rejected.
- 2. The bidders are requested to submit the receipt of showing cost of tender paper along with the attested copies of valid H.T. license from ELBO, Income tax return copy,PAN, TIN, up to date VAT clearance certificate and VAT registration certificate along with bid documents otherwise the bid shall be liable for rejection. The latest authenticated documentary proof shall be submitted. The proof submitted earlier in some other contest shall not be treated as valid and sufficient.
- 3. The bid must accompany proof of executing same nature of work as per eligibility criteria mentioned in tender call notice in Govt. / Govt. Undertaking. Departments. The copy of work order and completion certificates in support of credential should be enclosed with the tender otherwise the bid shall be rejected.
- 4. The bidding document should be super scribed "Tender for external electrification works, Tender No., Name of the Project etc." / "Tender for internal electrification work, Tender No., Name of the Project etc." / "Tender for area illumination works, Tender No., Name of the Project etc."
- 5. The tenders (also called bids) not submitted in prescribed format or in prescribed manner, shall be rejected at the risk and responsibility of bidder.
- 6. All the information as called for in the tender document should be submitted truly, clearly, legible, transparently, unambiguously and without the use of abbreviations. It shall be submitted in English only.
- 7. All the crucial figures, like rates and amount should be written in figures followed by words in a bracket.
- 8. There shall be no over writing in the tender document and other papers submitted. All additions, alternations, deletions and cutting should be initialed with rubber-stamp (or seal) by the same person, who signs the tender document, failing which so, the tender may be rejected.

- All the rates and amounts shall be quoted in Indian Rupee and shall be presumed to be in Indian Rupee only unless specifically permitted to be quoted otherwise in this tender document.
- 10. Each page of this tender document should be signed by the bidder with seal in token of having read, understood and accepted the terms and conditions of this contract.
- 11. Use separate piece of paper where the space provided in the formats in this tender document for submission of information is not sufficient.
- 12. The contractor shall stand for guarantee against defective materials / manufacturing defects(except lamp in case of Area illumination work) and workmanship for the work carried out by him for a period of **24** months from its commissioning /handing over & make good /repair/replace the faults during this period without any extra cost, failing which the same shall be got done at the risk and cost of the contractor. The work shall be supervised by the qualified supervisor from the contractor's side.
- 13. All information submitted or supplied in the formats of this tender document shall be presumed to be true to the best of knowledge of bidder.
- 14. The firms not having VAT Registration certificate shall not be eligible for submitting the bids. The blacklisted firms shall also not be eligible for participating in the bid.
- 15. The tenders/bids can be sent by post or courier as well. However, authorities shall not be responsible for postal or delays in receipt of bids.
- 16. If the last date for receipt of the tender/bid turns out to be a holiday, it will automatically be extended to next working day.
- 17. A bid submitted can not be withdrawn. The bidder or his authorized representative (one person only) will be allowed to be present at the time of opening of tenders. They will not participate in the discussions. Clarification sought, if any may be provided by them.
- 18. All or any of the tenders /bids submitted can be rejected without assigning any reason thereof. No claim, whatsoever, shall be admissible for the alleged loss/damages suffered by bidders on account of such rejections.
- 19. Bids shall be opened in the presence of the bidders or their authorized representative.
- 20. Prices quoted for each item shall be inclusive of all i:e. taxes and duties, excise duty, service taxes, loading, unloading, transportation, insurance, watch and ward etc.
- 21. Advance payment /part payment will not be entertained before completion and handing over the work.
- 22. No claim can be made due to some unforeseen delay for release of payment.

- 23. Payment of bill will be made only after completion of the work in all respects i.e. commissioning, testing, inspection of work by the electrical inspector, execution of agreement between user authority and distribution Company authority before charging of sub station / Line and handed over the work to the distribution Company. In case of Area Illumination Work payment of bill will be made only after completion of the work in all respects i.e. commissioning, testing and handed over the work to the user authority.
- 24. All the transit risk shall be responsibility of the contractor.
- 25. Failure to complete the work in full within the stipulated period may lead to forfeiture of EMD and blacklisting of the contractor/firm.
- 26. The authorities are not bound to accept the lowest quoted rate.
- 27. Terms and conditions of this tender document cannot be negotiated for variations.
- 28. The authority reserves the right to reject any or all tender in whole or part without assigning any reason and can impose any other condition(s) as deemed proper before or in course of finalisation of the tender.
- 29. The approved tender may be cancelled by the authority any time during validity without assigning any reason thereof and no claim can lie against OPHW&C for such cancellation.
- 30. All materials required for the work should be approved brand of the concerned Distribution company / OPHWC as per the given specification and brand. Before take up the work
 - A.P.M (Electrical) shall verify/ certify the quality of materials.
- 31. Before installation of the transformer E&MR certificate shall be submitted along with CPRI certificate and guarantee certificate of the transformer shall be submitted.
- 32. LT bushing cover and tap changer shall be provided.
- 33. All the disputes shall be subject to Jurisdiction of Civil Courts situated at Bhubaneswar.

Signature & seal of the Bidder.

Sd/-Joint Manager (Elect.)

GENERAL BID FORM BID REFERENCE NO: - 08/ 2015-16/ELECT/ OPHWC

1.Name:
Full Address:
Fax No:
Telephone No:
E-mail address of the firm: 2.Legal Status of the firm:
3. Give the location and Address of your Office/ Branch office:
4. Kindly confirm by writing" Yes" of "No" only
[A] Have you enclosed the EMD? If yes, mention the amount and its identifying details.
[B] Have you enclosed the valid H.T./ M.V. License?
[C] Have you enclosed the VAT clearance certificate?
[D] Have you enclosed the PAN card?
[E] Have you enclosed the audited balance sheet?
[F] Copies of assessment return of sales tax and income tax of last three years.
[G] Have you enclosed all the documents and papers called for in this tender document?
Kindly enclose a list. (Use a separate sheet of paper)
[H] If the answer to [G] above is 'No', which of the Documents / papers called for in the tender document have not enclosed.
(Kindly enclose a list of such document/papers – Use separate Sheet of paper, if necessary)

Sd/-Joint Manager (Elect.)

Signature & seal of the Bidder.

OFFICE OF THE CHAIRMAN-CUM- MANAGING DIRECTOR.

ODISHA STATE POLICE HOUSING & WELFARE CORPORATION LTD., BHUBANESWAR. BILL OF QUANTITY TENDER NO.- 08/2015-16/ ELECT/OPHWC

NAME OF THE WORK :- EXECUTION OF EXTERNAL ELECTRIFICATION WORKS FOR POWER SUPPLY TO FIRE STATION BUILDING AT PURUNABARIPADA IN THE DIST. OF MAYURBHANJ.

Sl. No.	NAME OF THE PROJECT	SCOPE OF WORK	QUOTED RATE INCLUSIVE OF ALL IN FIGURE	QUOTED RATE INCLUSIVE OF ALL IN WORD.
		I. Construction of 3 ph 3 wire 11 KV line using 9 mtr. Long 300 KG PSC Pole with 55 sq. mm. OH Insulated Cable - 0.07 Km(Span Length-70 Mtr.)		
1	FIRE STATION BUILDING AT PURUNABARIPADA	II. Installation of 25 KVA(Star Rated) 11/0.4KV DP mounted sub station using 9 mtr. Long 300 KG PSC Pole along with Boundary Wall ,Fencing metal spreading & Grill gate - 1 No.		
	IN THE DIST. OF MAYURBHANJ.	DP mounted sub station using 9 mtr. Long 300 KG PSC Pole along with Boundary Wall ,Fencing metal spreading & Grill gate - 1 No.		
		IV.Diversion of LT Bare Conductor to 1x35+1x25 sq.mm AB cable0.15 KM		
		V.Interposing Pole-2 NOS.		

	VI.Guarding Provision on	
	Road Crossing.	

Seal & Signature of the Contractor

 $$\operatorname{Sd}/\operatorname{-}$$ Asst. Project Manager (Elect.)

Sd/I/C Elect. (Hqr.)

OFFICE OF THE CHAIRMAN-CUM- MANAGING DIRECTOR. ODISHA STATE POLICE HOUSING & WELFARE CORPORATION LTD., BHUBANESWAR.

BILL OF QUANTITY

TENDER NO.- 08/2015-16/ ELECT/OPHWC

NAME OF THE WORK: EXECUTION OF EXTERNAL ELECTRIFICATION WORKS FOR POWER SUPPLY TO FIRE STATION BUILDING AT PURUNABARIPADA IN THE DIST. OF MAYURBHANJ.

SCOPE [A]	I. Construction of 3 ph 3 wire 11 KV line using PSC Pole with 55 sq. mm. OH Insulated Cable Length-70 Mtr.)	e - 0.07 Km(Spar	n		
SCOPE [B]	II. Installation of 25 KVA(Star Rated) 11/0.4KV DP mounted sub station using 9 mtr. Long 300 KG PSC Pole along with Boundary Wall ,Fencing metal spreading & Grill gate - 1 No.				
SCOPE [C]	III. Construction of 3 ph 4 wire LT line using 8 mtr. Long 200 KG PSC Pole with (3x35+1x25) sq.mm AB cable0.08 KM				
SCOPE [D]	IV.Diversion of LT Bare Conductor to 1x35+1x25 sq.mm AB cable 0.15 KM				
SCOPE [E]	V.Interposing Pole-2 NOS.				
SCOPE [F]	VI.Guarding Provision on Road Crossing.				
Sl no	Description of Meterials	Unit	Qty		
1	9 Mtr long PSC Pole	No.	4		
2	8 Mtr long PSC Pole	No.	5		
3	11 KV V Cross Arm(10.2 K.g each)	No.	2		
4	Back Clamp for V 1.44 Kg each	No.	2		
5	11 KV F clamp	No.	2		
6	11 KV GI Pin	No.	6		
7	11 KV Pin Insulator	No.	6		
8	11 KV T&C Hardware (45KN)	Set	6		
9	11 KV T&C Disc Insulator	No.	6		
10	18mm GI HT Stay	Set	3		
11	7/10 G.I Stay Wire	Kg	45		
12	Clamp for HT stay	Set	3		

14 40mm earthing device No. 5 15 Earthing Coil (GI) No. 7 16 100 x 50x 6 mm MS Channel (9.2Kg/mtr) Kg 180 17 75x40x6mm MS channel; (6.8kg/mtr) Kg 120 18 50x50x5mm MS angle (4.45kg/mtr) Kg 80 19 16mm MS bolt & Nut with washer Kg 40 20 3 pole 11KV 200A AB switch Set 1 21 3 pole 11KV 200A HG fuse Set 1 22 6SWG GI wire Kg 150 23 No.8 Arm Binding wire/Tape Kg 150 24 11 KV Lightening areestor(5KA) No. 3 25 11 KV 55mm2 OH insulated cable Km 0.25 26 25 KVA 11/0.4KV Transformer (Star) No. 1 27 Materials for Machinary work for earth pit with charcoal, salt, etc. 5 28 LT distribution box for 25 KVA S/S No. 1 29 Boubdary wall, fencing metal spreading & grill, gate Ls 1	13	11 KV Stay Insulator	No.	3
16 100 x 50x 6 mm MS Channel (9.2 Kg/mtr) Kg 180 17 75x40x6mm MS channel; (6.8 kg/mtr) Kg 120 18 50x50x5mm MS angle (4.45 kg/mtr) Kg 80 19 16mm MS bolt & Nut with washer Kg 40 20 3 pole 11 KV 200A AB switch Set 1 21 3 pole 11 KV 200A HG fuse Set 1 22 6SWG GI wire Kg 150 23 No.8 Arm Binding wire/Tape Kg 1 24 11 KV Lightening areestor(5KA) No. 3 25 11 KV 55mm2 OH insulated cable Km 0.25 26 25 KVA 11/0.4KV Transformer (Star) No. 1 27 Materials for Machinary work for earth pit with charcoal,salt,etc. 5 28 LT distribution box for 25 KVA S/S No. 1 29 Boubdary wall, fencing metal spreading & grill, gate Ls 1 30 16mm GI LT stay No. 4 31 7/12 GI Stay wire Kg 40	14	40mm earthing device	No.	5
17 75x40x6mm MS channel; (6.8kg/mtr) Kg 120 18 50x50x5mm MS angle (4.45kg/mtr) Kg 80 19 16mm MS bolt & Nut with washer Kg 40 20 3 pole 11KV 200A AB switch Set 1 21 3 pole 11KV 200A HG fuse Set 1 22 6SWG GI wire Kg 150 23 No.8 Arm Binding wire/Tape Kg 150 24 11 KV Lightening areestor(5KA) No. 3 25 11 KV 55mm2 OH insulated cable Km 0.25 26 25 KVA 11/0.4KV Transformer (Star) No. 1 27 Materials for Machinary work for earth pit with charcoal,salt,etc. 5 5 28 LT distribution box for 25 KVA S/S No. 1 29 Boubdary wall, fencing metal spreading & grill, gate Ls 1 30 16mm GI LT stay No. 4 31 7/12 GI Stay wire Kg 40 32 LT Stay Insulator No. 4	15	Earthing Coil (GI)	No.	7
17 75A-0xtorian MS chainer, (0.0xg/mir) Kg 80 19 16mm MS bolt & Nut with washer Kg 40 20 3 pole 11KV 200A AB switch Set 1 21 3 pole 11KV 200A HG fuse Set 1 22 6SWG GI wire Kg 150 23 No.8 Arm Binding wire/Tape Kg 1 24 11 KV Lightening areestor(5KA) No. 3 25 11 KV 55mm2 OH insulated cable Km 0.25 26 25 KVA 11/0.4KV Transformer (Star) No. 1 27 Materials for Machinary work for earth pit with charcoal, salt, etc. No. 1 28 LT distribution box for 25 KVA S/S No. 1 29 Boubdary wall, fencing metal spreading & grill, gate Ls 1 30 16mm GI LT stay No. 4 31 7/12 GI Stay wire Kg 40 32 LT Stay Insulator No. 4 33 Clamp for LT stay No. 4 34	16	100 x 50x 6 mm MS Channel (9.2Kg/mtr)	Kg	180
19	17	75x40x6mm MS channel; (6.8kg/mtr)	Kg	120
20 3 pole 11KV 200A AB switch Set 1 21 3 pole 11KV 200A HG fuse Set 1 22 6SWG GI wire Kg 150 23 No.8 Arm Binding wire/Tape Kg 1 24 11 KV Lightening areestor(5KA) No. 3 25 11 KV 55mm2 OH insulated cable Km 0.25 26 25 KVA 11/0.4KV Transformer (Star) No. 1 27 Materials for Machinary work for earth pit with charcoal, salt, etc. No. 1 28 LT distribution box for 25 KVA S/S No. 1 29 Boubdary wall, fencing metal spreading & grill, gate Ls 1 30 16mm GI LT stay No. 4 31 7/12 GI Stay wire Kg 40 32 LT Stay Insulator No. 4 33 Clamp for LT stay No. 4 34 Suspention clamp with hook No. 5 35 Dead end clamp No. 4 36 3x35+1x2	18	50x50x5mm MS angle (4.45kg/mtr)	Kg	80
21 3 pole 11KV 200A HG fuse Set 1 22 6SWG GI wire Kg 150 23 No.8 Arm Binding wire/Tape Kg 1 24 11 KV Lightening areestor(5KA) No. 3 25 11 KV 55mm2 OH insulated cable Km 0.25 26 25 KVA 11/0.4KV Transformer (Star) No. 1 27 Materials for Machinary work for earth pit with charcoal, salt, etc. No. 1 28 LT distribution box for 25 KVA S/S No. 1 29 Boubdary wall, fencing metal spreading & grill, gate Ls 1 30 16mm GI LT stay No. 4 31 7/12 GI Stay wire Kg 40 32 LT Stay Insulator No. 4 33 Clamp for LT stay No. 4 34 Suspention clamp with hook No. 5 35 Dead end clamp No. 4 36 3x35+1x25sqmm AB cable Km 0.09 37 1x35+1x25s	19	16mm MS bolt & Nut with washer	Kg	40
22 6SWG GI wire Kg 150 23 No.8 Arm Binding wire/Tape Kg 1 24 11 KV Lightening areestor(5KA) No. 3 25 11 KV 55mm2 OH insulated cable Km 0.25 26 25 KVA 11/0.4KV Transformer (Star) No. 1 27 Materials for Machinary work for earth pit with charcoal,salt,etc. No. 1 28 LT distribution box for 25 KVA S/S No. 1 29 Boubdary wall, fencing metal spreading & grill, gate Ls 1 30 16mm GI LT stay No. 4 31 7/12 GI Stay wire Kg 40 32 LT Stay Insulator No. 4 33 Clamp for LT stay No. 4 34 Suspention clamp with hook No. 5 35 Dead end clamp No. 4 36 3x35+1x25sqmm AB cable Km 0.09 37 1x35+1x25sqmm AB Cable Km 0.17 38 Allm. Cable	20	3 pole 11KV 200A AB switch	Set	1
23 No.8 Arm Binding wire/Tape Kg 1 24 11 KV Lightening areestor(5KA) No. 3 25 11 KV 55mm2 OH insulated cable Km 0.25 26 25 KVA 11/0.4KV Transformer (Star) No. 1 27 Materials for Machinary work for earth pit with charcoal,salt,etc. No. 1 28 LT distribution box for 25 KVA S/S No. 1 29 Boubdary wall, fencing metal spreading & grill, gate Ls 1 30 16mm GI LT stay No. 4 31 7/12 GI Stay wire Kg 40 32 LT Stay Insulator No. 4 33 Clamp for LT stay No. 4 34 Suspention clamp with hook No. 5 35 Dead end clamp No. 4 36 3x35+1x25sqmm AB cable Km 0.09 37 1x35+1x25sqmm AB Cable Km 0.17 38 Allm. Cable sockets No. 24 39 35mm2	21	3 pole 11KV 200A HG fuse	Set	1
24 11 KV Lightening areestor(5KA) No. 3 25 11 KV 55mm2 OH insulated cable Km 0.25 26 25 KVA 11/0.4KV Transformer (Star) No. 1 27 Materials for Machinary work for earth pit with charcoal,salt,etc. No. 5 28 LT distribution box for 25 KVA S/S No. 1 29 Boubdary wall, fencing metal spreading & grill, gate Ls 1 30 16mm GI LT stay No. 4 31 7/12 GI Stay wire Kg 40 32 LT Stay Insulator No. 4 33 Clamp for LT stay No. 4 34 Suspention clamp with hook No. 5 35 Dead end clamp No. 4 36 3x35+1x25sqmm AB cable Km 0.09 37 1x35+1x25sqmm AB Cable Km 0.17 38 Allm. Cable sockets No. 24 39 35mm2 3.5core cable Mtr 20 40 Anti climbing device (Barbed wire) Kg 45 41 Danger bo	22	6SWG GI wire	Kg	150
25 11 KV 55mm2 OH insulated cable Km 0.25 26 25 KVA 11/0.4KV Transformer (Star) No. 1 27 Materials for Machinary work for earth pit with charcoal, salt, etc. No. 5 28 LT distribution box for 25 KVA S/S No. 1 29 Boubdary wall, fencing metal spreading & grill, gate Ls 1 30 16mm GI LT stay No. 4 31 7/12 GI Stay wire Kg 40 32 LT Stay Insulator No. 4 33 Clamp for LT stay No. 4 34 Suspention clamp with hook No. 5 35 Dead end clamp No. 4 36 3x35+1x25sqmm AB cable Km 0.09 37 1x35+1x25sqmm AB Cable Km 0.17 38 Allm. Cable sockets No. 24 39 35mm2 3.5core cable Mtr 20 40 Anti climbing device (Barbed wire) Kg 45 41 Dang	23	No.8 Arm Binding wire/Tape	Kg	1
26 25 KVA 11/0.4KV Transformer (Star) No. 1 27 Materials for Machinary work for earth pit with charcoal, salt, etc. No. 5 28 LT distribution box for 25 KVA S/S No. 1 29 Boubdary wall, fencing metal spreading & grill, gate Ls 1 30 16mm GI LT stay No. 4 31 7/12 GI Stay wire Kg 40 32 LT Stay Insulator No. 4 33 Clamp for LT stay No. 4 34 Suspention clamp with hook No. 5 35 Dead end clamp No. 4 36 3x35+1x25sqmm AB cable Km 0.09 37 1x35+1x25sqmm AB Cable Km 0.17 38 Allm. Cable sockets No. 24 39 35mm2 3.5core cable Mtr 20 40 Anti climbing device (Barbed wire) Kg 45 41 Danger board No. 9 42 Padding & concreting of	24	11 KV Lightening areestor(5KA)	No.	3
27 Materials for Machinary work for earth pit with charcoal, salt, etc. No. 5 28 LT distribution box for 25 KVA S/S No. 1 29 Boubdary wall, fencing metal spreading & grill, gate Ls 1 30 16mm GI LT stay No. 4 31 7/12 GI Stay wire Kg 40 32 LT Stay Insulator No. 4 33 Clamp for LT stay No. 4 34 Suspention clamp with hook No. 5 35 Dead end clamp No. 4 36 3x35+1x25sqmm AB cable Km 0.09 37 1x35+1x25sqmm AB Cable Km 0.17 38 Allm. Cable sockets No. 24 39 35mm2 3.5core cable Mtr 20 40 Anti climbing device (Barbed wire) Kg 45 41 Danger board No. 9 42 Padding & concreting of poles (Mass concreate) No. 9	25	11 KV 55mm2 OH insulated cable	Km	0.25
27 charcoal,salt,etc. 5 28 LT distribution box for 25 KVA S/S No. 1 29 Boubdary wall, fencing metal spreading & grill, gate Ls 1 30 16mm GI LT stay No. 4 31 7/12 GI Stay wire Kg 40 32 LT Stay Insulator No. 4 33 Clamp for LT stay No. 4 34 Suspention clamp with hook No. 5 35 Dead end clamp No. 4 36 3x35+1x25sqmm AB cable Km 0.09 37 1x35+1x25sqmm AB Cable Km 0.17 38 Allm. Cable sockets No. 24 39 35mm2 3.5core cable Mtr 20 40 Anti climbing device (Barbed wire) Kg 45 41 Danger board No. 9 42 Padding & concreting of poles (Mass concreate) No. 9	26	25 KVA 11/0.4KV Transformer (Star)	No.	1
29 Boubdary wall, fencing metal spreading & grill, gate Ls 1 30 16mm GI LT stay No. 4 31 7/12 GI Stay wire Kg 40 32 LT Stay Insulator No. 4 33 Clamp for LT stay No. 4 34 Suspention clamp with hook No. 5 35 Dead end clamp No. 4 36 3x35+1x25sqmm AB cable Km 0.09 37 1x35+1x25sqmm AB Cable Km 0.17 38 Allm. Cable sockets No. 24 39 35mm2 3.5core cable Mtr 20 40 Anti climbing device (Barbed wire) Kg 45 41 Danger board No. 9 42 Padding & concreting of poles (Mass concreate) No. 9	27	•	No.	5
29 gate 1 30 16mm GI LT stay No. 4 31 7/12 GI Stay wire Kg 40 32 LT Stay Insulator No. 4 33 Clamp for LT stay No. 4 34 Suspention clamp with hook No. 5 35 Dead end clamp No. 4 36 3x35+1x25sqmm AB cable Km 0.09 37 1x35+1x25sqmm AB Cable Km 0.17 38 Allm. Cable sockets No. 24 39 35mm2 3.5core cable Mtr 20 40 Anti climbing device (Barbed wire) Kg 45 41 Danger board No. 9 42 Padding & concreting of poles (Mass concreate) No. 9	28	LT distribution box for 25 KVA S/S	No.	1
31 7/12 GI Stay wire Kg 40 32 LT Stay Insulator No. 4 33 Clamp for LT stay No. 4 34 Suspention clamp with hook No. 5 35 Dead end clamp No. 4 36 3x35+1x25sqmm AB cable Km 0.09 37 1x35+1x25sqmm AB Cable Km 0.17 38 Allm. Cable sockets No. 24 39 35mm2 3.5core cable Mtr 20 40 Anti climbing device (Barbed wire) Kg 45 41 Danger board No. 9 42 Padding & concreting of poles (Mass concreate) No. 9	29		Ls	1
32 LT Stay Insulator No. 4 33 Clamp for LT stay No. 4 34 Suspention clamp with hook No. 5 35 Dead end clamp No. 4 36 3x35+1x25sqmm AB cable Km 0.09 37 1x35+1x25sqmm AB Cable Km 0.17 38 Allm. Cable sockets No. 24 39 35mm2 3.5core cable Mtr 20 40 Anti climbing device (Barbed wire) Kg 45 41 Danger board No. 9 42 Padding & concreting of poles (Mass concreate) No. 9	30	16mm GI LT stay	No.	4
33 Clamp for LT stay No. 4 34 Suspention clamp with hook No. 5 35 Dead end clamp No. 4 36 3x35+1x25sqmm AB cable Km 0.09 37 1x35+1x25sqmm AB Cable Km 0.17 38 Allm. Cable sockets No. 24 39 35mm2 3.5core cable Mtr 20 40 Anti climbing device (Barbed wire) Kg 45 41 Danger board No. 9 42 Padding & concreting of poles (Mass concreate) No. 9	31	7/12 GI Stay wire	Kg	40
34 Suspention clamp with hook No. 5 35 Dead end clamp No. 4 36 3x35+1x25sqmm AB cable Km 0.09 37 1x35+1x25sqmm AB Cable Km 0.17 38 Allm. Cable sockets No. 24 39 35mm2 3.5core cable Mtr 20 40 Anti climbing device (Barbed wire) Kg 45 41 Danger board No. 9 42 Padding & concreting of poles (Mass concreate) No. 9	32	LT Stay Insulator	No.	4
35 Dead end clamp No. 4 36 3x35+1x25sqmm AB cable Km 0.09 37 1x35+1x25sqmm AB Cable Km 0.17 38 Allm. Cable sockets No. 24 39 35mm2 3.5core cable Mtr 20 40 Anti climbing device (Barbed wire) Kg 45 41 Danger board No. 9 42 Padding & concreting of poles (Mass concreate) No. 9	33	Clamp for LT stay	No.	4
36 3x35+1x25sqmm AB cable Km 0.09 37 1x35+1x25sqmm AB Cable Km 0.17 38 Allm. Cable sockets No. 24 39 35mm2 3.5core cable Mtr 20 40 Anti climbing device (Barbed wire) Kg 45 41 Danger board No. 9 42 Padding & concreting of poles (Mass concreate) No. 9	34	Suspention clamp with hook	No.	5
371x35+1x25sqmm AB CableKm0.1738Allm. Cable socketsNo.243935mm2 3.5core cableMtr2040Anti climbing device (Barbed wire)Kg4541Danger boardNo.942Padding & concreting of poles (Mass concreate)No.9	35	Dead end clamp	No.	4
38 Allm. Cable sockets No. 24 39 35mm2 3.5core cable Mtr 20 40 Anti climbing device (Barbed wire) Kg 45 41 Danger board No. 9 42 Padding & concreting of poles (Mass concreate) No. 9	36	3x35+1x25sqmm AB cable	Km	0.09
39 35mm2 3.5core cable Mtr 20 40 Anti climbing device (Barbed wire) Kg 45 41 Danger board No. 9 42 Padding & concreting of poles (Mass concreate) No. 9	37	1x35+1x25sqmm AB Cable	Km	0.17
40 Anti climbing device (Barbed wire) Kg 45 41 Danger board No. 9 42 Padding & concreting of poles (Mass concreate) No. 9	38	Allm. Cable sockets	No.	24
41 Danger board No. 9 42 Padding & concreting of poles (Mass concreate) No. 9	39	35mm2 3.5core cable	Mtr	20
42 Padding & concreting of poles (Mass concreate) No. 9	40	Anti climbing device (Barbed wire)	Kg	45
State	41	Danger board	No.	9
43 Concreting of stay No. 7	42	Padding & concreting of poles (Mass concreate)	No.	9
	43	Concreting of stay	No.	7

Seal & Signature of the Contractor

Sd/-Asst. Project Manager (Elect.)