

**THE ODISHA STATE POLICE HOUSING & WELFARE CORPORATION LTD.  
JANPATH, BHUBANESWAR-22.**

**Tel: 0674 2541545; Fax: 0674 2541543; E-mail : [jmelectricalophwc@gmail.com](mailto:jmelectricalophwc@gmail.com)**

**Web: [ophwc.nic.in](http://ophwc.nic.in)**

**BID REFERENCE NO: - 2/ 2015-16/ELECT/ OPHWC**

**SCHEDULE OF TENDER FOR INTERNAL ELECTRIFICATION WORK OF SUB –  
JAIL,KARANJIA IN THE DIST. OF MAYURBHANJ.**

**SOLD TO : M/S \_\_\_\_\_**

\_\_\_\_\_

**MONEY**

**RECEIPT NO : \_\_\_\_\_**

**DATE : \_\_\_\_\_**

[SIGNATURE OF ISSUING OFFICER]

**THE ODISHA STATE POLICE HOUSING & WELFARE CORPORATION LTD.**  
**JANPATH, BHUBANESWAR-22.**  
**Tel: 0674 2541545; Fax: 0674 2541543; E-mail : jmelectricalophwc@gmail.com**  
**Web: ophwc.nic.in**

**TENDER CALL NOTICE**  
**BID REFERENCE NO: - 02/ 2015-16/ELECT/ OPHWC**

1. Sealed tender in the prescribed form with detailed Tender Call Notice for execution of external electrification, internal electrification, Area illumination and Generator wiring works of different projects are invited in single cover system from the enlisted H.T. / M.V.( M.V. Contractors only participated with internal electrification work, Area illumination works and Generator wiring) electrical contractors/Firms under O.S.P.H&W.C., Bhubaneswar including supply of materials as per the specification. Tender to be submitted separately for each project.

Sl.No	Name of the Project	Estimated Cost	EMD	Cost of tender paper including vat	Period of completion	Eligibility Range
1	Internal Electrification work of Regional Probation Office at Berhampur in the Dist. of Ganjam.	Rs. 2,67,135.00	Rs.2,671.00	Rs.2,100.00	45 days	Up to 10 lakh & above
2	External electrification work of Sub – Jail,Gunupur in the Dist. of Rayagada.	Rs. 4,77,641.00	Rs.4,776.00	Rs.2,100.00	45 days	Up to 10 lakh & above
3	Internal Electrification work of Sub – Jail,Karanja in the Dist. of Mayurbhanj.	Rs. 11,10,785.00	Rs.11,108.00	Rs.6,300.00	45 days	10 lakh above
4	Internal Electrification work of Sub – Jail,Nilagiri in the Dist. of Balasore.	Rs.8,54,095.00	Rs.8,541.00	Rs.4,200.00	45 days	Upto 10 lakh & above
5	Internal Electrification work of Sub – Jail,Kuchinda in the Dist. of Sambalpur.	Rs. 12,77,200.00	Rs.12,772.00	Rs.6,300.00	45 days	10 lakh above
6	Internal Electrification work of Sub –	Rs. 11,40,149.00	Rs.11,401.00	Rs.6,300.00	45 days	10 lakh above

	Jail,Banpur in the Dist. of Khurda.					
7	Generator Wiring at Dhenkanal Dist. Jail in the Dist. of Dhenkanal.	Rs. 3,75,700.00	Rs.3,757.00	Rs.2,100.00	45 days	Up to 10 lakh & above
8	Peripheral lighting system at outside the Jail Premises of Spl. Jail,Rourkela in the Dist. of Sundergarh.	Rs. 3,89,496.00	Rs.3,895.00	Rs.2,100.00	45 days	Up to 10 lakh & above
9	Area illumination Work at Circle Jail,Baripada in the Dist. of Mayurbhanj.	Rs. 15,06,750.00	Rs.15,068.00	Rs.6,300.00	45 days	10 lakh above
10	Restoration of External Electrification work and Area illumination work of Sub-Jail, Kodala damaged due to cuclonic storm ' Philin' 2013.	Rs.3,24,327.00	Rs.3,243.00	Rs.2,100.00	45 days	Up to 10 lakh & above
11	Area illumination Work of 100 Men Barrack Pre-Engineered Structure at Gazalbadi in the Dist. of Ganjam.	Rs. 4,31,832.00	Rs. 4,318.00	Rs.2,100.00	45 days	Up to 10 lakh & above
12	Area illumination work of Model Police Station at Digapahandi in the Dist. of Ganjam.	Rs. 3,77,006.00	Rs.3,770.00	Rs.2,100.00	45 days	Up to 10 lakh & above
13	External electrification work of BSF Camp at Gamphakonda in the dist. of Malkangiri.	Rs. 5,49,196.00	Rs.5,492.00	Rs.4,200.00	45 days	Up to 10 lakh & above
14	External electrification work of New Fire Station Building at Saranagada in the Dist. of Kandhamal.	Rs.5,76,770.00	Rs.5,768.00	Rs.4,200.00	45 days	Upto 10 lakh & above
15	Area illumination work of 100 Men Barrack at Reserve Office,Phulbani in the Dist. of kandhamal.	Rs. 2,78,585.00	Rs.2,786.00	Rs.2,100.00	45 days	Up to 10 lakh & above
16	External electrification work of 100 Men barrack at Reserve Office Phulbani in the	Rs. 6,50,236.00	Rs.6,502.00	Rs.4,200.00	45 days	Up to 10 lakh & above

	Dist. of Kandhamal.					
17	Addl. External electrification work of Gopalpur Out Post in the Dist. of Balasore .	Rs. 5,47,214.00	Rs.5,472.00	Rs.4,200.00	45 days	Up to 10 lakh & above

2. The tender document may be obtained on payment of the tender paper cost as mentioned in the Column – 5 of the above table [Non refundable] for each project between 10.00 A.M. to 05.00 P.M on each working day from the office of the undersigned at the Address given above of O.S.P.H.&WC at Bhubaneswar on or before Dt.30.05.2015 .Tender document can also be obtained through speed post by sending a self addressed envelope of size 35 cm x 25 cm along with a Demand Draft / Pay Order of the tender paper cost as mentioned in the Column – 5 of the above table and Rs. 200.00 ( Rupees two hundred only ) extra for purchased by post[Non refundable] for each project on any scheduled Bank, payable at Bhubaneswar, drawn in favour of the **“The Odisha State Police Housing &Welfare corporation Ltd.”**. However, such request must be received by the undersigned on or before the last date for issue of tender document. The O.S.P.H.&W.C. authorities shall not be responsible for postal or other delays. The tender document will also be available from the web site [www.ophwc.nic.in](http://www.ophwc.nic.in) and the same can be downloaded to be used for tender offer. However in case of downloaded tender documents an amount of the tender paper cost as mentioned in the Column – 5 of the above table [Non refundable] for each project in shape of Demand Draft / Pay Order drawn on any scheduled Bank, is payable at Bhubaneswar in favour of the **“The Odisha State Police Housing & Welfare Corporation Ltd.”** along with the tender , failing which tender shall be liable for rejection.
- 3.The bidders are requested to submit the receipt of showing cost of tender paper along with the attested copies of valid H.T./MV license from ELBO, Income tax return copy, PAN card, TIN No, up to date VAT clearance certificate along with bid documents otherwise the bid shall be liable for rejection.
4. **EMD** - The tender shall be accompanied with EMD as mentioned above in shape of D.D. / Pay order drawn on any Nationalized Bank in favour of the **“The Odisha State Police Housing &Welfare corporation Ltd.”**, failing which the tender shall be rejected.
5. Other details can be seen in the tender documents.
6. Bids submitted otherwise than in the manner prescribed in the tender document shall be rejected.

7. The bidding document should be super scribed “Tender for external electrification works, Tender No., Name of the Project etc.” / “Tender for internal electrification work, Tender No., Name of the Project etc.”/ “Tender for area illumination works, Tender No., Name of the Project etc.”/ “Tender for Generator wiring, Tender No., Name of the Project etc.”
8. The tender document is available from :10 AM on Dt.20.05.2015
9. Last date for issue of tender document is up to : 05.00 PM on Dt.30.05.2015
10. Last date for receipt of tender document is up to : 12.30 PM on Dt.05.06.2015
11. Date of opening of bid at : 03.30 PM on Dt.05.06.2015
12. The authority reserves the right to reject any or all the bids without assigning any reason thereof.
13. An affidavit is to be furnish by the bidder at the time of submitting bid document that he is not blacklisted / defaulter contractor or Firm etc. The authority reserves the right to reject any or all the bids without assigning any reason thereof and can impose any conditions as deemed proper before finalisation of tender.

Sd/-  
**Joint Manager (Elect.)**

**GENERAL CONDITION OF THE CONTRACT**  
**BID REFERENCE NO: - 02 / 2015-16 /ELECT/ OPHWC**

1. The tender document shall be accompany with the EMD as above only in shape of Demand Draft / Pay Order drawn on any Nationalized Bank payable at Bhubaneswar in favour of the “**The Odisha State Police Housing & Welfare Corporation Ltd.**” failing which the tender shall be rejected.
2. The bidders are requested to submit the receipt of showing cost of tender paper along with the attested copies of valid H.T. license from ELBO, Income tax return copy, PAN card, TIN No, upto date VAT clearance certificate and VAT registration certificate along with bid documents otherwise the bid shall be liable for rejection. The latest authenticated documentary proof shall be submitted. The proof submitted earlier in some other contest shall not be treated as valid and sufficient.
3. The bid must accompany proof of executing same nature of work as per eligibility criteria mentioned in tender call notice in Govt. / Govt. Undertaking. Departments. The copy of work order and completion certificates in support of credential should be enclosed with the tender otherwise the bid shall be rejected.
4. The bidding document should be super scribed “Tender for external electrification works, Tender No., Name of the Project etc.” / “Tender for internal electrification work, Tender No., Name of the Project etc.”/ “Tender for area illumination works, Tender No., Name of the Project etc.”/ “Tender for Generator wiring, Tender No., Name of the Project etc.”
5. The tenders (also called bids) not submitted in prescribed format or in prescribed manner, shall be rejected at the risk and responsibility of bidder.
6. All the information as called for in the tender document should be submitted truly, clearly, legible, transparently, unambiguously and without the use of abbreviations. It shall be submitted in English only.
7. All the crucial figures, like rates and amount should be written in figures followed by words in a bracket.
8. There shall be no over writing in the tender document and other papers submitted. All additions, alternations, deletions and cutting should be initialed with rubber-stamp (or seal) by the same person, who signs the tender document, failing which so, the tender may be rejected.

9. All the rates and amounts shall be quoted in Indian Rupee and shall be presumed to be in Indian Rupee only unless specifically permitted to be quoted otherwise in this tender document.
10. Each page of this tender document should be signed by the bidder with seal in token of having read, understood and accepted the terms and conditions of this contract.
11. Use separate piece of paper where the space provided in the formats in this tender document for submission of information is not sufficient.
12. The contractor shall stand for guarantee against defective materials / manufacturing defects(except lamp in case of Area illumination work) and workmanship for the work carried out by him for a period of **24** months from its commissioning /handing over & make good /repair/replace the faults during this period without any extra cost, failing which the same shall be got done at the risk and cost of the contractor. The work shall be supervised by the qualified supervisor from the contractor's side.
13. All information submitted or supplied in the formats of this tender document shall be presumed to be true to the best of knowledge of bidder.
14. The firms not having VAT Registration certificate shall not be eligible for submitting the bids. The blacklisted firms shall also not be eligible for participating in the bid.
15. The tenders/bids can be sent by post or courier as well. However, authorities shall not be responsible for postal or delays in receipt of bids.
16. If the last date for receipt of the tender/bid turns out to be a holiday, it will automatically be extended to next working day.
17. A bid submitted can not be withdrawn. The bidder or his authorized representative (one person only) will be allowed to be present at the time of opening of tenders. They will not participate in the discussions. Clarification sought, if any may be provided by them.
18. All or any of the tenders /bids submitted can be rejected without assigning any reason thereof. No claim, whatsoever, shall be admissible for the alleged loss/damages suffered by bidders on account of such rejections.
19. Bids shall be opened in the presence of the bidders or their authorized representative.
20. Prices quoted for each item shall be inclusive of all i:e. taxes and duties, excise duty, service taxes, loading, unloading, transportation, insurance, watch and ward etc.
21. Advance payment /part payment will not be entertained before completion and handing over the work.
22. No claim can be made due to some unforeseen delay for release of payment.

23. Payment of bill will be made only after completion of the work in all respects i.e. commissioning, testing, inspection of work by the electrical inspector, execution of agreement between user authority and distribution Company authority before charging of sub station / Line and handed over the work to the *distribution Company. In case of internal electrification, Area illumination and Generator wiring works payment of bill will be made only after completion of the work in all respects i.e. commissioning, testing and handed over the work to the user authority.*
24. All the transit risk shall be responsibility of the contractor.
25. Failure to complete the work in full within the stipulated period may lead to forfeiture of EMD and blacklisting of the contractor/firm.
26. The authorities are not bound to accept the lowest quoted rate.
27. Terms and conditions of this tender document can not be negotiated for variations.
28. The authority reserves the right to reject any or all tender in whole or part without assigning any reason and can impose any other condition(s) as deemed proper before or in course of finalisation of the tender.
29. The approved tender may be cancelled by the authority any time during validity without assigning any reason thereof and no claim can lie against OPHW&C for such cancellation.
30. All materials required for the work should be approved brand of the concerned Distribution company / as per the given specification and brand. Before take up the work A.P.M (Electrical) shall verify/ certify the quality of materials.
31. Before installation of the transformer E&MR certificate shall be submitted along with CPRI certificate and guarantee certificate of the transformer shall be submitted.
32. LT bushing cover and tap changer shall be provided.
33. All the disputes shall be subject to Jurisdiction of Civil Courts situated at Bhubaneswar.

**Signature & seal of the Bidder.**

**Sd/-  
Joint Manager (Elect.)**



**GENERAL BID FORM**  
**BID REFERENCE NO: - 02/ 2015-16/ELECT/ OPHWC**

**1.Name :**

**Full Address :**

**Fax No :**

**Telephone No :**

**E-mail address of the firm :**

**2.Legal Status of the firm :**

**3.Give the location and Address of your Office/ Branch office :**

**4.Kindly confirm by writing” Yes” of “No” only**

**[A] Have you enclosed the EMD? If yes, mention the amount and its identifying details.**

**[B] Have you enclosed the valid H.T./ M.V. License?**

**[C] Have you enclosed the VAT clearance certificate?**

**[D] Have you enclosed the PAN card?**

**[E] Have you enclosed the audited balance sheet?**

**[F] Copies of assessment return of sales tax and income tax of last three years.**

**[G] Have you enclosed all the documents and papers called for in this tender document?**

Kindly enclose a list. (Use a separate sheet of paper)

**[H] If the answer to [G] above is ‘No’, which of the Documents / papers called for in the tender document have not enclosed.**

(Kindly enclose a list of such document/papers – Use separate Sheet of paper, if necessary)

**Signature & seal of the Bidder.**

**Sd/-**  
**Joint Manager (Elect.)**

**OFFICE OF THE CHAIRMAN-CUM- MANAGING DIRECTOR.**

**ODISHA STATE POLICE HOUSING & WELFARE CORPORATION LTD., BHUBANESWAR.**

**BILL OF QUANTITY**

**TENDER NO.- 02/2015-16/ ELECT/OPHWC**

**NAME OF THE WORK :- EXECUTION OF INTERNAL ELECTRIFICATION WORKS OF SUB-JAIL,KARANJIA IN THE DIST. OF MAYURBHANJ.**

Sl. No.	SCOPE OF WORK	UNIT	RATE	QUOTED RATE INCLUSIVE OF ALL IN RS.	QUOTED AMOUNT INCLUSIVE OF ALL IN RS.
---------	---------------	------	------	-------------------------------------	---------------------------------------

**A ADMINSTRATIVE BUILDING**

Sl. No.	Description of work	Unit	Qty.	Rate	Total (Rs.) Amount
1	Semi Concealed wiring to <b>different points</b> with ISI marked 1.5 sq.mm( current carrying capacity min. 13 Amps.) 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor in 19 mm.dia. Extra super quality pvc / polythene pipe including supply & fixing of 6A, 250V. flush type switch mounted on 3 mm. thick bakelite cover on required size iron board duly painted & fixed inside/on the wall including supply of ceiling rose / angle holder etc. mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted or RJ box (ceiling ) fixed inside/on the wall with 1.0 sq.mm( current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge. [Make- (a)Switch, ceiling rose, angle holder, bell push switch, batten holder etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]				
(a)	Angle Holder Point	Nos	12		
(b)	Tube Light Point	Nos	17		

(c)	Siren Point	Nos	1		
(d)	Call Bell Point	Nos	1		
(e)	Bulk Head Point	Nos	1		
2	<p>Semi Concealed wiring to <b>Security light point</b> at 18' height from ground level/ top corners of the building with ISI marked 1.5 sq.mm,( current carrying capacity min. 13 Amps.) 650/1100 volt. pvc insulated single core (stranded ) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply &amp; fixing of 6 Amp. / 16 Amp. ,250V. flush type switch mounted on 3 mm.thick bakelite cover on required size iron board duly painted &amp; fixed at ground floor lobby inside/on the wall including supply of ceiling rose mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted fixed inside/on the wall with 1.0 sq.mm( current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in- charge. [Make- (a)Switch, ceiling rose etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	Nos	4		

<p><b>3</b></p>	<p>Semi Concealed wiring to <b>ceiling fan point</b> with ISI marked 1.5 sq.mm( current carrying capacity min. 13 Amps.) 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply &amp; fixing of 6A,250V. flush type switch with step type electronic regulator mounted on 3 mm. thick bakelite cover on required size iron board duly painted &amp; fixed inside/on the wall including supply of ceiling rose mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted or RJ box (ceiling ) fixed inside/on the wall with 1.0 sq.mm ( current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge. [Make- (a)Switch, ceiling rose etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	<p>Nos</p>	<p>10</p>		
<p><b>4</b></p>	<p>Semi Concealed wiring to <b>5 pin 6 Amp. socket point ( for wall fan)</b> with ISI marked 1.5 sq.mm 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply &amp; fixing of 5 pin 6 Amp. 250V. flush type socket &amp; switch mounted on 3 mm. thick bakelite cover on required size iron board / existing board duly painted &amp; fixed inside/on the wall with1.0 sq.mm 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge. [Make- (a)Switch,socket etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	<p>Nos</p>	<p>12</p>		

5	<p>Semi Concealed wiring to <b>power point [16 Amp.]</b> with ISI marked 6.0 sq.mm 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply &amp; fixing of 5 pin 16 Amp. 250V. flush type socket, switch, separate/combine) mounted on 3 mm.thick bakelite cover on required size iron board duly painted &amp; fixed inside/on the wall with 1.5 sq.mm 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge. [Make- (a)Switch ,socket etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	Nos	6		
6	<p>Semi Concealed wiring to <b>Computer point</b> with ISI marked 1.5sq.mm(3/20SWG) ( current carrying capacity min. 13 Amps.) 650/1100 volt pvc insulated single core unsheathed copper conductor in 19 mm. dia. super quality polythene/ pvc pipe including supply &amp; fixing of 3 nos of 6A, 250V. flush type socket&amp; 3 nos of switch mounted on 3 mm. thick bakelite cover on required size iron board /existing board duly painted &amp; fixed inside/on the wall with 1.0 sq.mm( current carrying capacity min. 7 Amps.) 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor as earth continuity copper wire including all connections as per instruction of Electrical Engineer-in- charge.All switches &amp; ceiling roses are ISI marked. [Make- (a)Switch,socket etc– Anchor Roma/legrand/ Havells Crabtree ,(b) Wires -Finolex/RR/Great White/HPL/HAVELLS , (c) all other materials ISI mark]</p>	Nos	4		

7	Semi Concealed wiring to <b>submain with two runs of ISI marked 1.5 sq.mm</b> , 650 / 1100 volt. Pvc insulated single core (stranded ) unsheathed copper conductor in 19 mm. dia. extra super quality pvc /polythene pipe with 1.0 sq.mm 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor as earth continuity wire from B.D.B. to S.B. including all connections as per instruction of Electrical Engineer-in- charge. [Make- (a)Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]	Mtr	180		
8	Semi Concealed wiring to <b>submain with two runs of ISI marked 6.0 sq.mm</b> , 650 /1100 volt. Pvc insulated single core (stranded ) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe with 1.5 sq.mm, 650 /1100 volt. Pvc insulated single core (stranded ) unsheathed copper conductor as earth continuity wire from B.D.B to Power Points & M.D.B, to B.D.B including all connections as per instruction of Electrical Engineer-in- charge[Make- (a)Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]	Mtr	135		
9	Concealed wiring to <b>submain</b> with four runs of ISI marked <b>16 sq.mm(7/17SWG)</b> , 650 /1100 volt. Pvc insulated single core unsheathed copper conductor in 19 mm. dia. super quality polythene pipe/pvc with 6.0 sq.mm pvc insulated earth continuity copper wire from 125 Amp. TPN MCCB to 63 Amp. TPN MCCB including all connections as per instruction of Electrical Engineer-in-charge.[Make- (a)Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]	Mtr	15		

10	Supply,laying & testing of <b>3.5 core,70 sq.mm PVC insulated , PVC sheathed aluminium armoured power cable</b> of 1100 volt grade through under ground / surface as per the site requirement including all accessories and connections with making good the damages caused and as per direction of Engineer-in-charge from 1st LT Pole to Main Panel Board..[Make- (a)Cable - Finolex/HAVELLS (c) all other materials ISI mark]	Mtr	70		
11	Supply and fixing of <b>8 way BDB consists of 1 No. 63Amp. DP MCB &amp; 6 Nos. of 32Amp. SPMCB</b> including all accessories and connections[Make-(a)MCB- Legrand/ Schnider/L&T/ ABB , (b) all other accessories ISI mark]	Set	3		
12	Supply and fixing of <b>63 AMP. FOUR POLE MCB – 01 NO wth 63 AMP. 415 VOLT CUT OUT – 03 NOS WITH COPPER BUS BAR &amp; INDICATOR ETC.</b> including all accessories and connections as per instruction of Electrical Engineer-in- charge. [Make- (a)MCB /MCCB - Legrand/ Schnider/L&T/ ABB, ( b)Volt meter, Ammeter-AE/CAPPA, (d) all other accessories ISI mark]	Set	1		
13	Supply and fixing of <b>125Amp. FOUR Pole change over panel Board</b> including all accessories and connections..[Make-(a)Change Over Switch - Simens/HPL/L&T/ABB, (b)Cut out- Anchor/BPL, ( c) Volt meter, Ammeter-AE/CAPPA, (d) all other accessories ISI mark]	Set	1		

14	<p>Supply and fixing of <b>125 AMP. TPMCCB [25 KA]</b> - 01 SET  with 100 AMP. 415 VOLT CUT OUT - 03 NOS WITHOUT METER SPACE OUT GOING - 100 AMP, 25 / 3 MM. COPPER BUS BAR - 04 NOS INSTRUMENTS 0 – 100 AMP. AMMETER WITH SELECTOR SWITCH - 01 SET 100 / 5 AMP. CT - 01 SET 0 – 500 VOLT VOLTMETER WITH SELECTORSWITCH - 01 SET INDICATING LAMP WITH CONTROLLING SWITCH - 01 SET etc. including all accessories and connections as per instruction of Electrical Engineer-in-charge.[Make-(a)Main Switch - Simens/HPL/L&amp;T/ABB, (b)Cut out- Anchor/BPL, © Volt meter, Ammeter-AE/CAPPA, (d) all other accessories ISI mark]</p>	Nos	1		
15	<p>Supply and fixing of <b>18 watt. holder type CFL lamp</b> for the installed angle holder .[Make-CG/Philips/Bajaj]</p>	Nos	12		
16	<p>Supply and fixing of <b>1 x 28 wt. T5 patty type tube light fittings</b> complete set with lamp , connecting wire and all accessories refer to catalouge No - MAKE – CROMPTON CODE – T5GP28EB/MAKE-PHILIPS MODEL-MIROLTA SLIM-CODE-TMS540/MAKE-HPL-CODE-HIBE10128including fixing and connections as per instruction of Electrical Engineer-in-charge..</p>	Nos	17		
17	<p>Supply and fixing of <b>1200 mm sweep AC ceiling fan</b> with star 5 rated connecting wire and all accessories refer to catalouge No - [MAKE- USHA ,MODEL-ATOM , /CROMPTON,MODEL-EMPOWER 50 /KHAITAN MODEL – NEWTECetc. including hanging and connections as per instruction of Electrical Engineer-in-charge.</p>	Nos	10		
18	<p>Supply and fixing of <b>electrically operated , double mounted type single phase 200/250 volt 6000 RPM 50 Hz , 3 mile range Siren</b> including supply of all materials and construction of siren shed &amp; siren base.</p>	Nos	1		



19	Supply and fixing of <b>Bulk Head fitting</b> including all accessories refer to catalouge No - MAKE – CROMPTON CODE – ICBH10/MAKE-PHILIPS/ CODE-NXC101/MAKE-HPL-CODE-HIBHO10008s and connections as per instruction of Electrical Engineer-in-charge.	Nos	1		
20	Supply & fixing of <b>4 x24 wt. T5 energy saving light fitting</b> with bulb,choke,cover, G.I. Bracket, Clamp & Nut Bolt connecting wire all accessories refer to catalouge No-CROMPTON CODE – T5SHO424 EB IP 65/MAKE-HPL-CODE-HPLT5STAL424 / PHILIPSincluding fixing and connections as per instruction of Electrical Engineer-in-charge.	Nos	4		
21	Supply and fixing of <b>calling bell (ding dong)</b> including all accessories and connections as per instruction of Electrical Engineer-in-charge.	Nos	1		
22	Supply and installation of <b>1.5Tr. Split type Air Conditioner</b> ( 5 Star) of reputed brand with supply and fixing of 5 KVA ,130-280 Volt voltage range wall/floor mounted stabiliser including all accessories,fastner angle copper piping up to 15ft & connections as per instruction of Electrical Engineer-in-charge MAKE of A.C. – CARRIER KURVE, /MAKE – BLUE STAR, CODE-3HW18TB , MAKE OF STABILIZER-JYOTI/SHAKTI/ AUTOTEK	Nos	1		
23	Inverter Wiring including all accessories and connection ( subject to actual)	LS	LS		
24	Supply and fixing of 800 VA Digital Home UPS including strully stand , all accessories and connections .( Make- Microtek/ Genus)	No	1		
25	Supply and fixing of 150 AH Tall Tubular Battery with ( 3+1) yr. warranty including all accessories and connections .( Make- Microtek/ Genus)	No	1		

26	Supply and fixing of <b>earthing</b> including 38 mm. dia. 3 mtr. long G.I pipe[Heavy Duty].The pipe shall have 12 mm. dia. perforated holes at 15 cm centre to centre up to 2.5 mtrs height from the bottom and fitted with a 38 mm. dia. G.I flange at the top with provision of holes for making connection of earth continuity wire,complete with masonry work for earth pit chamber.The earth pit shall have an alternative layer of 105 mm. charcoal and 50 mm. salt up to a depth of 465 mm. and rest shall be filled with charcoal to a further depth of 2035 mm. The earth pit should maintain a minium clearance 1.5 mtr. from building & 2 mtr. in between two earth pit and as per instruction of Electrical Engineer-in-charge.	Nos	2		
27	Supply and fixing of <b>sub earthing</b> with No-8 bare copper wire as earth Continuity wire from Main pannel board to earth electrode inside the wall/ground to a depth of 50 mm. and make good of the wall/ground including all connections.	Rft	200		
			<b>SUB TOTAL-A</b>		
<b>B</b>	<b>DINING HALL</b>				

-

<p><b>1</b></p>	<p>Semi Concealed wiring to <b>different points</b> with ISI marked 1.5 sq.mm( current carrying capacity min. 13 Amps.) 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor in 19 mm.dia. Extra super quality pvc / polythene pipe including supply &amp; fixing of 6A, 250V. flush type switch mounted on 3 mm. thick bakelite cover on required size iron board duly painted &amp; fixed inside/on the wall including supply of ceiling rose / angle holder etc. mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted or RJ box (ceiling ) fixed inside/on the wall with 1.0 sq.mm( current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge. [Make- (a)Switch, ceiling rose, angle holder, bell push switch, batten holder etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>				
<p><b>a</b></p>	<p>Angle Holder Point</p>	<p>Nos</p>	<p>4</p>		
<p><b>b</b></p>	<p>Tube Light Point</p>	<p>Nos</p>	<p>8</p>		

2	<p>Semi Concealed wiring to <b>Security light point</b> at 18' height from ground level/ top corners of the building with ISI marked 1.5 sq.mm,( current carrying capacity min. 13 Amps.) 650/1100 volt. pvc insulated single core (stranded ) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply &amp; fixing of 6 Amp. / 16 Amp. ,250V. flush type switch mounted on 3 mm.thick bakelite cover on required size iron board duly painted &amp; fixed at ground floor lobby inside/on the wall including supply of ceiling rose mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted fixed inside/on the wall with 1.0 sq.mm( current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in- charge. [Make- (a)Switch, ceiling rose etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	Nos	2		
---	---	-----	---	--	--

<p><b>3</b></p>	<p>Semi Concealed wiring to <b>ceiling fan point</b> with ISI marked 1.5 sq.mm( current carrying capacity min. 13 Amps.) 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply &amp; fixing of 6A,250V. flush type switch with step type electronic regulator mounted on 3 mm. thick bakelite cover on required size iron board duly painted &amp; fixed inside/on the wall including supply of ceiling rose mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted or RJ box (ceiling ) fixed inside/on the wall with 1.0 sq.mm ( current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge. [Make- (a)Switch, ceiling rose etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]( * 2 mtr extension pipe required )</p>	<p>Nos</p>	<p>8</p>		
<p><b>4</b></p>	<p>Supply,laying &amp; testing of <b>3.5 core,50 sq.mm PVC insulated , PVC sheathed aluminium armoured power cable</b> of 1100 volt grade through under ground / surface as per the site requirement including all accessories and connections with making good the damages caused and as per direction of Engineer-in-charge from Panel Board at Main Gate to Panel Board at Dining Hall..[Make- (a)Cable - Finolex/HAVELLS (c) all other materials ISI mark]</p>	<p>Mtr</p>	<p>45</p>		

5	Semi Concealed wiring to <b>submain with two runs of ISI marked 1.5 sq.mm</b> , 650 / 1100 volt. Pvc insulated single core (stranded ) unsheathed copper conductor in 19 mm. dia. extra super quality pvc /polythene pipe with 1.0 sq.mm 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor as earth continuity wire B.D.B. to S.B. including all connections as per instruction of Electrical Engineer-in- charge. [Make- (a)Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]	Mtr	20		
6	Semi Concealed wiring to <b>submain with two runs of ISI marked 6.0 sq.mm</b> , 650 /1100 volt. Pvc insulated single core (stranded ) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe with 1.5 sq.mm, 650 /1100 volt. Pvc insulated single core (stranded ) unsheathed copper conductor as earth continuity wire from M.D.B, to B.D.B including all connections as per instruction of Electrical Engineer-in-charge[Make- (a)Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]	Mtr	15		
7	Supply and fixing of <b>18 watt. holder type CFL lamp</b> for the installed angle holder .[Make-CG/Philips/Bajaj]	Nos	4		
8	Supply and fixing of <b>1200 mm sweep AC ceiling fan</b> with star 5 rated connecting wire and all accessories refer to catalouge No - [MAKE- USHA ,MODEL-ATOM , /CROMPTON,MODEL-EMPOWER 50 /KHAITAN MODEL – NEWTECetc. including hanging and connections as per instruction of Electrical Engineer-in-charge.	Nos	8		

9	Supply and fixing of <b>1 x 28 wt. T5 patty type tube light fittings</b> complete set with lamp , connecting wire and all accessories refer to catalouge No - MAKE – CROMPTON CODE – T5GP28EB/MAKE-PHILIPS MODEL-MIROLTA SLIM-CODE-TMS540/MAKE-HPL-CODE-HIBE10128including fixing and connections as per instruction of Electrical Engineer-in-charge..	Nos	8		
10	Supply & fixing of <b>4 x24 wt. T5 energy saving light fitting</b> with bulb,choke,cover, G.I. Bracket, Clamp & Nut Bolt connecting wire all accessories refer to catalouge No-CROMPTON CODE – T5SHO424 EB IP 65/MAKE-HPL-CODE-HPLT5STAL424 / PHILIPSincluding fixing and connections as per instruction of Electrical Engineer-in-charge.	Nos	2		
11	Supply and fixing of <b>8 way BDB consists of 1 No. 63Amp. DP MCB &amp; 6 Nos. of 32Amp. SPMCB</b> including all accessories and connections[Make-(a)MCB- Legrand/ Schnider/L&T/ ABB , (b) all other accessories ISI mark]	Set	1		
12	Supply and fixing of <b>125 AMP. TPMCCB [25 KA]</b> - 01 SET with 100 AMP. 415 VOLT CUT OUT - 03 NOS WITHOUT METER SPACE OUT GOING - 100 AMP, 25 / 3 MM. COPPER BUS BAR - 04 NOS INSTRUMENTS 0 – 100 AMP. AMMETER WITH SELECTOR SWITCH - 01 SET 100 / 5 AMP. CT - 01 SET 0 – 500 VOLT VOLTMETER WITH SELECTORSWITCH - 01 SET INDICATING LAMP WITH CONTROLLING SWITCH - 01 SET etc. including all accessories and connections as per instruction of Electrical Engineer-in-charge.[Make-(a)Main Switch - Simens/HPL/L&T/ABB, (b)Cut out- Anchor/BPL, © Volt meter, Ammeter- AE/CAPPA, (d) all other accessories ISI mark]	Nos	1		

13	Supply and fixing of <b>earthing</b> including 38 mm. dia. 3 mtr. long G.I pipe[Heavy Duty].The pipe shall have 12 mm. dia. perforated holes at 15 cm centre to centre up to 2.5 mtrs height from the bottom and fitted with a 38 mm. dia. G.I flange at the top with provision of holes for making connection of earth continuity wire,complete with masonry work for earth pit chamber.The earth pit shall have an alternative layer of 105 mm. charcoal and 50 mm. salt up to a depth of 465 mm. and rest shall be filled with charcoal to a further depth of 2035 mm. The earth pit should maintain a minium clearance 1.5 mtr. from building & 2 mtr. in between two earth pit and as per instruction of Electrical Engineer-in-charge.	Nos	2		
14	Supply and fixing of <b>sub earthing</b> with No-8 bare copper wire as earth Continuity wire from Main pannel board to earth electrode inside the wall/ground to a depth of 50 mm. and make good of the wall/ground including all connections.	Rft	100		

**SUB TOTAL-B**

-

C	<b>HOSPITAL BUILDING</b>
---	--------------------------



1	<p>Semi Concealed wiring to <b>different points</b> with ISI marked 1.5 sq.mm( current carrying capacity min. 13 Amps.) 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor in 19 mm.dia. Extra super quality pvc / polythene pipe including supply &amp; fixing of 6A, 250V. flush type switch mounted on 3 mm. thick bakelite cover on required size iron board duly painted &amp; fixed inside/on the wall including supply of ceiling rose / angle holder etc. mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted or RJ box (ceiling ) fixed inside/on the wall with 1.0 sq.mm( current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge. [Make- (a)Switch, ceiling rose, angle holder, bell push switch, batten holder etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>				
(a)	Angle Holder Point	Nos	3		
(b)	Tube Light Point	Nos	6		

2	<p>Semi Concealed wiring to <b>Security light point</b> at 18' height from ground level/ top corners of the building with ISI marked 1.5 sq.mm,( current carrying capacity min. 13 Amps.) 650/1100 volt. pvc insulated single core (stranded ) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply &amp; fixing of 6 Amp. / 16 Amp. ,250V. flush type switch mounted on 3 mm.thick bakelite cover on required size iron board duly painted &amp; fixed at ground floor lobby inside/on the wall including supply of ceiling rose mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted fixed inside/on the wall with 1.0 sq.mm( current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in- charge. [Make- (a)Switch, ceiling rose etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	Nos	2		
---	---	-----	---	--	--

<p><b>3</b></p>	<p>Semi Concealed wiring to <b>ceiling fan point</b> with ISI marked 1.5 sq.mm( current carrying capacity min. 13 Amps.) 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply &amp; fixing of 6A,250V. flush type switch with step type electronic regulator mounted on 3 mm. thick bakelite cover on required size iron board duly painted &amp; fixed inside/on the wall including supply of ceiling rose mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted or RJ box (ceiling ) fixed inside/on the wall with 1.0 sq.mm ( current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge. [Make- (a)Switch, ceiling rose etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]( * 2 mtr extension pipe required )</p>	<p>Nos</p>	<p>3</p>		
<p><b>4</b></p>	<p>Semi Concealed wiring to <b>5 pin 6 Amp. socket point ( for wall fan)</b> with ISI marked 1.5 sq.mm 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply &amp; fixing of 5 pin 6 Amp. 250V. flush type socket &amp; switch mounted on 3 mm. thick bakelite cover on required size iron board / existing board duly painted &amp; fixed inside/on the wall with1.0 sq.mm 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge. [Make- (a)Switch ,socket etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	<p>Nos</p>	<p>3</p>		

5	<p>Semi Concealed wiring to <b>power point [16 Amp.]</b> with ISI marked 6.0 sq.mm 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply &amp; fixing of 5 pin 16 Amp. 250V. flush type socket, switch, separate/combine) mounted on 3 mm.thick bakelite cover on required size iron board duly painted &amp; fixed inside/on the wall with 1.5 sq.mm 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge. [Make- (a)Switch , socket etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	Nos	3		
6	<p>Semi Concealed wiring to <b>submain with two runs of ISI marked 1.5 sq.mm</b> , 650 / 1100 volt. Pvc insulated single core (stranded ) unsheathed copper conductor in 19 mm. dia. extra super quality pvc /polythene pipe with1.0 sq.mm 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor as earth continuity wire B.D.B. to S.B. including all connections as per instruction of Electrical Engineer-in- charge. [Make- (a)Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	Mtr	20		
7	<p>Semi Concealed wiring to <b>submain with two runs of ISI marked 6.0 sq.mm</b>, 650 /1100 volt. Pvc insulated single core (stranded ) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe with 1.5 sq.mm, 650 /1100 volt. Pvc insulated single core (stranded ) unsheathed copper conductor as earth continuity wire from B.D.B to Power Points &amp; M.D.B, to B.D.B including all connections as per instruction of Electrical Engineer-in- charge[Make- (a)Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	Mtr	110		

8	Supply, laying & testing of <b>3.5 core, 35 sq.mm PVC insulated , PVC sheathed aluminium armoured power cable</b> of 1100 volt grade through under ground / surface as per the site requirement including all accessories and connections with making good the damages caused and as per direction of Engineer-in-charge from Ward No-3 ,4,5 to Hospital Building [Make- (a) Cable- Finolex/ Havells , (b) all other materials ISI mark]	Mtr	25		
9	Supply and fixing of <b>8 way BDB consists of 1 No. 63Amp. DP MCB &amp; 6 Nos. of 32Amp. SPMCB</b> including all accessories and connections [Make-(a) MCB- Legrand/ Schnider/L&T/ ABB , (b) all other accessories ISI mark]	Set	2		
10	Supply and fixing of <b>63 AMP. FOUR POLE MCB – 01 NO wth 63 AMP. 415 VOLT CUT OUT – 03 NOS WITH COPPER BUS BAR &amp; INDICATOR ETC.</b> including all accessories and connections as per instruction of Electrical Engineer-in- charge. [Make- (a) MCB /MCCB - Legrand/ Schnider/L&T/ ABB, ( b) Volt meter, Ammeter-AE/CAPPA, (d) all other accessories ISI mark]	Set	1		
11	Supply and fixing of <b>18 watt. holder type CFL lamp</b> for the installed angle holder .[Make-CG/Philips/Bajaj]	Nos	3		
12	Supply and fixing of <b>1 x 28 wt. T5 patty type tube light fittings</b> complete set with lamp , connecting wire and all accessories refer to catalouge No - MAKE – CROMPTON CODE – T5GP28EB/MAKE-PHILIPS MODEL-MIROLTA SLIM-CODE-TMS540/MAKE-HPL-CODE-HIBE10128 including fixing and connections as per instruction of Electrical Engineer-in-charge..	Nos	6		

13	Supply and fixing of <b>1200 mm sweep AC ceiling fan</b> with star 5 rated connecting wire and all accessories refer to catalouge No - [MAKE- USHA ,MODEL-ATOM , /CROMPTON,MODEL-EMPOWER 50 /KHAITAN MODEL – NEWTECetc. including hanging and connections as per instruction of Electrical Engineer-in-charge.	Nos	3		
14	Supply & fixing of <b>4 x24 wt. T5 energy saving light fitting</b> with bulb,choke,cover, G.I. Bracket, Clamp & Nut Bolt connecting wire all accessories refer to catalouge No- CROMPTON CODE – T5SHO424 EB IP 65/MAKE-HPL-CODE-HPLT5STAL424 / PHILIPSincluding fixing and connections as per instruction of Electrical Engineer-in-charge.	Nos	2		
15	Supply and fixing of <b>earthing</b> including 38 mm. dia. 3 mtr. long G.I pipe[Heavy Duty].The pipe shall have 12 mm. dia. perforated holes at 15 cm centre to centre up to 2.5 mtrs height from the bottom and fitted with a 38 mm. dia. G.I flange at the top with provision of holes for making connection of earth continuity wire,complete with masonry work for earth pit chamber.The earth pit shall have an alternative layer of 105 mm. charcoal and 50 mm. salt up to a depth of 465 mm. and rest shall be filled with charcoal to a further depth of 2035 mm. The earth pit should maintain a minium clearance 1.5 mtr. from building & 2 mtr. in between two earth pit and as per instruction of Electrical Engineer-in-charge.	Nos	2		
16	Supply and fixing of <b>sub earthing</b> with No-8 bare copper wire as earth Continuity wire from Main pannel board to earth electrode inside the wall/ground to a depth of 50 mm. and make good of the wall/ground including all connections.	Rft	80		
<b>SUB TOTAL-C</b>					
<b>D</b>	<b>WARD NO-3 &amp; 4</b>				-

1	<p>Semi Concealed wiring to <b>different points</b> with ISI marked 1.5 sq.mm( current carrying capacity min. 13 Amps.) 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor in 19 mm.dia. Extra super quality pvc / polythene pipe including supply &amp; fixing of 6A, 250V. flush type switch mounted on 3 mm. thick bakelite cover on required size iron board duly painted &amp; fixed inside/on the wall including supply of ceiling rose / angle holder etc. mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted or RJ box (ceiling ) fixed inside/on the wall with 1.0 sq.mm( current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge. [Make- (a)Switch, socket etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>				
<b>a</b>	Television Point (with 2 Nos 6 Amp. Switch & 2 Nos 6 Amp. Socket)	Nos	2	840.00	1680.00

2	<p>Semi Concealed wiring to <b>Security light point</b> at 18' height from ground level/ top corners of the building with ISI marked 1.5 sq.mm,( current carrying capacity min. 13 Amps.) 650/1100 volt. pvc insulated single core (stranded ) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply &amp; fixing of 6 Amp. / 16 Amp. ,250V. flush type switch mounted on 3 mm.thick bakelite cover on required size iron board duly painted &amp; fixed at ground floor lobby inside/on the wall including supply of ceiling rose mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted fixed inside/on the wall with 1.0 sq.mm( current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in- charge. [Make- (a)Switch, ceiling rose etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	Nos	1		
3	<p>Supply,laying &amp; testing of <b>3.5 core,35 sq.mm PVC insulated , PVC sheathed aluminium armoured power cable</b> of 1100 volt grade through under ground / surface as per the site requirement including all accessories and connections with making good the damages caused and as per direction of Engineer-in-charge from Dining Hall to Ward No-3 &amp;4 [Make- (a) Cable- Finolex/ Havells , (b) all other materials ISI mark]</p>	Mtr	25		
4	<p>Supply and fixing of <b>18 watt. holder type CFL lamp</b> for the installed angle holder .[Make-CG/Philips/Bajaj]</p>	Nos	16		



5	Supply and fixing of <b>1 x 28 wt. T5 patty type tube light fittings</b> complete set with lamp , connecting wire and all accessories refer to catalouge No - MAKE – CROMPTON CODE – T5GP28EB/MAKE-PHILIPS MODEL-MIROLTA SLIM-CODE-TMS540/MAKE-HPL-CODE-HIBE10128including fixing and connections as per instruction of Electrical Engineer-in-charge..	Nos	10		
6	Supply and fixing of <b>1200 mm sweep AC ceiling fan</b> with star 5 rated connecting wire and all accessories refer to catalouge No - [MAKE- USHA ,MODEL-ATOM , /CROMPTON,MODEL-EMPOWER 50 /KHAITAN MODEL – NEWTECetc. including hanging and connections as per instruction of Electrical Engineer-in-charge.	Nos	6		
7	Supply & fixing of 4 x24 wt. T5 energy saving light fitting with bulb,choke,cover, G.I. Bracket, Clamp & Nut Bolt connecting wire all accessories refer to catalouge No- CROMPTON CODE – T5SHO424 EB IP 65/MAKE-HPL-CODE-HPLT5STAL424 / PHILIPSincluding fixing and connections as per instruction of Electrical Engineer-in-charge.	Nos	1		
				<b>SUB TOTAL-D</b>	<b>1,680.00</b>
<b>E</b>	<b>WARD NO -5</b>				

1	Semi Concealed wiring to <b>different points</b> with ISI marked 1.5 sq.mm( current carrying capacity min. 13 Amps.) 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor in 19 mm.dia. Extra super quality pvc / polythene pipe including supply & fixing of 6A, 250V. flush type switch mounted on 3 mm. thick bakelite cover on required size iron board duly painted & fixed inside/on the wall including supply of ceiling rose / angle holder etc. mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted or RJ box (ceiling ) fixed inside/on the wall with 1.0 sq.mm( current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge. [Make- (a)Switch, ceiling rose, angle holder, bell push switch, batten holder etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]				
(a)	Angle Holder Point	Nos	2		
(b)	Tube Light Point	Nos	4		
(c)	Television Point (with 2 Nos 6 Amp. Switch & 2 Nos 6 Amp. Socket)	Nos	1		

2	<p>Semi Concealed wiring to <b>Security light point</b> at 18' height from ground level/ top corners of the building with ISI marked 1.5 sq.mm,( current carrying capacity min. 13 Amps.) 650/1100 volt. pvc insulated single core (stranded ) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply &amp; fixing of 6 Amp. / 16 Amp. ,250V. flush type switch mounted on 3 mm.thick bakelite cover on required size iron board duly painted &amp; fixed at ground floor lobby inside/on the wall including supply of ceiling rose mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted fixed inside/on the wall with 1.0 sq.mm( current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in- charge. [Make- (a)Switch, ceiling rose etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	Nos	1		
---	---	-----	---	--	--

3	<p>Semi Concealed wiring to <b>ceiling fan point</b> with ISI marked 1.5 sq.mm( current carrying capacity min. 13 Amps.) 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply &amp; fixing of 6A,250V. flush type switch with step type electronic regulator mounted on 3 mm. thick bakelite cover on required size iron board duly painted &amp; fixed inside/on the wall including supply of ceiling rose mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted or RJ box (ceiling ) fixed inside/on the wall with 1.0 sq.mm ( current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge. [Make- (a)Switch, ceiling rose etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	Nos	6		
4	<p>Semi Concealed wiring to <b>submain with two runs of ISI marked 1.5 sq.mm</b> , 650 / 1100 volt. Pvc insulated single core (stranded ) unsheathed copper conductor in 19 mm. dia. extra super quality pvc /polythene pipe with 1.0 sq.mm 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor as earth continuity wire B.D.B. to S.B. including all connections as per instruction of Electrical Engineer-in- charge. [Make- (a)Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	Mtr	20		
5	<p>Supply,laying &amp; testing of <b>3.5 core,35 sq.mm PVC insulated , PVC sheathed aluminium armoured power cable</b> of 1100 volt grade through under ground / surface as per the site requirement including all accessories and connections with making good the damages caused and as per direction of Engineer-in-charge from Dining Hall to Ward No-5 [Make- (a) Cable- Finolex/ Havells , (b) all other materials ISI mark]</p>	Mtr	20		

<b>6</b>	Supply and fixing of <b>16 way BDB consists of 1 No. 63Amp. 4P MCB &amp; 12 Nos. of 32Amp. SPMCB</b> including all accessories and connections[Make-(a)MCB- Legrand/ Schnider/L&T/ ABB , (b) all other accessories ISI mark]	Set	1		
<b>7</b>	Supply and fixing of <b>18 watt. holder type CFL lamp</b> for the installed angle holder .[Make-CG/Philips/Bajaj]	Nos	2		
<b>8</b>	Supply and fixing of <b>1 x 28 wt. T5 patty type tube light fittings</b> complete set with lamp , connecting wire and all accessories refer to catalouge No - MAKE – CROMPTON CODE – T5GP28EB/MAKE-PHILIPS MODEL-MIROLTA SLIM-CODE-TMS540/MAKE-HPL-CODE-HIBE10128including fixing and connections as per instruction of Electrical Engineer-in-charge..	Nos	4		
<b>9</b>	Supply and fixing of <b>1200 mm sweep AC ceiling fan</b> with star 5 rated connecting wire and all accessories refer to catalouge No - [MAKE- USHA ,MODEL-ATOM , /CROMPTON,MODEL-EMPOWER 50 /KHAITAN MODEL – NEWTECetc. including hanging and connections as per instruction of Electrical Engineer-in-charge.	Nos	6		
<b>10</b>	Supply & fixing of <b>4 x24 wt. T5 energy saving light fitting</b> with bulb,choke,cover, G.I. Bracket, Clamp & Nut Bolt connecting wire all accessories refer to catalouge No- CROMPTON CODE – T5SHO424 EB IP 65/MAKE-HPL-CODE-HPLT5STAL424 / PHILIPSincluding fixing and connections as per instruction of Electrical Engineer-in-charge.	Nos	1		

**SUB TOTAL-E**

-

<b>F</b>	<b>FEMALE WARD &amp; WARD NO-I</b>				
----------	------------------------------------	--	--	--	--

1	<p>Semi Concealed wiring to <b>different points</b> with ISI marked 1.5 sq.mm( current carrying capacity min. 13 Amps.) 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor in 19 mm.dia. Extra super quality pvc / polythene pipe including supply &amp; fixing of 6A, 250V. flush type switch mounted on 3 mm. thick bakelite cover on required size iron board duly painted &amp; fixed inside/on the wall including supply of ceiling rose / angle holder etc. mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted or RJ box (ceiling ) fixed inside/on the wall with 1.0 sq.mm( current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge. [Make- (a)Switch, socket, ceiling rose, angle holder, bell push switch, batten holder etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>				
(a)	Angle Holder Point	Nos	18		
(b)	Tube Light Point	Nos	29		
(c)	Television Point (with 2 Nos 6 Amp. Switch & 2 Nos 6 Amp. Socket)	Nos	2		

2	<p>Semi Concealed wiring to <b>ceiling fan point</b> with ISI marked 1.5 sq.mm( current carrying capacity min. 13 Amps.) 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply &amp; fixing of 6A,250V. flush type switch with step type electronic regulator mounted on 3 mm. thick bakelite cover on required size iron board duly painted &amp; fixed inside/on the wall including supply of ceiling rose mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted or RJ box (ceiling ) fixed inside/on the wall with 1.0 sq.mm ( current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge. [Make- (a)Switch, ceiling rose etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	Nos	16		
3	<p>Semi Concealed wiring to <b>exhaust fan point</b> with ISI marked 1.5 sq.mm( current carrying capacity min. 13 Amps.) 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor in 19 mm. dia. extra super quality pvc /polythene pipe including supply &amp; fixing of 6A,250V. flush type switch mounted on 3 mm. thick bakelite cover on required size iron board duly painted &amp; fixed inside/on the wall including supply of ceiling rose mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted or RJ box (ceiling ) fixed inside/on the wall with 1.0 sq.mm( current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge.[Make- (a)Switch, ceiling rose etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	Nos	1		

4	<p>Semi Concealed wiring to <b>5 pin 6 Amp. socket point</b> with ISI marked 1.5 sq.mm 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply &amp; fixing of 5 pin 6 Amp. 250V. flush type socket &amp; switch mounted on 3 mm. thick bakelite cover on required size iron board / existing board duly painted &amp; fixed inside/on the wall with 1.0 sq.mm 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge. [Make- (a)Switch, socket etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	Nos	1		
5	<p>Semi Concealed wiring to <b>submain with two runs of ISI marked 1.5 sq.mm</b> , 650 / 1100 volt. Pvc insulated single core (stranded ) unsheathed copper conductor in 19 mm. dia. extra super quality pvc /polythene pipe with 1.0 sq.mm 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor as earth continuity wire from B.D.B. to S.B. including all connections as per instruction of Electrical Engineer-in- charge. [Make- (a)Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	Mtr	90		
6	<p>Semi Concealed wiring to <b>submain with two runs of ISI marked 6.0sq.mm</b> , 650 / 1100 volt. Pvc insulated single core (stranded ) unsheathed copper conductor in 19 mm. dia. extra super quality pvc /polythene pipe with 1.5 sq.mm 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor as earth continuity wire from M.D.B. to B.D.B.. including all connections as per instruction of Electrical Engineer-in- charge. [Make- (a)Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	Mtr	60		



7	Supply,laying & testing of <b>3.5 core,35 sq.mm PVC insulated , PVC sheathed aluminium armoured power cable</b> of 1100 volt grade through under ground / surface as per the site requirement including all accessories and connections with making good the damages caused and as per direction of Engineer-in-charge from Dining to Ward No- 1[Make- (a) Cable- Finolex/ Havells , (b) all other materials ISI mark]	Mtr	10		
8	Supply and fixing of <b>8 way BDB consists of 1 No. 63Amp. DP MCB &amp; 6 Nos. of 32Amp. SPMCB</b> including all accessories and connections[Make-(a)MCB- Legrand/ Schnider/L&T/ ABB , (b) all other accessories ISI mark]	Set	3		
9	Supply and fixing of <b>63 AMP. FOUR POLE MCB – 01 NO wth 63 AMP. 415 VOLT CUT OUT – 03 NOS WITH COPPER BUS BAR &amp; INDICATOR ETC.</b> including all accessories and connections as per instruction of Electrical Engineer-in- charge. [Make-(a)MCB /MCCB - Legrand/ Schnider/L&T/ ABB, ( b)Volt meter, Ammeter-AE/CAPPA, (d) all other accessories ISI mark]	Set	1		
10	Supply and fixing of <b>18 watt. holder type CFL lamp</b> for the installed angle holder .[Make-CG/Philips/Bajaj]	Nos	18		
11	Supply and fixing of <b>1 x 28 wt. T5 patty type tube light fittings</b> complete set with lamp , connecting wire and all accessories refer to catalouge No - MAKE – CROMPTON CODE – T5GP28EB/MAKE-PHILIPS MODEL-MIROLTA SLIM-CODE-TMS540/MAKE-HPL-CODE-HIBE10128including fixing and connections as per instruction of Electrical Engineer-in-charge..	Nos	29		

12	Supply and fixing of <b>1200 mm sweep AC ceiling fan</b> with star 5 rated connecting wire and all accessories refer to catalouge No - [MAKE- USHA ,MODEL-ATOM , /CROMPTON,MODEL-EMPOWER 50 /KHAITAN MODEL – NEWTECetc. including hanging and connections as per instruction of Electrical Engineer-in-charge.	Nos	16		
13	Supply and fixing of <b>300 mm sweep exhaust fan</b> with connecting wire and all accessories refer to catalouge No- <b>Khaitan [Model-Euro] / Usha[Model-Turbojet Dlx] / Cromton [Model-Tranair/Transair reversable]</b> including fixing and connections as per instruction of Electrical Engineer-in-charge	Nos	1		
14	Supply and fixing of <b>earthing</b> including 38 mm. dia. 3 mtr. long G.I pipe[Heavy Duty].The pipe shall have 12 mm. dia. perforated holes at 15 cm centre to centre up to 2.5 mtrs height from the bottom and fitted with a 38 mm. dia. G.I flange at the top with provision of holes for making connection of earth continuity wire,complete with masonry work for earth pit chamber.The earth pit shall have an alternative layer of 105 mm. charcoal and 50 mm. salt up to a depth of 465 mm. and rest shall be filled with charcoal to a further depth of 2035 mm. The earth pit should maintain a minium clearance 1.5 mtr. from building & 2 mtr. in between two earth pit and as per instruction of Electrical Engineer-in-charge.	Nos	2		
15	Supply and fixing of <b>sub earthing</b> with No-8 bare copper wire as earth Continuity wire from Main pannel board to earth electrode inside the wall/ground to a depth of 50 mm. and make good of the wall/ground including all connections.	Rft	80		
			<b>SUB TOTAL-F</b>		-
<b>G</b>	<b>KITCHEN ROOM</b>				

1	<p>Semi Concealed wiring to <b>different points</b> with ISI marked 1.5 sq.mm( current carrying capacity min. 13 Amps.) 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor in 19 mm.dia. Extra super quality pvc / polythene pipe including supply &amp; fixing of 6A, 250V. flush type switch mounted on 3 mm. thick bakelite cover on required size iron board duly painted &amp; fixed inside/on the wall including supply of ceiling rose / angle holder etc. mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted or RJ box (ceiling ) fixed inside/on the wall with 1.0 sq.mm( current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge. [Make- (a)Switch, ceiling rose, angle holder, bell push switch, batten holder etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>				
(a)	Bulk Head Point	Nos	8		

<p>2</p>	<p>Semi Concealed wiring to <b>Security light point</b> at 18' height from ground level/ top corners of the building with ISI marked 1.5 sq.mm,( current carrying capacity min. 13 Amps.) 650/1100 volt. pvc insulated single core (stranded ) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply &amp; fixing of 6 Amp. / 16 Amp. ,250V. flush type switch mounted on 3 mm.thick bakelite cover on required size iron board duly painted &amp; fixed at ground floor lobby inside/on the wall including supply of ceiling rose mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted fixed inside/on the wall with 1.0 sq.mm( current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in- charge. [Make- (a)Switch, ceiling rose etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	<p>Nos</p>	<p>2</p>		
----------	---	------------	----------	--	--

3	<p>Semi Concealed wiring to <b>exhaust fan point</b> with ISI marked 1.5 sq.mm( current carrying capacity min. 13 Amps.) 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor in 19 mm. dia. extra super quality pvc /polythene pipe including supply &amp; fixing of 6A,250V. flush type switch mounted on 3 mm. thick bakelite cover on required size iron board duly painted &amp; fixed inside/on the wall including supply of ceiling rose mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted or RJ box (ceiling ) fixed inside/on the wall with 1.0 sq.mm( current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge.[Make- (a)Switch, ceiling rose etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	Nos	3		
4	<p>Semi Concealed wiring to <b>5 pin 6 Amp. socket point</b> with ISI marked 1.5 sq.mm 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply &amp; fixing of 5 pin 6 Amp. 250V. flush type socket &amp; switch mounted on 3 mm. thick bakelite cover on required size iron board / existing board duly painted &amp; fixed inside/on the wall with1.0 sq.mm 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge. [Make- (a)Switch , Socket etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL /HAVELLS (c) all other materials ISI mark]</p>	Nos	1		

5	<p>Semi Concealed wiring to <b>power point [16 Amp.]</b> with ISI marked 6.0 sq.mm 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply &amp; fixing of 5 pin 16 Amp. 250V. flush type socket, switch, separate/combine) mounted on 3 mm.thick bakelite cover on required size iron board duly painted &amp; fixed inside/on the wall with 1.5 sq.mm 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge. [Make- (a)Switch,socket etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	Nos	1		
6	<p>Semi Concealed wiring to <b>submain with two runs of ISI marked 1.5 sq.mm</b> , 650 / 1100 volt. Pvc insulated single core (stranded ) unsheathed copper conductor in 19 mm. dia. extra super quality pvc /polythene pipe with 1.0 sq.mm 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor as earth continuity wire from B.D.B. to S.B. including all connections as per instruction of Electrical Engineer-in- charge. [Make- (a)Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	Mtr	20		
7	<p>Semi Concealed wiring to <b>submain with two runs of ISI marked 6.0sq.mm</b> , 650 / 1100 volt. Pvc insulated single core (stranded ) unsheathed copper conductor in 19 mm. dia. extra super quality pvc /polythene pipe with 1.5 sq.mm 650/1100 volt pvc insulated single core (stranded ) unsheathed copper conductor as earth continuity wire from B.D.B TO Power Point . including all connections as per instruction of Electrical Engineer-in- charge. [Make- (a)Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	Mtr	15		

8	Supply,laying & testing of <b>2 core,16 sq.mm PVC insulated , PVC sheathed aluminium armoured power cable</b> of 1100 volt grade through under ground / surface as per the site requirement including all accessories and connections with making good the damages caused and as per direction of Engineer-in-charge from Nearest L.T. Pole to Main Panel Board. [Make- (a) Cable- Finolex/ Havells , (b) all other materials ISI mark]	Mtr	30		
9	Supply and fixing of <b>8 way BDB consists of 1 No. 63Amp. DP MCB &amp; 6 Nos. of 32Amp. SPMCB</b> including all accessories and connections[Make-(a)MCB- Legrand/ Schnider/L&T/ ABB , (b) all other accessories ISI mark]	Set	1		
10	Supply and fixing of <b>Bulk Head fitting</b> including all accessories refer to catalouge No - MAKE – CROMPTON CODE – ICBH10/MAKE-PHILIPS/ CODE-NXC101/MAKE-HPL-CODE-HIBHO10008s and connections as per instruction of Electrical Engineer-in-charge.	Nos	8		
11	Supply and fixing of <b>300 mm sweep exhaust fan</b> with connecting wire and all accessories refer to catalouge No- <b>Khaitan [Model-Euro] / Usha[Model-Turbojet Dlx] / Cromton [Model-Tranair/Transair reversable]</b> including fixing and connections as per instruction of Electrical Engineer-in-charge	Nos	3		
12	Supply & fixing of <b>4 x24 wt. T5 energy saving light fitting</b> with bulb,choke,cover, G.I. Bracket, Clamp & Nut Bolt connecting wire all accessories refer to catalouge No- CROMPTON CODE – T5SHO424 EB IP 65/MAKE-HPL-CODE-HPLT5STAL424 / PHILIPSincluding fixing and connections as per instruction of Electrical Engineer-in-charge.	Nos	2		
				<b>SUB TOTAL-G</b>	<b>-</b>

Seal & Signature of the Contractor

Sd/-  
Asst. Project Manager (Elect.)