

**THE ODISHA STATE POLICE HOUSING & WELFARE CORPORATION LTD.
JANPATH, BHUBANESWAR-22.**

Tel: 0674 2541545; Fax: 0674 2541543; E-mail : jmelectricalophwc@gmail.com

Web: ophwc.nic.in

BID REFERENCE NO: - 22/ 2015-16/ELECT/ OPHWC

**SCHEDULE OF TENDER FOR RENOVATION OF ELECTRICAL INSTALLATION
AT NABARANGPUR SUB-JAIL IN THE DIST. OF NABARANGPUR.**

SOLD TO : M/S _____

MONEY

RECEIPT NO : _____

DATE : _____

[SIGNATURE OF ISSUING OFFICER]

THE ODISHA STATE POLICE HOUSING & WELFARE CORPORATION LTD.
JANPATH, BHUBANESWAR-22.
Tel: 0674 2541545; Fax: 0674 2541543; E-mail : jmelectricalophwc@gmail.com
Web: ophwc.nic.in

TENDER CALL NOTICE
BID REFERENCE NO: - 22/ 2015-16/ELECT/ OPHWC

1. Sealed tender in the prescribed form with detailed Tender Call Notice for execution of External electrification, Renovation & Improvement of Electrical Installation Lighting Protection System and Area illumination works of different Jail projects are invited in single cover system from the enlisted H.T. / M.V.(M.V. Contractors only participated with internal electrification , Area Lighting and Lighting Protection system works) electrical Contractors/Firms under O.S.P.H&W.C., Bhubaneswar including supply of materials as per the specification. Tender to be submitted separately for each project.

Sl.No	Name of the Project	Estimated Cost	EMD	Cost of tender paper including vat	Period of completion	Eligibility Range
1	Renovation and Improvement of Electrical Installation in Circle Jail, Baripada in the Dist. of Mayurbhanj.	Rs.12,47,260.00	Rs.12,473.00	Rs.6300.00	45 days	10 lakh above
2	Renovation of Electrical Wiring at Nabarangpur Sub-Jail in the Dist. of Nabarangpur.	Rs.25,48,540.00	Rs.25,485.00	Rs.6300.00	45 days	20 lakh above
3	Renovation and Improvement of Electrical Installation at Sub-Jail Baliguda in the dist. of Kandhamal.	Rs.8,27,500.00	Rs.8,275.00	Rs.4,200.00	45 days	Up to 10 lakh & above
4	Renovation and Improvement of Electrical Installation at Sub-Jail Champua in the Dist. of Keonjhar.	Rs.12,64,900.00	Rs.12,649.00	Rs.6300.00	45 days	10 lakh above
5	Renovation and Improvement of Electrical Installation at Sub-Jail Rairangpur	Rs.13,53,550.00	Rs.13,536.00	Rs.6300.00	45 days	10 lakh above
6	Repair and Renovation	Rs.5,15,250.00	Rs.5,153.00	Rs.4,200.00	45 days	Up to 10

	work at Sub-Jail,Paralakhemundi in the Dist. of Gajapati.					lakh & above
7	Renovation and Improvement of Electrical Installation at Sub-Jail Banki in the Dist. of Cuttack.	Rs.2,65,620.00	Rs.2,656.00	Rs.2,100.00	45 days	Up to 10 lakh & above
8	Improvement of Electrical Installation at Sub-Jail Padmapur.	Rs.6,85,375.00	Rs.6,854.00	Rs.4,200.00	45 days	Up to 10 lakh & above
9	Renovation and Improvement of Electrical Installation in Adminstrative Block at Sub-Jail Dhenkanal in the Dist. of Dhenkanal.	Rs.5,13,314.00	Rs.5,133.00	Rs.4,200.00	45 days	Up to 10 lakh & above
10	Renovation of Electrical Wiring at Narasinghpur-Jail in the dist. of Cuttack.	Rs.21,71,165.00	Rs.21,712..00	Rs.6300.00	45 days	20 lakh above
11	Lighting Protection System for Adminstrative Building & Male Ward at Narasinghpur Jail in the Dist. of Cuttack..	Rs.5,49,500.00	Rs.5,495.00	Rs.4,200.00	45 days	Up to 10 lakh & above
12	Renovation and Improvement of Electrical Installation at Sub-Jail Athamallik in the Dist. of Cuttack.	Rs.7,65,070.00	Rs.7,651.00	Rs.4,200.00	45 days	Upto 10 lakh & above
13	Renovation and Improvement of Electrical Installation at Sub-Jail Anandpur in the Dist. of Keonjhar.	Rs.9,85,080.00	Rs.9,851.00	Rs.4,200.00	45 days	Up to 10 lakh & above
14	Renovation and Improvement of Electrical Installation at Sub-Jail Jajpur in the Dist. of Jajpur.	Rs.10,31,770.00	Rs.10,318.00	Rs.6300.00	45 days	10 lakh & above
15	Renovation and Improvement of Electrical Installation at Sub-Jail Jajpur Road in the Dist. of Jajpur.	Rs.11,32,415.00	Rs.11,324.00	Rs.6300.00	45 days	10 lakh & above

16	External Electrification work of Sub-Jail,Padmapur	Rs.6,74,315.00	Rs.6,743.00	Rs.4,200.00	45 days	Up to 10 lakh & above
17	Installation of Security Lighting Arrangement at Sub-Jail Jajpur Road in the Dist. of Jajpur	Rs.8,19,500.00	Rs.8,195.00	Rs.4,200.00	45 days	Up to 10 lakh & above
18	Renovation and Improvement of Electrical Installation at Angul Jail in the Dist. of Angul.	Rs.11,79,920.00	Rs.11,799.00	Rs.6300.00	45 days	10 lakh above
19	Internal Electrification Work at Sundergarh Jail in the Dist. of Sundergarh.	Rs.20,16,045.00	Rs.20,160.00	Rs.6300.00	45 days	20 lakh above
20	Pheripheral Lighting Work at Sundergarh Jail in the Dist. of Sundergarh.	Rs.18,56,200.00	Rs.18,562.00	Rs.6300.00	45 days	10 lakh & above
21	Repair and Renovation of Electrical works at Special JailJharpada ,Bhubaneswar in the Dist. of Khurda.	Rs.5,39,190.00	Rs.5,392.00	Rs.4,200.00	45 days	Up to 10 lakh & above
22	Renovation and Improvement of Electrical Installation at Dist. Jail Puri in the Dist. of Puri.	Rs.9,01,640.00	Rs.9,016.00	Rs.4,200.00	45 days	Up to 10 lakh & above
23	Area Illumination work of Padmapur-Sub-Jail	Rs.5,83,700.00	Rs.5,837.00	Rs.4,200.00	45 days	Up to 10 lakh & above

2. The tender document may be obtained on payment of the tender paper cost as mentioned in the Column – 5 of the above table [Non refundable] for each project between 10.00 A.M. to 05.00 P.M on each working day from the office of the undersigned at the Address given above of O.S.P.H.&WC at Bhubaneswar on or before Dt. 10 .02.2016 .Tender document can also be obtained through speed post by sending a self addressed envelope of size 35 cm x 25 cm along with a Demand Draft / Pay Order of the tender paper cost as mentioned in the Column – 5 of the above table and Rs. 200.00 (Rupees two hundred only) extra for purchased by post[Non refundable] for each project on any scheduled Bank, payable at Bhubaneswar, drawn in favour of the **“The Odisha State Police Housing &Welfare corporation Ltd.”**. However, such request must be received by the undersigned on or before the last date for issue of tender document. The O.S.P.H.&W.C. authorities shall not be responsible for postal or

other delays. The tender document will also be available from the web site www.ophwc.nic.in and the same can be downloaded to be used for tender offer. However in case of downloaded tender documents an amount of the tender paper cost as mentioned in the Column – 5 of the above table [Non refundable] for each project in shape of Demand Draft / Pay Order drawn on any scheduled Bank, is payable at Bhubaneswar in favour of the **“The Odisha State Police Housing & Welfare Corporation Ltd.”** along with the tender , failing which tender shall be liable for rejection.

3. The bidders are requested to submit the receipt of showing cost of tender paper along with the attested copies of valid H.T./MV license from ELBO, Income tax return copy, PAN card, TIN No, up to date VAT clearance certificate along with bid documents otherwise the bid shall be liable for rejection.
4. **EMD** - The tender shall be accompanied with EMD as mentioned above in shape of D.D. / Pay order drawn on any Nationalized Bank in favour of the **“The Odisha State Police Housing & Welfare corporation Ltd.”**, failing which the tender shall be rejected.
5. Other details can be seen in the tender documents.
6. Bids submitted otherwise than in the manner prescribed in the tender document shall be rejected.
7. The bidding document should be super scribed “Tender forworks, Tender No., Name of the Project etc.”
8. The tender document is available from :10 AM on Dt. 28/01/2016
9. Last date for issue of tender document is up to : 05.00 PM on Dt. 10 /02/2016
10. Last date for receipt of tender document is up to : 12.30 PM on Dt. 15 /02/2016
11. Date of opening of bid at : 03.30 PM on Dt. 15/02/2016
12. The authority reserves the right to reject any or all the bids without assigning any reason thereof.
13. An affidavit is to be furnish by the bidder at the time of submitting bid document that he is not blacklisted / defaulter contractor or Firm etc. The authority reserves the right to reject any or all the bids without assigning any reason thereof and can impose any conditions as deemed proper before finalisation of tender.

Sd/-
Joint Manager (Elect.)

GENERAL CONDITION OF THE CONTRACT
BID REFERENCE NO: - 22 / 2015-16 /ELECT/ OPHWC

1. The tender document shall be accompany with the EMD as above only in shape of Demand Draft / Pay Order drawn on any Nationalized Bank payable at Bhubaneswar in favour of the “**The Odisha State Police Housing & Welfare Corporation Ltd.**” failing which the tender shall be rejected.
2. The bidders are requested to submit the receipt of showing cost of tender paper along with the attested copies of valid H.T. license from ELBO, Income tax return copy, PAN card, TIN No, upto date VAT clearance certificate and VAT registration certificate along with bid documents otherwise the bid shall be liable for rejection. The latest authenticated documentary proof shall be submitted. The proof submitted earlier in some other contest shall not be treated as valid and sufficient.
3. The bid must accompany proof of executing same nature of work as per eligibility criteria mentioned in tender call notice in Govt. / Govt. Undertaking. Departments. The copy of work order and completion certificates in support of credential should be enclosed with the tender otherwise the bid shall be rejected.
4. The bidding document should be super scribed “Tender for.....works,Tender No., Name of the Project etc.”
5. The tenders (also called bids) not submitted in prescribed format or in prescribed manner, shall be rejected at the risk and responsibility of bidder.
6. All the information as called for in the tender document should be submitted truly, clearly, legible, transparently, unambiguously and without the use of abbreviations. It shall be submitted in English only.
7. All the crucial figures, like rates and amount should be written in figures followed by words in a bracket.
8. There shall be no over writing in the tender document and other papers submitted. All additions, alternations, deletions and cutting should be initialed with rubber-stamp (or seal) by the same person, who signs the tender document, failing which so, the tender may be rejected.
9. All the rates and amounts shall be quoted in Indian Rupee and shall be presumed to be in Indian Rupee only unless specifically permitted to be quoted otherwise in this tender document.

10. Each page of this tender document should be signed by the bidder with seal in token of having read, understood and accepted the terms and conditions of this contract.
11. Use separate piece of paper where the space provided in the formats in this tender document for submission of information is not sufficient.
12. The contractor shall stand for guarantee against defective materials / manufacturing defects(except lamp in case of Area illumination work) and workmanship for the work carried out by him for a period of **24** months from its commissioning /handing over & make good /repair/replace the faults during this period without any extra cost, failing which the same shall be got done at the risk and cost of the contractor. The work shall be supervised by the qualified supervisor from the contractor's side.
13. All information submitted or supplied in the formats of this tender document shall be presumed to be true to the best of knowledge of bidder.
14. The firms not having VAT Registration certificate shall not be eligible for submitting the bids. The blacklisted firms shall also not be eligible for participating in the bid.
15. The tenders/bids can be sent by post or courier as well. However, authorities shall not be responsible for postal or delays in receipt of bids.
16. If the last date for receipt of the tender/bid turns out to be a holiday, it will automatically be extended to next working day.
17. A bid submitted can not be withdrawn. The bidder or his authorized representative (one person only) will be allowed to be present at the time of opening of tenders. They will not participate in the discussions. Clarification sought, if any may be provided by them.
18. All or any of the tenders /bids submitted can be rejected without assigning any reason thereof. No claim, whatsoever, shall be admissible for the alleged loss/damages suffered by bidders on account of such rejections.
19. Bids shall be opened in the presence of the bidders or their authorized representative.
20. Prices quoted for each item shall be inclusive of all i.e. taxes and duties, excise duty, service taxes, loading, unloading, transportation, insurance, watch and ward etc.
21. Advance payment /part payment will not be entertained before completion and handing over the work.
22. No claim can be made due to some unforeseen delay for release of payment.
23. Payment of bill will be made only after completion of the work in all respects i.e. commissioning, testing, inspection of work by the electrical inspector, execution of agreement between user authority and distribution Company authority before charging of

sub station / Line and handed over the work to the *distribution Company. In case of Renovation & Improvement of Electrical Work payment of bill will be made only after completion of the work in all respects i.e. commissioning, testing and handed over the work to the user authority.*

24. All the transit risk shall be responsibility of the contractor.
25. Failure to complete the work in full within the stipulated period may lead to forfeiture of EMD and blacklisting of the contractor/firm.
26. The authorities are not bound to accept the lowest quoted rate.
27. Terms and conditions of this tender document can not be negotiated for variations.
28. The authority reserves the right to reject any or all tender in whole or part without assigning any reason and can impose any other condition(s) as deemed proper before or in course of finalisation of the tender.
29. The approved tender may be cancelled by the authority any time during validity without assigning any reason thereof and no claim can lie against OPHW&C for such cancellation.
30. All materials required for the work should be approved brand of the concerned Distribution company / as per the given specification and brand. Before take up the work A.P.M (Electrical) shall verify/ certify the quality of materials.
31. Before installation of the transformer E&MR certificate shall be submitted along with CPRI certificate and guarantee certificate of the transformer shall be submitted.
32. LT bushing cover and tap changer shall be provided.
33. All the disputes shall be subject to Jurisdiction of Civil Courts situated at Bhubaneswar.

Signature & seal of the Bidder.

**Sd/-
Joint Manager (Elect.)**

GENERAL BID FORM
BID REFERENCE NO: - 22/ 2015-16/ELECT/ OPHWC

1.Name :

Full Address :

Fax No :

Telephone No :

E-mail address of the firm :

2.Legal Status of the firm :

3.Give the location and Address of your Office/ Branch office :

4.Kindly confirm by writing” Yes” of “No” only

[A] Have you enclosed the EMD? If yes, mention the amount and its identifying details.

[B] Have you enclosed the valid H.T./ M.V. License?

[C] Have you enclosed the VAT clearance certificate?

[D] Have you enclosed the PAN card?

[E] Have you enclosed the audited balance sheet?

[F] Copies of assessment return of sales tax and income tax of last three years.

[G] Have you enclosed all the documents and papers called for in this tender document?

Kindly enclose a list. (Use a separate sheet of paper)

[H] If the answer to [G] above is ‘No’, which of the Documents / papers called for in the tender document have not enclosed.

(Kindly enclose a list of such document/papers – Use separate Sheet of paper, if necessary)

Signature & seal of the Bidder.

Sd/-
Joint Manager (Elect.)

OFFICE OF THE CHAIRMAN-CUM- MANAGING DIRECTOR.
ODISHA STATE POLICE HOUSING & WELFARE CORPORATION LTD., BHUBANESWAR.

BILL OF QUANTITY

TENDER NO.- 22/2015-16/ ELECT/OPHWC

NAME OF THE WORK :- EXECUTION OF INTERNAL ELECTRIFICATION WORKS OF SUB-JAIL,NABARANGPUR.

Sl. No.	SCOPE OF WORK	UNIT	QTY.	QUOTED RATE INCLUSIVE OF ALL IN FIGURE & WORD	QUOTED AMOUNT INCLUSIVE OF ALL IN FIGURE & WORD
A ENTRANCE GATE ROOM					
1	Semi Concealed wiring to different points with ISI marked 1.5 sq.mm(current carrying capacity min. 13 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm.dia. Extra super quality pvc / polythene pipe including supply & fixing of 6A, 250V. flush type switch mounted on 3 mm. thick bakelite cover on required size iron board duly painted & fixed inside/on the wall including supply of ceiling rose / angle holder etc. mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted or RJ box (ceiling) fixed inside/on the wall with 1.0 sq.mm(current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in- charge. [Make-(a)Switch, ceiling rose, angle holder, bell push switch, batten holder etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]				
(a)	Angle Holder Point	Nos	4		

2	<p>Semi Concealed wiring to Security light point at 18' height from ground level/ top corners of the building with ISI marked 1.5 sq.mm,(current carrying capacity min. 13 Amps.) 650/1100 volt. pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply & fixing of 6 Amp. / 16 Amp. ,250V. flush type switch mounted on 3 mm.thick bakelite cover on required size iron board duly painted & fixed at ground floor lobby inside/on the wall including supply of ceiling rose mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted fixed inside/on the wall with 1.0 sq.mm(current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in- charge. [Make- (a)Switch, ceiling rose etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	Nos	5		
---	---	-----	---	--	--

<p>3</p>	<p>Semi Concealed wiring to ceiling fan point with ISI marked 1.5 sq.mm(current carrying capacity min. 13 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply & fixing of 6A,250V. flush type switch with step type electronic regulator mounted on 3 mm. thick bakelite cover on required size iron board duly painted & fixed inside/on the wall including supply of ceiling rose mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted or RJ box (ceiling) fixed inside/on the wall with 1.0 sq.mm (current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge. [Make- (a)Switch, ceiling rose etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	<p>Nos</p>	<p>1</p>		
<p>4</p>	<p>Semi Concealed wiring to 5 pin 6 Amp. socket point with ISI marked 1.5 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply & fixing of 5 pin 6 Amp. 250V. flush type socket & switch mounted on 3 mm. thick bakelite cover on required size iron board / existing board duly painted & fixed inside/on the wall with1.0 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge. [Make- (a)Switch & Socket etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	<p>Nos</p>	<p>4</p>		

5	Semi Concealed wiring to submain with two runs of ISI marked 1.5 sq.mm , 650 / 1100 volt. Pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc /polythene pipe with 1.0 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire For B.D.B. to S.B. including all connections as per instruction of Electrical Engineer-in- charge. [Make- (a)Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]	Mtr	70		
6	Semi Concealed wiring to submain with two runs of ISI marked 4.0 sq.mm , 650 / 1100 volt. Pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc /polythene pipe with 1.5 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire from 200 AMP Main Panel to Powerpoint . including all connections as per instruction of Electrical Engineer-in-charge.[Make- (a)Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]	Mtr	70		
7	Supply and fixing of 20 watt. holder type CFL lamp for the installed angle holder .[Make-CG/Philips/Bajaj]	Nos	4		
8	Supply and fixing of 1200 mm sweep AC ceiling fan with star 5 rated connecting wire and all accessories refer to catalouge No - [MAKE- USHA ,MODEL-ATOM , /CROMPTON,MODEL-EMPOWER 50 /KHAITAN MODEL – NEWTECetc. including hanging and connections as per instruction of Electrical Engineer-in-charge.	Nos	1		

9	Supply & fixing of 4 x24 wt. T5 energy saving light fitting with bulb,choke,cover, G.I. Bracket, Clamp & Nut Bolt connecting wire all accessories refer to catalouge No-CROMPTON CODE – T5SHO424 EB IP 65/MAKE-HPL-CODE-HPLT5STAL424 / PHILIPSincluding fixing and connections as per instruction of Electrical Engineer-in-charge.	Nos	5		
10	Supply and fixing of 63 AMP. FOUR POLE MCB – 01 NO wth 63 AMP. 415 VOLT CUT OUT – 03 NOS WITH COPPER BUS BAR & INDICATOR ETC. including all accessories and connections as per instruction of Electrical Engineer-in- charge. [Make-(a)MCB /MCCB - Legrand/ Schnider/L&T/ ABB, (b)Volt meter, Ammeter-AE/CAPPA, (d) all other acessories ISI mark]	Set	1		
11	Supply and fixing of 200 AMP. TPMCCB [35 KA] - 01 SET with 100 AMP. 415 VOLT CUT OUT - 03 NOS WITHOUT METER SPACE OUT GOING - 100 AMP, 25 / 3 MM. COPPER BUS BAR - 04 NOS INSTRUMENTS 0 – 100 AMP. AMMETER WITH SELECTOR SWITCH - 01 SET 100 / 5 AMP. CT - 01 SET 0 – 500 VOLT VOLTMETER WITH SELECTORSWITCH - 01 SET INDICATING LAMP WITH CONTROLLING SWITCH - 01 SET etc. including all accessories and connections as per instruction of Electrical Engineer-in-charge.[Make-(a)MCB /MCCB - Legrand/ Schnider/L&T/ ABB, (b)Volt meter, Ammeter-AE/CAPPA, (d) all other acessories ISI mark]	Nos	1		
12	Supply and fixing of 125Amp. FOUR Pole change over panel Board with bus bar including all accessories and connections..[Make-(a)Change Over Switch - Simens/HPL/L&T/ABB, (b)Cut out-Anchor/BPL, (c) Volt meter, Ammeter-AE/CAPPA, (d) all other acessories ISI mark]	Set	1		

13	Supply,laying & testing of 3.5 core,50 sq.mm PVC insulated , PVC sheathed aluminium armoured power cable of 1100 volt grade through under ground / surface as per the site requirement including all accessories and connections with making good the damages caused and as per direction of Engineer-in-charge from outside LT Pole to 200 Amp TPMCCB	Mtr	60		
14	Supply,laying & testing of 3.5 core,25 sq.mm PVC insulated , PVC sheathed aluminium armoured power cable of 1100 volt grade through under ground / surface as per the site requirement including all accessories and connections with making good the damages caused and as per direction of Engineer-in-charge from Changeover to 63 Amp TPNMCCB PANEL& from DG to ChangeOver	Mtr	70		
15	Supply and fixing of 8 way BDB consists of 1 No. 40Amp. DP MCB & 6 Nos. of 20Amp. SPMCB including all accessories and connections.[Make-(a)MCB- Legrand/ Schnider/L&T/ ABB , (b) all other accessories ISI mark]	Set	3		
16	Supply and fixing of earthing including 38 mm. dia. 3 mtr. long G.I pipe[Heavy Duty].The pipe shall have 12 mm. dia. perforated holes at 15 cm centre to centre up to 2.5 mtrs height from the bottom and fitted with a 38 mm. dia. G.I flange at the top with provision of holes for making connection of earth continuity wire,complete with masonry work for earth pit chamber.The earth pit shall have an alternative layer of 105 mm. charcoal and 50 mm. salt up to a depth of 465 mm. and rest shall be filled with charcoal to a further depth of 2035 mm. The earth pit should maintain a minium clearance 1.5 mtr. from building & 2 mtr. in between two earth pit and as per instruction of Electrical Engineer-in-charge.	Nos	2		

17	Supply and fixing of sub earthing with No-8 bare copper wire as earth Continuity wire from Main pannel board to earth electrode inside the wall/ground to a depth of 50 mm. and make good of the wall/ground including all connections.	Rft	120		
18	Supply and fixing of 80 mm dia GI Pipe 10ft Long	Nos	18		
B JAILOR ROOM					
1	Semi Concealed wiring to different points with ISI marked 1.5 sq.mm(current carrying capcity min. 13 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm.dia. Extra super quality pvc / polythene pipe including supply & fixing of 6A, 250V. flush type switch mounted on 3 mm. thick bakelite cover on required size iron board duly painted & fixed inside/on the wall including supply of ceiling rose / angle holder etc. mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted or RJ box (ceiling) fixed inside/on the wall with 1.0 sq.mm(current carrying capcity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in- charge. [Make-(a)Switch, ceiling rose, angle holder, bell push switch, batten holder etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]				
(a)	Angle Holder Point	Nos	3		
(b)	Tube Light Point	Nos	3		
©	Calling Bell Point	Nos	1		

2	<p>Semi Concealed wiring to ceiling fan point with ISI marked 1.5 sq.mm(current carrying capacity min. 13 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply & fixing of 6A,250V. flush type switch with step type electronic regulator mounted on 3 mm. thick bakelite cover on required size iron board duly painted & fixed inside/on the wall including supply of ceiling rose mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted or RJ box (ceiling) fixed inside/on the wall with 1.0 sq.mm (current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge. [Make- (a)Switch, ceiling rose etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	Nos	1		
---	--	-----	---	--	--

<p>3</p>	<p>Semi Concealed wiring to exhaust fan point with ISI marked 1.5 sq.mm(current carrying capacity min. 13 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc /polythene pipe including supply & fixing of 6A,250V. flush type switch mounted on 3 mm. thick bakelite cover on required size iron board duly painted & fixed inside/on the wall including supply of ceiling rose mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted or RJ box (ceiling) fixed inside/on the wall with 1.0 sq.mm(current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge.[Make-(a)Switch, ceiling rose etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	<p>Nos</p>	<p>1</p>		
<p>4</p>	<p>Semi Concealed wiring to 5 pin 6 Amp. socket point with ISI marked 1.5 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply & fixing of 5 pin 6 Amp. 250V. flush type socket & switch mounted on 3 mm. thick bakelite cover on required size iron board / existing board duly painted & fixed inside/on the wall with1.0 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire (For Computer, CC TV & TV) including all connections as per instruction of Electrical Engineer-in-charge. [Make-(a)Switch, Socket etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	<p>Nos</p>	<p>18</p>		

5	<p>Semi Concealed wiring to power point [16 Amp.] with ISI marked 6.0 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply & fixing of 5 pin 16 Amp. 250V. flush type socket, switch, separate/combine) mounted on 3 mm.thick bakelite cover on required size iron board duly painted & fixed inside/on the wall with 1.5 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire from 200 Amp Main Panel to 15 Amp Socket Point Through 40 AMP DP MCB Box including all connections as per instruction of Electrical Engineer-in- charge. [Make- (a)Switch etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	Nos	2		
6	<p>Supply and fixing of 20 watt. holder type CFL lamp for the installed angle holder .[Make-CG/Philips/Bajaj]</p>	Nos	4		
7	<p>Supply and fixing of 1 x 40 wt. patty type tube light fittings complete set with lamp , connecting wire and all accessories refer to catalouge No - MAKE – CROMPTON CODE – DJBN1314EB/MAKE-PHILIPS – MODEL-TARANG/CODE-TMC090 /HPL-CODE-HCPE2136 including fixing and connections as per instruction of Electrical Engineer-in-charge..</p>	Nos	3		
8	<p>Supply and installation of 1.5Tr. Split type Air Conditioner (5 Star) of reputed brand with supply and fixing of 5 KVA ,130-280 Volt voltage range wall/floor mounted stabiliser including all accessories,fastner angle copper piping up to 15ft & connections as per instruction of Electrical Engineer-in-charge MAKE of A.C. – CARRIER KURVE, /MAKE – BLUE STAR, CODE-3HW18TB , MAKE OF STABILIZER-JYOTI/SHAKTI/ AUTOTEK</p>	Nos	1		

9	Supply and fixing of 1200 mm sweep AC ceiling fan with star 5 rated connecting wire and all accessories refer to catalouge No - [MAKE- USHA ,MODEL-ATOM , /CROMPTON,MODEL-EMPOWER 50 /KHAITAN MODEL – NEWTECetc. including hanging and connections as per instruction of Electrical Engineer-in-charge.	Nos	1		
10	Supply and fixing of 300 mm sweep exhaust fan with connecting wire and all accessories refer to catalouge No- Khaitan [Model-Euro] / Usha[Model-Turbojet Dlx] / Cromton [Model-Tranair/Transair reversable] including fixing and connections as per instruction of Electrical Engineer-in-charge	Nos	1		
11	Supply and fixing of calling bell (ding dong) including all accessories and connections as per instruction of Electrical Engineer-in-charge.	Nos	1		
12	Supply and fixing of 2 way MCB Box consists of 1 No. 40 Amp. DP MCB including all accessories and connections...[Make-(a)MCB- ABB / STANDARD / HAVELLS / LEGRAND/HPL, (b) all other accessories ISI mark]	Set	1		
C ASST. JAILOR ROOM					

1	<p>Semi Concealed wiring to different points with ISI marked 1.5 sq.mm(current carrying capacity min. 13 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm.dia. Extra super quality pvc / polythene pipe including supply & fixing of 6A, 250V. flush type switch mounted on 3 mm. thick bakelite cover on required size iron board duly painted & fixed inside/on the wall including supply of ceiling rose / angle holder etc. mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted or RJ box (ceiling) fixed inside/on the wall with 1.0 sq.mm(current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in- charge. [Make- (a)Switch, ceiling rose, angle holder, bell push switch, batten holder etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>				
(a)	Angle Holder Point	Nos	2		
(b)	Tube Light Point	Nos	2		
©	Calling Bell Point	Nos	1		

2	<p>Semi Concealed wiring to ceiling fan point with ISI marked 1.5 sq.mm(current carrying capacity min. 13 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply & fixing of 6A,250V. flush type switch with step type electronic regulator mounted on 3 mm. thick bakelite cover on required size iron board duly painted & fixed inside/on the wall including supply of ceiling rose mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted or RJ box (ceiling) fixed inside/on the wall with 1.0 sq.mm (current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge. [Make- (a)Switch, ceiling rose etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	Nos	1		
---	--	-----	---	--	--

3	Semi Concealed wiring to 5 pin 6 Amp. socket point with ISI marked 1.5 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply & fixing of 5 pin 6 Amp. 250V. flush type socket & switch mounted on 3 mm. thick bakelite cover on required size iron board / existing board duly painted & fixed inside/on the wall with 1.0 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge. [Make-(a)Switch, Socket etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]	Nos	4		
4	Supply and fixing of 1 x 40 wt. patty type tube light fittings complete set with lamp , connecting wire and all accessories refer to catalouge No - MAKE – CROMPTON CODE – DJBN1314EB/MAKE-PHILIPS – MODEL-TARANG/CODE-TMC090 /HPL-CODE-HCPE2136 including fixing and connections as per instruction of Electrical Engineer-in-charge..	Nos	2		
5	Supply and fixing of 20 watt. holder type CFL lamp for the installed angle holder .[Make-CG/Philips/Bajaj]	Nos	3		
6	Supply and fixing of 1200 mm sweep AC ceiling fan with star 5 rated connecting wire and all accessories refer to catalouge No - [MAKE- USHA ,MODEL-ATOM , /CROMPTON,MODEL-EMPOWER 50 /KHAITAN MODEL – NEWTECetc. including hanging and connections as per instruction of Electrical Engineer-in-charge.	Nos	1		
7	Supply and fixing of calling bell (ding dong) including all accessories and connections as per instruction of Electrical Engineer-in-charge.	Nos	1		

D MALE WARD-1

--

1	<p>Semi Concealed wiring to different points with ISI marked 1.5 sq.mm(current carrying capacity min. 13 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm.dia. Extra super quality pvc / polythene pipe including supply & fixing of 6A, 250V. flush type switch mounted on 3 mm. thick bakelite cover on required size iron board duly painted & fixed inside/on the wall including supply of ceiling rose / angle holder etc. mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted or RJ box (ceiling) fixed inside/on the wall with 1.0 sq.mm(current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in- charge. [Make- (a)Switch, ceiling rose, angle holder, bell push switch, batten holder etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>				
(a)	Angle Holder Point (DG-3 Nos.& AC-6 Nos.)	Nos	9		
(b)	Tube Light Point	Nos	15		

2	<p>Semi Concealed wiring to Security light point at 18' height from ground level/ top corners of the building with ISI marked 1.5 sq.mm,(current carrying capacity min. 13 Amps.) 650/1100 volt. pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply & fixing of 6 Amp. / 16 Amp. ,250V. flush type switch mounted on 3 mm.thick bakelite cover on required size iron board duly painted & fixed at ground floor lobby inside/on the wall including supply of ceiling rose mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted fixed inside/on the wall with 1.0 sq.mm(current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in- charge. [Make- (a)Switch, ceiling rose etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark] (DG-2 Nos & AC-4 Nos)</p>	Nos	6		
---	--	-----	---	--	--

<p>3</p>	<p>Semi Concealed wiring to ceiling fan point with ISI marked 1.5 sq.mm(current carrying capacity min. 13 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply & fixing of 6A,250V. flush type switch with step type electronic regulator mounted on 3 mm. thick bakelite cover on required size iron board duly painted & fixed inside/on the wall including supply of ceiling rose mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted or RJ box (ceiling) fixed inside/on the wall with 1.0 sq.mm (current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge. [Make- (a)Switch, ceiling rose etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	<p>Nos</p>	<p>15</p>		
----------	--	------------	-----------	--	--

4	<p>Semi Concealed wiring to exhaust fan point with ISI marked 1.5 sq.mm(current carrying capacity min. 13 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc /polythene pipe including supply & fixing of 6A,250V. flush type switch mounted on 3 mm. thick bakelite cover on required size iron board duly painted & fixed inside/on the wall including supply of ceiling rose mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted or RJ box (ceiling) fixed inside/on the wall with 1.0 sq.mm(current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge.[Make-(a)Switch, ceiling rose etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	Nos	1		
5	<p>Semi Concealed wiring to 5 pin 6 Amp. socket point with ISI marked 1.5 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply & fixing of 5 pin 6 Amp. 250V. flush type socket & switch mounted on 3 mm. thick bakelite cover on required size iron board / existing board duly painted & fixed inside/on the wall with1.0 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge. [Make-(a)Switch, Socket etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	Nos	4		

6	Semi Concealed wiring to submain with two runs of ISI marked 1.5 sq.mm , 650 / 1100 volt. Pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc /polythene pipe with 1.0 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire For B.D.B. to S.B. including all connections as per instruction of Electrical Engineer-in- charge. [Make-(a)Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]	Mtr	50		
7	Supply and fixing of 8 way BDB consists of 1 No. 40 Amp. DP MCB & 6 Nos. of 20Amp. SPMCB including all accessories and connections.[Make-(a)MCB- Legrand/ Schnider/L&T/ ABB , (b) all other accessories ISI mark]	Set	1		
8	Supply and fixing of 6 way BDB consists of 1 No. 32 Amp. DP MCB & 4 Nos. of 16 Amp. SPMCB including all accessories and connections.[Make-(a)MCB- Legrand/ Schnider/L&T/ ABB , (b) all other accessories ISI mark] (For DG Control)	Set	1		
9	Supply,laying & testing of 2 core,16 sq.mm PVC insulated , PVC sheathed aluminium armoured power cable of 1100 volt grade through under ground / surface as per the site requirement including all accessories and connections with making good the damages caused and as per direction of Engineer-in-charge from 63 Amp. Feddar Pillar Box at Kitchen to Mail Ward-1 [Make- (a) Cable- Finolex/ Havells , (b) all other materials ISI mark] (For AC Supply)	Mtr	25		

10	Supply, laying & testing of 2 core, 10 sq.mm PVC insulated , PVC sheathed aluminium armoured power cable of 1100 volt grade through under ground / surface as per the site requirement including all accessories and connections with making good the damages caused and as per direction of Engineer-in-charge from 63 Amp. Feeder Pillar Box at Kitchen to Mail Ward-1 [Make- (a) Cable- Finolex/ Havells , (b) all other materials ISI mark] (For DG Supply)	Mtr	25		
11	Supply & fixing of 4 x 24 wt. T5 energy saving light fitting with bulb, choke, cover, G.I. Bracket, Clamp & Nut Bolt connecting wire all accessories refer to catalogue No- CROMPTON CODE – T5SHO424 EB IP 65/MAKE-HPL-CODE-HPLT5STAL424 / PHILIPS including fixing and connections as per instruction of Electrical Engineer-in-charge.	Nos	4		
12	Supply and fixing of 1 x 36 wt. CFL / PLL single bar street light fittings with acrylic cover, connecting wire, GI bracket, clamp, nut bolt and all accessories refer to catalogue No- refer to catalogue No- Crompton [Model-SFE 1614 EB] / Bajaj [Model no- BJS LF 1440 MSLPF, Code- 161597] / Philips including fixing and connections as per instruction of Electrical Engineer-in-charge. (For DG)	Nos	2		
13	Supply and fixing of 1 x 40 wt. patty type tube light fittings complete set with lamp , connecting wire and all accessories refer to catalogue No - MAKE – CROMPTON CODE – DJBN1314EB/MAKE-PHILIPS – MODEL-TARANG/CODE-TMC090 /HPL-CODE-HCPE2136 including fixing and connections as per instruction of Electrical Engineer-in-charge..	Nos	17		
14	Supply and fixing of 20 watt. holder type CFL lamp for the installed angle holder .[Make-CG/Philips/Bajaj]	Nos	9		

15	Supply and fixing of 1200 mm sweep AC ceiling fan with star 5 rated connecting wire and all accessories refer to catalouge No - [MAKE- USHA ,MODEL-ATOM , /CROMPTON,MODEL-EMPOWER 50 /KHAITAN MODEL – NEWTECetc. including hanging and connections as per instruction of Electrical Engineer-in-charge.	Nos	14		
16	Supply and fixing of 300 mm sweep exhaust fan with connecting wire and all accessories refer to catalouge No- Khaitan [Model-Euro] / Usha[Model-Turbojet Dlx] / Cromton [Model-Tranair/Transair reversable] including fixing and connections as per instruction of Electrical Engineer-in-charge	Nos	1		
17	Supply and fixing of earthing including 38 mm. dia. 3 mtr. long G.I pipe[Heavy Duty].The pipe shall have 12 mm. dia. perforated holes at 15 cm centre to centre up to 2.5 mtrs height from the bottom and fitted with a 38 mm. dia. G.I flange at the top with provision of holes for making connection of earth continuity wire,complete with masonry work for earth pit chamber.The earth pit shall have an alternative layer of 105 mm. charcoal and 50 mm. salt up to a depth of 465 mm. and rest shall be filled with charcoal to a further depth of 2035 mm. The earth pit should maintain a minium clearance 1.5 mtr. from building & 2 mtr. in between two earth pit and as per instruction of Electrical Engineer-in-charge.	Nos	1		
18	Supply and fixing of sub earthing with No-8 bare copper wire as earth Continuity wire from Main pannel board to earth electrode inside the wall/ground to a depth of 50 mm. and make good of the wall/ground including all connections.	Rft	60		

E KITCHEN & DINING

--

1	<p>Semi Concealed wiring to different points with ISI marked 1.5 sq.mm(current carrying capacity min. 13 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm.dia. Extra super quality pvc / polythene pipe including supply & fixing of 6A, 250V. flush type switch mounted on 3 mm. thick bakelite cover on required size iron board duly painted & fixed inside/on the wall including supply of ceiling rose / angle holder etc. mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted or RJ box (ceiling) fixed inside/on the wall with 1.0 sq.mm(current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in- charge. [Make- (a)Switch, ceiling rose, angle holder, bell push switch, batten holder etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>				
(a)	Angle Holder Point (DG-2 Nos.& AC-7 Nos.)	Nos	9		
(b)	Tube Light Point	Nos	6		

2	<p>Semi Concealed wiring to Security light point at 18' height from ground level/ top corners of the building with ISI marked 1.5 sq.mm,(current carrying capacity min. 13 Amps.) 650/1100 volt. pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply & fixing of 6 Amp. / 16 Amp. ,250V. flush type switch mounted on 3 mm.thick bakelite cover on required size iron board duly painted & fixed at ground floor lobby inside/on the wall including supply of ceiling rose mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted fixed inside/on the wall with 1.0 sq.mm(current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in- charge. [Make- (a)Switch, ceiling rose etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark] (DG-1 Nos & AC-2 Nos)</p>	Nos	3		
---	--	-----	---	--	--

<p>3</p>	<p>Semi Concealed wiring to ceiling fan point with ISI marked 1.5 sq.mm(current carrying capacity min. 13 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply & fixing of 6A,250V. flush type switch with step type electronic regulator mounted on 3 mm. thick bakelite cover on required size iron board duly painted & fixed inside/on the wall including supply of ceiling rose mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted or RJ box (ceiling) fixed inside/on the wall with 1.0 sq.mm (current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge. [Make- (a)Switch, ceiling rose etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	<p>Nos</p>	<p>3</p>		
----------	--	------------	----------	--	--

4	<p>Semi Concealed wiring to exhaust fan point with ISI marked 1.5 sq.mm(current carrying capacity min. 13 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc /polythene pipe including supply & fixing of 6A,250V. flush type switch mounted on 3 mm. thick bakelite cover on required size iron board duly painted & fixed inside/on the wall including supply of ceiling rose mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted or RJ box (ceiling) fixed inside/on the wall with 1.0 sq.mm(current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge.[Make-(a)Switch, ceiling rose etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	Nos	4		
5	<p>Semi Concealed wiring to 5 pin 6 Amp. socket point with ISI marked 1.5 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply & fixing of 5 pin 6 Amp. 250V. flush type socket & switch mounted on 3 mm. thick bakelite cover on required size iron board / existing board duly painted & fixed inside/on the wall with1.0 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge. [Make-(a)Switch, Socket etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	Nos	2		

6	<p>Semi Concealed wiring to power point [16 Amp.] with ISI marked 6.0 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply & fixing of 5 pin 16 Amp. 250V. flush type socket, switch, separate/combine) mounted on 3 mm.thick bakelite cover on required size iron board duly painted & fixed inside/on the wall with 1.5 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire from 40 Amp SPMCB at BDB to 15 Amp Socket Point including all connections as per instruction of Electrical Engineer-in-charge. [Make- (a)Switch etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	Nos	2		
7	<p>Semi Concealed wiring to submain with two runs of ISI marked 1.5 sq.mm , 650 / 1100 volt. Pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc /polythene pipe with 1.0 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire For B.D.B. to S.B. including all connections as per instruction of Electrical Engineer-in- charge. [Make- (a)Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	Mtr	20		

8	Semi Concealed wiring to submain with two runs of ISI marked 6.0 sq.mm , 650 / 1100 volt. Pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc /polythene pipe with 1.5 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire from Feedar Pillar Box to BDB & from BDB to 15 Amp Socket Point including all connections as per instruction of Electrical Engineer-in- charge.[Make-(a)Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]	Mtr	30		
9	Supply,laying & testing of 3.5 core 25 sq.mm PVC insulated , PVC sheathed aluminium armoured power cable of 1100 volt grade through under ground / surface as per the site requirement including all accessories and connections with making good the damages caused and as per direction of Engineer-in-chargefrom Changeover to 40 Amp. Feedar Pillar Box.	Mtr	70		
10	Supply,laying & testing of 3.5 core 35 sq.mm PVC insulated , PVC sheathed aluminium armoured power cable of 1100 volt grade through under ground / surface as per the site requirement including all accessories and connections with making good the damages caused and as per direction of Engineer-in-charge from 200 Amp. Panel to 63 Amp. Feedar Pillar Box.	Mtr	70		
11	Supply and fixing of 1 x 40 wt. patty type tube light fittings complete set with lamp , connecting wire and all accessories refer to catalouge No - MAKE – CROMPTON CODE – DJBN1314EB/MAKE-PHILIPS – MODEL-TARANG/CODE-TMC090 /HPL-CODE-HCPE2136 including fixing and connections as per instruction of Electrical Engineer-in-charge..	Nos	6		
12	Supply and fixing of 20 watt. holder type CFL lamp for the installed angle holder .[Make-CG/Philips/Bajaj]	Nos	9		

13	Supply and fixing of 1200 mm sweep AC ceiling fan with star 5 rated connecting wire and all accessories refer to catalouge No - [MAKE- USHA ,MODEL-ATOM , /CROMPTON,MODEL-EMPOWER 50 /KHAITAN MODEL – NEWTECetc. including hanging and connections as per instruction of Electrical Engineer-in-charge.	Nos	3		
14	Supply and fixing of 300 mm sweep exhaust fan with connecting wire and all accessories refer to catalouge No- Khaitan [Model-Euro] / Usha[Model-Turbojet Dlx] / Cromton [Model-Tranair/Transair reversable] including fixing and connections as per instruction of Electrical Engineer-in-charge	Nos	4		
15	Supply & fixing of 4 x24 wt. T5 energy saving light fitting with bulb,choke,cover, G.I. Bracket, Clamp & Nut Bolt connecting wire all accessories refer to catalouge No- CROMPTON CODE – T5SHO424 EB IP 65/MAKE-HPL-CODE-HPLT5STAL424 / PHILIPSincluding fixing and connections as per instruction of Electrical Engineer-in-charge.	Nos	2		
16	Supply and fixing of 1 x 36 wt. CFL / PLL single bar street light fittings with acrylic cover, connecting wire,GI bracket, clamp,nut bolt and all accessories refer to catalouge No- refer to catalouge No- Crompton[Model-SFE 1614 EB] / Bajaj [Model no- BJS LF 1440 MSLPF, Code- 161597] /Philips including fixing and connections as per instruction of Electrical Engineer-in-charge. (For DG)	Nos	1		
17	Supply and fixing of 8 way BDB consists of 1 No. 40 Amp. DP MCB & 2 Nos. of 32Amp. SPMCB & 4 Nos of 20 Amp. SPMCB including all accessories and connections.[Make-(a)MCB- Legrand/ Schnider/L&T/ ABB , (b) all other acessories ISI mark]	Set	1		

18	Supply and fixing of 6 way BDB consists of 1 No. 32 Amp. DP MCB & 4 Nos. of 16 Amp. SPMCB including all accessories and connections.[Make-(a)MCB- Legrand/ Schnider/L&T/ ABB , (b) all other accessories ISI mark] (For DG Control)	Set	1		
19	Supply and fixing of Feedar Pillar Box having 01 No. 63 Amp. TPNMCB & 3 Nos. 150 Amp Cut-out & 25 x 6 Busbar 4 Nos. & 2 Pole 40 Amp. Isolater & 40 Amp. 4 Pole Isolater 1 no. (Each 2 Pole Isolater for each Block & 4 Pole Isolater for male Ward 3,4,5,6), INDICATING LAMP WITH CONTROLLING SWITCH - 01 SET etc. including all accessories and connections as per instruction of Electrical Engineer-in- charge.[Make-(a)MCB /MCCB - Legrand/ Schnider/L&T/ ABB, (b)Volt meter, Ammeter-AE/CAPPA, (d) all other accessories ISI mark]	Set	1		
20	Supply and fixing of Feedar Pillar Box having 1 No. 40 Amp TPNMCB & 3 Nos. 63 Amp. Cut-out & 25 x 3 Busbar 4 Nos. 2 Pole 32 Amp. Isolater 5 Nos. (Each 2 Pole Isolater for each Block) , INDICATING LAMP WITH CONTROLLING SWITCH - 01 SET etc. including all accessories and connections as per instruction of Electrical Engineer-in-charge.[Make-(a)MCB /MCCB - Legrand/ Schnider/L&T/ ABB, (b)Volt meter, Ammeter-AE/CAPPA, (d) all other accessories ISI mark]	Set	1		

21	<p>Supply and fixing of earthing including 38 mm. dia. 3 mtr. long G.I pipe[Heavy Duty].The pipe shall have 12 mm. dia. perforated holes at 15 cm centre to centre up to 2.5 mtrs height from the bottom and fitted with a 38 mm. dia. G.I flange at the top with provision of holes for making connection of earth continuity wire,complete with masonry work for earth pit chamber.The earth pit shall have an alternative layer of 105 mm. charcoal and 50 mm. salt up to a depth of 465 mm. and rest shall be filled with charcoal to a further depth of 2035 mm. The earth pit should maintain a minium clearance 1.5 mtr. from building & 2 mtr. in between two earth pit and as per instruction of Electrical Engineer-in-charge.</p>	Nos	2		
22	<p>Supply and fixing of sub earthing with No-8 bare copper wire as earth Continuity wire from Main pannel board to earth electrode inside the wall/ground to a depth of 50 mm. and make good of the wall/ground including all connections.</p>	Rft	120		
F CELL- 1 & 2					

1	<p>Semi Concealed wiring to different points with ISI marked 1.5 sq.mm(current carrying capacity min. 13 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm.dia. Extra super quality pvc / polythene pipe including supply & fixing of 6A, 250V. flush type switch mounted on 3 mm. thick bakelite cover on required size iron board duly painted & fixed inside/on the wall including supply of ceiling rose / angle holder etc. mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted or RJ box (ceiling) fixed inside/on the wall with 1.0 sq.mm(current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in- charge. [Make- (a)Switch, ceiling rose, angle holder, bell push switch, batten holder etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>				
(a)	Angle Holder Point (DG-2 Nos.& AC-2 Nos.)	Nos	4		

2	<p>Semi Concealed wiring to Security light point at 18' height from ground level/ top corners of the building with ISI marked 1.5 sq.mm,(current carrying capacity min. 13 Amps.) 650/1100 volt. pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply & fixing of 6 Amp. / 16 Amp. ,250V. flush type switch mounted on 3 mm.thick bakelite cover on required size iron board duly painted & fixed at ground floor lobby inside/on the wall including supply of ceiling rose mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted fixed inside/on the wall with 1.0 sq.mm(current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in- charge. [Make- (a)Switch, ceiling rose etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark] (DG-1 Nos & AC-2 Nos)</p>	Nos	3		
---	--	-----	---	--	--

3	<p>Semi Concealed wiring to ceiling fan point with ISI marked 1.5 sq.mm(current carrying capacity min. 13 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply & fixing of 6A,250V. flush type switch with step type electronic regulator mounted on 3 mm. thick bakelite cover on required size iron board duly painted & fixed inside/on the wall including supply of ceiling rose mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted or RJ box (ceiling) fixed inside/on the wall with 1.0 sq.mm (current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge. [Make- (a)Switch, ceiling rose etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	Nos	2		
4	<p>Semi Concealed wiring to submain with two runs of ISI marked 1.5 sq.mm , 650 / 1100 volt. Pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc /polythene pipe with 1.0 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire For B.D.B. to S.B. including all connections as per instruction of Electrical Engineer-in- charge. [Make- (a)Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	Mtr	20		
5	<p>Supply and fixing of 6 way BDB consists of 1 No. 32 Amp. DP MCB & 4 Nos. of 16 Amp. SPMCB including all accessories and connections.[Make-(a)MCB- Legrand/ Schnider/L&T/ ABB , (b) all other accessories ISI mark] (For DG & AC Control)</p>	Set	2		

6	Supply, laying & testing of 2 core, 10 sq. mm PVC insulated , PVC sheathed aluminium armoured power cable of 1100 volt grade through under ground / surface as per the site requirement including all accessories and connections with making good the damages caused and as per direction of Engineer-in-charge from 63 & 40 Amp. Feeder Pillar Box at Kitchen to Cell 1 & 2 [Make- (a) Cable- Finolex/ Havells , (b) all other materials ISI mark] (For AC & DG Supply)	Mtr	80		
7	Supply and fixing of 20 watt. holder type CFL lamp for the installed angle holder .[Make-CG/Philips/Bajaj]	Nos	4		
8	Supply & fixing of 4 x 24 wt. T5 energy saving light fitting with bulb, choke, cover, G.I. Bracket, Clamp & Nut Bolt connecting wire all accessories refer to catalogue No- CROMPTON CODE – T5SHO424 EB IP 65/MAKE-HPL-CODE-HPLT5STAL424 / PHILIPS including fixing and connections as per instruction of Electrical Engineer-in-charge.	Nos	3		
9	Supply and fixing of 1200 mm sweep AC ceiling fan with star 5 rated connecting wire and all accessories refer to catalogue No - [MAKE- USHA ,MODEL-ATOM , /CROMPTON,MODEL-EMPOWER 50 /KHAITAN MODEL – NEWTEC etc. including hanging and connections as per instruction of Electrical Engineer-in-charge.	Nos	2		

<p>10</p>	<p>Supply and fixing of earthing including 38 mm. dia. 3 mtr. long G.I pipe[Heavy Duty].The pipe shall have 12 mm. dia. perforated holes at 15 cm centre to centre up to 2.5 mtrs height from the bottom and fitted with a 38 mm. dia. G.I flange at the top with provision of holes for making connection of earth continuity wire,complete with masonry work for earth pit chamber.The earth pit shall have an alternative layer of 105 mm. charcoal and 50 mm. salt up to a depth of 465 mm. and rest shall be filled with charcoal to a further depth of 2035 mm. The earth pit should maintain a minium clearance 1.5 mtr. from building & 2 mtr. in between two earth pit and as per instruction of Electrical Engineer-in-charge.</p>	<p>Nos</p>	<p>1</p>		
<p>11</p>	<p>Supply and fixing of sub earthing with No-8 bare copper wire as earth Continuity wire from Main pannel board to earth electrode inside the wall/ground to a depth of 50 mm. and make good of the wall/ground including all connections.</p>	<p>Rft</p>	<p>30</p>		
<p>G OUT SIDE TOILET 1, 2, 3, 4, 5 (29 Nos.)</p>					

1	<p>Semi Concealed wiring to different points with ISI marked 1.5 sq.mm(current carrying capacity min. 13 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm.dia. Extra super quality pvc / polythene pipe including supply & fixing of 6A, 250V. flush type switch mounted on 3 mm. thick bakelite cover on required size iron board duly painted & fixed inside/on the wall including supply of ceiling rose / angle holder etc. mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted or RJ box (ceiling) fixed inside/on the wall with 1.0 sq.mm(current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in- charge. [Make-(a)Switch, ceiling rose, angle holder, bell push switch, batten holder etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>				
(a)	Angle Holder Point	Nos	29		
2	<p>Semi Concealed wiring to submain with two runs of ISI marked 1.5 sq.mm , 650 / 1100 volt. Pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc /polythene pipe with 1.0 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire For B.D.B. to S.B. including all connections as per instruction of Electrical Engineer-in- charge. [Make-(a)Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	Mtr	30		
3	<p>Supply and fixing of 2 core 4 sq.mm Al. service wire with all accessories including fixing and connections .[Make- Joshi / Multicab] for Service connection to the Toilet</p>	Mtr	150		

4	Supply and fixing of 20 watt. holder type CFL lamp for the installed angle holder .[Make-CG/Philips/Bajaj]	Nos	29		
5	Supply and fixing of 2 way MCB Box consists of 1 No. 20 Amp. DP MCB including all accessories and connections...[Make-(a)MCB- ABB / STANDARD / HAVELLS / LEGRAND/HPL, (b) all other accessories ISI mark]	Set	1		

H FEMALE WARD

1	Semi Concealed wiring to different points with ISI marked 1.5 sq.mm(current carrying capacity min. 13 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm.dia. Extra super quality pvc / polythene pipe including supply & fixing of 6A, 250V. flush type switch mounted on 3 mm. thick bakelite cover on required size iron board duly painted & fixed inside/on the wall including supply of ceiling rose / angle holder etc. mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted or RJ box (ceiling) fixed inside/on the wall with 1.0 sq.mm(current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in- charge. [Make-(a)Switch, ceiling rose, angle holder, bell push switch, batten holder etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]				
(a)	Angle Holder Point (DG-5 Nos.& AC-14 Nos.)	Nos	19		
(b)	Tube Light Point	Nos	9		

2	<p>Semi Concealed wiring to Security light point at 18' height from ground level/ top corners of the building with ISI marked 1.5 sq.mm,(current carrying capacity min. 13 Amps.) 650/1100 volt. pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply & fixing of 6 Amp. / 16 Amp. ,250V. flush type switch mounted on 3 mm.thick bakelite cover on required size iron board duly painted & fixed at ground floor lobby inside/on the wall including supply of ceiling rose mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted fixed inside/on the wall with 1.0 sq.mm(current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in- charge. [Make- (a)Switch, ceiling rose etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark] (DG-3 Nos & AC-4 Nos)</p>	Nos	7		
---	--	-----	---	--	--

<p>3</p>	<p>Semi Concealed wiring to ceiling fan point with ISI marked 1.5 sq.mm(current carrying capacity min. 13 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply & fixing of 6A,250V. flush type switch with step type electronic regulator mounted on 3 mm. thick bakelite cover on required size iron board duly painted & fixed inside/on the wall including supply of ceiling rose mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted or RJ box (ceiling) fixed inside/on the wall with 1.0 sq.mm (current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge. [Make- (a)Switch, ceiling rose etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	<p>Nos</p>	<p>4</p>		
----------	--	------------	----------	--	--

4	<p>Semi Concealed wiring to exhaust fan point with ISI marked 1.5 sq.mm(current carrying capacity min. 13 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc /polythene pipe including supply & fixing of 6A,250V. flush type switch mounted on 3 mm. thick bakelite cover on required size iron board duly painted & fixed inside/on the wall including supply of ceiling rose mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted or RJ box (ceiling) fixed inside/on the wall with 1.0 sq.mm(current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge.[Make-(a)Switch, ceiling rose etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	Nos	4		
5	<p>Semi Concealed wiring to 5 pin 6 Amp. socket point with ISI marked 1.5 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply & fixing of 5 pin 6 Amp. 250V. flush type socket & switch mounted on 3 mm. thick bakelite cover on required size iron board / existing board duly painted & fixed inside/on the wall with1.0 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge. [Make-(a)Switch, Socket etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	Nos	4		

6	Semi Concealed wiring to submain with two runs of ISI marked 1.5 sq.mm , 650 / 1100 volt. Pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc /polythene pipe with 1.0 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire For B.D.B. to S.B. including all connections as per instruction of Electrical Engineer-in- charge. [Make-(a)Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]	Mtr	50		
7	Supply and fixing of 8 way BDB consists of 1 No. 40 Amp. DP MCB & 6 Nos. of 20Amp. SPMCB including all accessories and connections.[Make-(a)MCB- Legrand/ Schnider/L&T/ ABB , (b) all other accessories ISI mark]	Set	1		
8	Supply and fixing of 6 way BDB consists of 1 No. 32 Amp. DP MCB & 4 Nos. of 16 Amp. SPMCB including all accessories and connections.[Make-(a)MCB- Legrand/ Schnider/L&T/ ABB , (b) all other accessories ISI mark] (For DG Control)	Set	1		
9	Supply,laying & testing of 2 core,16 sq.mm PVC insulated , PVC sheathed aluminium armoured power cable of 1100 volt grade through under ground / surface as per the site requirement including all accessories and connections with making good the damages caused and as per direction of Engineer-in-charge from 63 Amp. Feedar Pillar Box at Kitchen to Female Ward [Make- (a) Cable- Finolex/ Havells , (b) all other materials ISI mark] (For AC Supply)	Mtr	40		

10	Supply, laying & testing of 2 core, 10 sq.mm PVC insulated , PVC sheathed aluminium armoured power cable of 1100 volt grade through under ground / surface as per the site requirement including all accessories and connections with making good the damages caused and as per direction of Engineer-in-charge from 63 Amp. Feeder Pillar Box at Kitchen to Female Ward [Make- (a) Cable- Finolex/ Havells , (b) all other materials ISI mark] (For DG Supply)	Mtr	40		
11	Supply & fixing of 4 x 24 wt. T5 energy saving light fitting with bulb, choke, cover, G.I. Bracket, Clamp & Nut Bolt connecting wire all accessories refer to catalogue No- CROMPTON CODE – T5SHO424 EB IP 65/MAKE-HPL-CODE-HPLT5STAL424 / PHILIPS including fixing and connections as per instruction of Electrical Engineer-in-charge.	Nos	4		
12	Supply and fixing of 1 x 36 wt. CFL / PLL single bar street light fittings with acrylic cover, connecting wire, GI bracket, clamp, nut bolt and all accessories refer to catalogue No- refer to catalogue No- Crompton [Model-SFE 1614 EB] / Bajaj [Model no- BJS LF 1440 MSLPF, Code- 161597] / Philips including fixing and connections as per instruction of Electrical Engineer-in-charge. (For DG)	Nos	3		
13	Supply and fixing of 1 x 40 wt. patty type tube light fittings complete set with lamp , connecting wire and all accessories refer to catalogue No - MAKE – CROMPTON CODE – DJBN1314EB/MAKE-PHILIPS – MODEL-TARANG/CODE-TMC090 /HPL-CODE-HCPE2136 including fixing and connections as per instruction of Electrical Engineer-in-charge..	Nos	15		
14	Supply and fixing of 20 watt. holder type CFL lamp for the installed angle holder .[Make-CG/Philips/Bajaj]	Nos	25		

15	Supply and fixing of 1200 mm sweep AC ceiling fan with star 5 rated connecting wire and all accessories refer to catalouge No - [MAKE- USHA ,MODEL-ATOM , /CROMPTON,MODEL-EMPOWER 50 /KHAITAN MODEL – NEWTECetc. including hanging and connections as per instruction of Electrical Engineer-in-charge.	Nos	7		
16	Supply and fixing of 300 mm sweep exhaust fan with connecting wire and all accessories refer to catalouge No- Khaitan [Model-Euro] / Usha[Model-Turbojet Dlx] / Cromton [Model-Tranair/Transair reversable] including fixing and connections as per instruction of Electrical Engineer-in-charge	Nos	4		
17	Supply and fixing of earthing including 38 mm. dia. 3 mtr. long G.I pipe[Heavy Duty].The pipe shall have 12 mm. dia. perforated holes at 15 cm centre to centre up to 2.5 mtrs height from the bottom and fitted with a 38 mm. dia. G.I flange at the top with provision of holes for making connection of earth continuity wire,complete with masonry work for earth pit chamber.The earth pit shall have an alternative layer of 105 mm. charcoal and 50 mm. salt up to a depth of 465 mm. and rest shall be filled with charcoal to a further depth of 2035 mm. The earth pit should maintain a minium clearance 1.5 mtr. from building & 2 mtr. in between two earth pit and as per instruction of Electrical Engineer-in-charge.	Nos	1		
18	Supply and fixing of sub earthing with No-8 bare copper wire as earth Continuity wire from Main pannel board to earth electrode inside the wall/ground to a depth of 50 mm. and make good of the wall/ground including all connections.	Rft	60		
19	Supply and fixing of 2 core 4 sq.mm Al. service wire with all accessories including fixing and connections .[Make- Joshi / Multicab] for Service connection to the Toilet	mtr	60		

I MALE WARD 3,4,5,6

--

1	<p>Semi Concealed wiring to different points with ISI marked 1.5 sq.mm(current carrying capacity min. 13 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm.dia. Extra super quality pvc / polythene pipe including supply & fixing of 6A, 250V. flush type switch mounted on 3 mm. thick bakelite cover on required size iron board duly painted & fixed inside/on the wall including supply of ceiling rose / angle holder etc. mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted or RJ box (ceiling) fixed inside/on the wall with 1.0 sq.mm(current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in- charge. [Make- (a)Switch, ceiling rose, angle holder, bell push switch, batten holder etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>				
(a)	Angle Holder Point (DG-9 Nos.& AC-19 Nos.)	Nos	26		
(b)	Tube Light Point	Nos	28		

2	<p>Semi Concealed wiring to Security light point at 18' height from ground level/ top corners of the building with ISI marked 1.5 sq.mm,(current carrying capacity min. 13 Amps.) 650/1100 volt. pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply & fixing of 6 Amp. / 16 Amp. ,250V. flush type switch mounted on 3 mm.thick bakelite cover on required size iron board duly painted & fixed at ground floor lobby inside/on the wall including supply of ceiling rose mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted fixed inside/on the wall with 1.0 sq.mm(current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in- charge. [Make- (a)Switch, ceiling rose etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark] (DG-2 Nos & AC-8 Nos)</p>	Nos	10		
---	--	-----	----	--	--

<p>3</p>	<p>Semi Concealed wiring to ceiling fan point with ISI marked 1.5 sq.mm(current carrying capacity min. 13 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply & fixing of 6A,250V. flush type switch with step type electronic regulator mounted on 3 mm. thick bakelite cover on required size iron board duly painted & fixed inside/on the wall including supply of ceiling rose mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted or RJ box (ceiling) fixed inside/on the wall with 1.0 sq.mm (current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge. [Make- (a)Switch, ceiling rose etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	<p>Nos</p>	<p>32</p>		
----------	--	------------	-----------	--	--

4	<p>Semi Concealed wiring to exhaust fan point with ISI marked 1.5 sq.mm(current carrying capacity min. 13 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc /polythene pipe including supply & fixing of 6A,250V. flush type switch mounted on 3 mm. thick bakelite cover on required size iron board duly painted & fixed inside/on the wall including supply of ceiling rose mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted or RJ box (ceiling) fixed inside/on the wall with 1.0 sq.mm(current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge.[Make-(a)Switch, ceiling rose etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	Nos	4		
5	<p>Semi Concealed wiring to 5 pin 6 Amp. socket point with ISI marked 1.5 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply & fixing of 5 pin 6 Amp. 250V. flush type socket & switch mounted on 3 mm. thick bakelite cover on required size iron board / existing board duly painted & fixed inside/on the wall with1.0 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge. [Make-(a)Switch, Socket etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	Nos	10		

6	Semi Concealed wiring to submain with two runs of ISI marked 1.0 sq.mm , 650 / 1100 volt. Pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc /polythene pipe with 1.0 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire For B.D.B. to S.B. including all connections as per instruction of Electrical Engineer-in- charge. [Make- (a)Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]	Mtr	75		
7	Semi Concealed wiring to submain with two runs of ISI marked 6.0sq.mm , 650 / 1100 volt. Pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc /polythene pipe with 1.0 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire For M.D.B. to L.D.B. And switch Board including all connections as per instruction of Electrical Engineer-in-charge. [Make- (a)Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]	Mtr	65		
8	Supply and fixing of 8 way BDB consists of 1 No. 32 Amp. DP MCB & 6 Nos. of 20Amp. SPMCB including all accessories and connections.[Make-(a)MCB- Legrand/ Schnider/L&T/ ABB , (b) all other accessories ISI mark]	Set	3		
9	Supply and fixing of 6 way BDB consists of 1 No. 32 Amp. DP MCB & 4 Nos. of 16 Amp. SPMCB including all accessories and connections.[Make-(a)MCB- Legrand/ Schnider/L&T/ ABB , (b) all other accessories ISI mark] (For DG Control)	Set	2		

10	Supply,laying & testing of 31/2 core,25 sq.mm PVC insulated , PVC sheathed aluminium armoured power cable of 1100 volt grade through under ground / surface as per the site requirement including all accessories and connections with making good the damages caused and as per direction of Engineer-in-charge from 63 Amp. Feddar Pillar Box at Kitchen to Female Ward [Make- (a) Cable- Finolex/ Havells , (b) all other materials ISI mark] (For AC Supply)	Mtr	150		
11	Supply,laying & testing of 2 core,16sq.mm PVC insulated , PVC sheathed aluminium armoured power cable of 1100 volt grade through under ground / surface as per the site requirement including all accessories and connections with making good the damages caused and as per direction of Engineer-in-charge from 40 Amp. Feddar Pillar Box at Kitchen to Male Ward [Make- (a) Cable- Finolex/ Havells , (b) all other materials ISI mark] (For DG Supply)	Mtr	150		
12	Supply & fixing of 4 x24 wt. T5 energy saving light fitting with bulb,choke,cover, G.I. Bracket, Clamp & Nut Bolt connecting wire all accessories refer to catalouge No-CROMPTON CODE – T5SHO424 EB IP 65/MAKE-HPL-CODE-HPLT5STAL424 / PHILIPSincluding fixing and connections as per instruction of Electrical Engineer-in-charge.	Nos	10		
13	Supply and fixing of 1 x 36 wt. CFL / PLL single bar street light fittings with acrylic cover, connecting wire,GI bracket, clamp,nut bolt and all accessories refer to catalouge No- refer to catalouge No-Crompton[Model-SFE 1614 EB] / Bajaj [Model no- BJSLF 1440 MSLPF, Code-161597] /Philips including fixing and connections as per instruction of Electrical Engineer-in-charge. (For DG)	Nos	2		

14	Supply and fixing of 1 x 40 wt. patty type tube light fittings complete set with lamp , connecting wire and all accessories refer to catalouge No - MAKE – CROMPTON CODE – DJBN1314EB/MAKE-PHILIPS – MODEL-TARANG/CODE-TMC090 /HPL-CODE-HCPE2136 including fixing and connections as per instruction of Electrical Engineer-in-charge..	Nos	35		
15	Supply and fixing of 20 watt. holder type CFL lamp for the installed angle holder .[Make-CG/Philips/Bajaj]	Nos	25		
16	Supply and fixing of 1200 mm sweep AC ceiling fan with star 5 rated connecting wire and all accessories refer to catalouge No - [MAKE- USHA ,MODEL-ATOM , /CROMPTON,MODEL-EMPOWER 50 /KHAITAN MODEL – NEWTECetc. including hanging and connections as per instruction of Electrical Engineer-in-charge.	Nos	35		
17	Supply and fixing of 300 mm sweep exhaust fan with connecting wire and all accessories refer to catalouge No- Khaitan [Model-Euro] / Usha[Model-Turbojet Dlx] / Cromton [Model-Tranair/Transair reversable] including fixing and connections as per instruction of Electrical Engineer-in-charge	Nos	4		
18	Supply and fixing of earthing including 38 mm. dia. 3 mtr. long G.I pipe[Heavy Duty].The pipe shall have 12 mm. dia. perforated holes at 15 cm centre to centre up to 2.5 mtrs height from the bottom and fitted with a 38 mm. dia. G.I flange at the top with provision of holes for making connection of earth continuity wire,complete with masonry work for earth pit chamber.The earth pit shall have an alternative layer of 105 mm. charcoal and 50 mm. salt up to a depth of 465 mm. and rest shall be filled with charcoal to a further depth of 2035 mm. The earth pit should maintain a minium clearance 1.5 mtr. from building & 2 mtr. in between two earth pit and as per instruction of Electrical Engineer-in-charge.	Nos	3		

19	Supply and fixing of sub earthing with No-8 bare copper wire as earth Continuity wire from Main pannel board to earth electrode inside the wall/ground to a depth of 50 mm. and make good of the wall/ground including all connections.	Rft	120		
20	Supply and fixing of 2 core 4 sq.mm Al. service wire with all accessories including fixing and connections .[Make- Joshi / Multicab] for Service connection to the Toilet	mtr	60		
21	Supply and fixing of 40 Amp Panel with 1 No. 40 Amp. TPN MCB, BusBar & 4 Nos 32 Amp DPMCB including all accessories and connections.[Make-(a)MCB- Legrand/ Schnider/L&T/ ABB , (b) all other accessories ISI mark]	Set	3		

J MEDICAL WARD 1

1	Semi Concealed wiring to different points with ISI marked 1.5 sq.mm(current carrying capcity min. 13 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm.dia. Extra super quality pvc / polythene pipe including supply & fixing of 6A, 250V. flush type switch mounted on 3 mm. thick bakelite cover on required size iron board duly painted & fixed inside/on the wall including supply of ceiling rose / angle holder etc. mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted or RJ box (ceiling) fixed inside/on the wall with 1.0 sq.mm(current carrying capcity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in- charge. [Make-(a)Switch, ceiling rose, angle holder, bell push switch, batten holder etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]				
(a)	Angle Holder Point (DG-1 Nos.& AC-4 Nos.)	Nos	5		

(b)	Tube Light Point	Nos	2		
2	<p>Semi Concealed wiring to Security light point at 18' height from ground level/ top corners of the building with ISI marked 1.5 sq.mm,(current carrying capacity min. 13 Amps.) 650/1100 volt. pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply & fixing of 6 Amp. / 16 Amp. ,250V. flush type switch mounted on 3 mm.thick bakelite cover on required size iron board duly painted & fixed at ground floor lobby inside/on the wall including supply of ceiling rose mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted fixed inside/on the wall with 1.0 sq.mm(current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in- charge. [Make- (a)Switch, ceiling rose etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark] (DG-1 Nos & AC-1 Nos)</p>	Nos	2		

<p>3</p>	<p>Semi Concealed wiring to ceiling fan point with ISI marked 1.5 sq.mm(current carrying capacity min. 13 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply & fixing of 6A,250V. flush type switch with step type electronic regulator mounted on 3 mm. thick bakelite cover on required size iron board duly painted & fixed inside/on the wall including supply of ceiling rose mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted or RJ box (ceiling) fixed inside/on the wall with 1.0 sq.mm (current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge. [Make- (a)Switch, ceiling rose etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	<p>Nos</p>	<p>1</p>		
----------	--	------------	----------	--	--

4	<p>Semi Concealed wiring to exhaust fan point with ISI marked 1.5 sq.mm(current carrying capacity min. 13 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc /polythene pipe including supply & fixing of 6A,250V. flush type switch mounted on 3 mm. thick bakelite cover on required size iron board duly painted & fixed inside/on the wall including supply of ceiling rose mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted or RJ box (ceiling) fixed inside/on the wall with 1.0 sq.mm(current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge.[Make-(a)Switch, ceiling rose etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	Nos	1		
5	<p>Semi Concealed wiring to 5 pin 6 Amp. socket point with ISI marked 1.5 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply & fixing of 5 pin 6 Amp. 250V. flush type socket & switch mounted on 3 mm. thick bakelite cover on required size iron board / existing board duly painted & fixed inside/on the wall with1.0 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge. [Make-(a)Switch , Socket etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	Nos	3		

6	<p>Semi Concealed wiring to power point [16 Amp.] with ISI marked 6.0 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply & fixing of 5 pin 16 Amp. 250V. flush type socket, switch, separate/combine) mounted on 3 mm.thick bakelite cover on required size iron board duly painted & fixed inside/on the wall with 1.5 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire from 40 Amp MCB AT BDB to 15 Amp Socket Point including all connections as per instruction of Electrical Engineer-in-charge. [Make- (a)Switch etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	Nos	2		
7	<p>Semi Concealed wiring to submain with two runs of ISI marked 1.5 sq.mm , 650 / 1100 volt. Pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc /polythene pipe with 1.0 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire For B.D.B. to S.B. including all connections as per instruction of Electrical Engineer-in- charge. [Make- (a)Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	Mtr	25		

8	Semi Concealed wiring to submain with two runs of ISI marked 6.0 sq.mm , 650 / 1100 volt. Pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc /polythene pipe with 1.0 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire For B.D.B. to p.p. including all connections as per instruction of Electrical Engineer-in- charge. [Make-(a)Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]	Mtr	26		
9	Supply and fixing of 8 way BDB consists of 1 No. 40 Amp. DP MCB & 3 Nos. of 20Amp. SPMCB & 3 Nos 40 AMP SPMCB including all accessories and connections.[Make-(a)MCB- Legrand/ Schnider/L&T/ ABB , (b) all other accessories ISI mark]	Set	1		
10	Supply and fixing of 6 way BDB consists of 1 No. 32 Amp. DP MCB & 4 Nos. of 16 Amp. SPMCB including all accessories and connections.[Make-(a)MCB- Legrand/ Schnider/L&T/ ABB , (b) all other accessories ISI mark] (For DG Control)	Set	1		
11	Supply,laying & testing of 2 core,16 sq.mm PVC insulated , PVC sheathed aluminium armoured power cable of 1100 volt grade through under ground / surface as per the site requirement including all accessories and connections with making good the damages caused and as per direction of Engineer-in-charge from 63 Amp. Feedar Pillar Box at Legal to Medical Ward [Make- (a) Cable- Finolex/ Havells , (b) all other materials ISI mark] (For AC Supply)	Mtr	15		

12	Supply, laying & testing of 2 core, 10 sq.mm PVC insulated , PVC sheathed aluminium armoured power cable of 1100 volt grade through under ground / surface as per the site requirement including all accessories and connections with making good the damages caused and as per direction of Engineer-in-charge from 40 Amp. Feeder Pillar Box at legal Ward to Medical Ward [Make- (a) Cable- Finolex/ Havells , (b) all other materials ISI mark] (For DG Supply)	Mtr	15		
13	Supply & fixing of 4 x 24 wt. T5 energy saving light fitting with bulb, choke, cover, G.I. Bracket, Clamp & Nut Bolt connecting wire all accessories refer to catalogue No- CROMPTON CODE – T5SHO424 EB IP 65/MAKE-HPL-CODE-HPLT5STAL424 / PHILIPS including fixing and connections as per instruction of Electrical Engineer-in-charge.	Nos	2		
14	Supply and fixing of 1 x 36 wt. CFL / PLL single bar street light fittings with acrylic cover, connecting wire, GI bracket, clamp, nut bolt and all accessories refer to catalogue No- refer to catalogue No- Crompton [Model-SFE 1614 EB] / Bajaj [Model no- BJS LF 1440 MSLPF, Code- 161597] / Philips including fixing and connections as per instruction of Electrical Engineer-in-charge. (For DG)	Nos	2		
15	Supply and fixing of 1 x 40 wt. patty type tube light fittings complete set with lamp , connecting wire and all accessories refer to catalogue No - MAKE – CROMPTON CODE – DJBN1314EB/MAKE-PHILIPS – MODEL-TARANG/CODE-TMC090 /HPL-CODE-HCPE2136 including fixing and connections as per instruction of Electrical Engineer-in-charge..	Nos	2		
16	Supply and fixing of 20 watt. holder type CFL lamp for the installed angle holder .[Make-CG/Philips/Bajaj]	Nos	5		

17	Supply and fixing of 1200 mm sweep AC ceiling fan with star 5 rated connecting wire and all accessories refer to catalouge No - [MAKE- USHA ,MODEL-ATOM , /CROMPTON,MODEL-EMPOWER 50 /KHAITAN MODEL – NEWTECetc. including hanging and connections as per instruction of Electrical Engineer-in-charge.	Nos	1		
18	Supply and fixing of 300 mm sweep exhaust fan with connecting wire and all accessories refer to catalouge No- Khaitan [Model-Euro] / Usha[Model-Turbojet Dlx] / Cromton [Model-Tranair/Transair reversable] including fixing and connections as per instruction of Electrical Engineer-in-charge	Nos	1		
19	Supply and fixing of earthing including 38 mm. dia. 3 mtr. long G.I pipe[Heavy Duty].The pipe shall have 12 mm. dia. perforated holes at 15 cm centre to centre up to 2.5 mtrs height from the bottom and fitted with a 38 mm. dia. G.I flange at the top with provision of holes for making connection of earth continuity wire,complete with masonry work for earth pit chamber.The earth pit shall have an alternative layer of 105 mm. charcoal and 50 mm. salt up to a depth of 465 mm. and rest shall be filled with charcoal to a further depth of 2035 mm. The earth pit should maintain a minium clearance 1.5 mtr. from building & 2 mtr. in between two earth pit and as per instruction of Electrical Engineer-in-charge.	Nos	1		
20	Supply and fixing of sub earthing with No-8 bare copper wire as earth Continuity wire from Main pannel board to earth electrode inside the wall/ground to a depth of 50 mm. and make good of the wall/ground including all connections.	Rft	60		

21	Supply and installation of 1.5Tr. Split type Air Conditioner (5 Star) of reputed brand with supply and fixing of 5 KVA ,130-280 Volt voltage range wall/floor mounted stabiliser including all accessories,fastner angle copper piping up to 15ft & connections as per instruction of Electrical Engineer-in-charge MAKE of A.C. – CARRIER KURVE, /MAKE – BLUE STAR, CODE-3HW18TB , MAKE OF STABILIZER-JYOTI/SHAKTI/ AUTOTEK	Nos	1		
----	---	-----	---	--	--

K MEDICAL WARD 2

1	Semi Concealed wiring to different points with ISI marked 1.5 sq.mm(current carrying capcity min. 13 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm.dia. Extra super quality pvc / polythene pipe including supply & fixing of 6A, 250V. flush type switch mounted on 3 mm. thick bakelite cover on required size iron board duly painted & fixed inside/on the wall including supply of ceiling rose / angle holder etc. mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted or RJ box (ceiling) fixed inside/on the wall with 1.0 sq.mm(current carrying capcity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in- charge. [Make- (a)Switch, ceiling rose, angle holder, bell push switch, batten holder etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]				
(a)	Angle Holder Point (DG-3 Nos.& AC-15Nos.)	Nos	18		
(b)	Tube Light Point	Nos	10		

2	<p>Semi Concealed wiring to Security light point at 18' height from ground level/ top corners of the building with ISI marked 1.5 sq.mm,(current carrying capacity min. 13 Amps.) 650/1100 volt. pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply & fixing of 6 Amp. / 16 Amp. ,250V. flush type switch mounted on 3 mm.thick bakelite cover on required size iron board duly painted & fixed at ground floor lobby inside/on the wall including supply of ceiling rose mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted fixed inside/on the wall with 1.0 sq.mm(current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in- charge. [Make- (a)Switch, ceiling rose etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark] (DG-1 Nos & AC-1 Nos)</p>	Nos	2		
---	--	-----	---	--	--

<p>3</p>	<p>Semi Concealed wiring to ceiling fan point with ISI marked 1.5 sq.mm(current carrying capacity min. 13 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply & fixing of 6A,250V. flush type switch with step type electronic regulator mounted on 3 mm. thick bakelite cover on required size iron board duly painted & fixed inside/on the wall including supply of ceiling rose mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted or RJ box (ceiling) fixed inside/on the wall with 1.0 sq.mm (current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge. [Make- (a)Switch, ceiling rose etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	<p>Nos</p>	<p>4</p>		
----------	--	------------	----------	--	--

4	<p>Semi Concealed wiring to exhaust fan point with ISI marked 1.5 sq.mm(current carrying capacity min. 13 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc /polythene pipe including supply & fixing of 6A,250V. flush type switch mounted on 3 mm. thick bakelite cover on required size iron board duly painted & fixed inside/on the wall including supply of ceiling rose mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted or RJ box (ceiling) fixed inside/on the wall with 1.0 sq.mm(current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge.[Make-(a)Switch, ceiling rose etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	Nos	1		
5	<p>Semi Concealed wiring to 5 pin 6 Amp. socket point with ISI marked 1.5 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply & fixing of 5 pin 6 Amp. 250V. flush type socket & switch mounted on 3 mm. thick bakelite cover on required size iron board / existing board duly painted & fixed inside/on the wall with1.0 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge. [Make-(a)Switch , Socket etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	Nos	3		

6	<p>Semi Concealed wiring to power point [16 Amp.] with ISI marked 6.0 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply & fixing of 5 pin 16 Amp. 250V. flush type socket, switch, separate/combine) mounted on 3 mm.thick bakelite cover on required size iron board duly painted & fixed inside/on the wall with 1.5 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire from 40 Amp MCB AT BDB to 15 Amp Socket Point including all connections as per instruction of Electrical Engineer-in-charge. [Make- (a)Switch etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	Nos	4		
7	<p>Semi Concealed wiring to submain with two runs of ISI marked 1.5 sq.mm , 650 / 1100 volt. Pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc /polythene pipe with 1.0 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire For B.D.B. to S.B. including all connections as per instruction of Electrical Engineer-in- charge. [Make- (a)Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	Mtr	25		

8	Semi Concealed wiring to submain with two runs of ISI marked 6.0 sq.mm , 650 / 1100 volt. Pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc /polythene pipe with 1.0 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire For B.D.B. to P.P. including all connections as per instruction of Electrical Engineer-in- charge. [Make-(a)Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]	Mtr	26		
9	Supply and fixing of 8 way BDB consists of 1 No. 40 Amp. DP MCB & 2 Nos. of 20Amp. SPMCB & 4 Nos 40 AMP SPMCB including all accessories and connections.[Make-(a)MCB- Legrand/ Schnider/L&T/ ABB , (b) all other accessories ISI mark]	Set	1		
10	Supply and fixing of 6 way BDB consists of 1 No. 32 Amp. DP MCB & 4 Nos. of 16 Amp. SPMCB including all accessories and connections.[Make-(a)MCB- Legrand/ Schnider/L&T/ ABB , (b) all other accessories ISI mark] (For DG Control)	Set	1		
11	Supply,laying & testing of 2 core,16 sq.mm PVC insulated , PVC sheathed aluminium armoured power cable of 1100 volt grade through under ground / surface as per the site requirement including all accessories and connections with making good the damages caused and as per direction of Engineer-in-charge from 63 Amp. Feedar Pillar Box at LegalWard to Medical Ward [Make- (a) Cable- Finolex/ Havells , (b) all other materials ISI mark] (For AC Supply)	Mtr	300		

12	Supply & fixing of 4 x24 wt. T5 energy saving light fitting with bulb,choke,cover, G.I. Bracket, Clamp & Nut Bolt connecting wire all accessories refer to catalouge No- CROMPTON CODE – T5SHO424 EB IP 65/MAKE-HPL-CODE-HPLT5STAL424 / PHILIPSincluding fixing and connections as per instruction of Electrical Engineer-in-charge.	Nos	1		
13	Supply and fixing of 1 x 36 wt. CFL / PLL single bar street light fittings with acrylic cover, connecting wire,GI bracket, clamp,nut bolt and all accessories refer to catalouge No- refer to catalouge No- Crompton[Model-SFE 1614 EB] / Bajaj [Model no- BJSLF 1440 MSLPF, Code-161597] /Philips including fixing and connections as per instruction of Electrical Engineer-in-charge. (For DG)	Nos	1		
14	Supply and fixing of 1 x 40 wt. patty type tube light fittings complete set with lamp , connecting wire and all accessories refer to catalouge No - MAKE – CROMPTON CODE – DJBN1314EB/MAKE-PHILIPS – MODEL-TARANG/CODE-TMC090 /HPL-CODE-HCPE2136 including fixing and connections as per instruction of Electrical Engineer-in-charge..	Nos	10		
15	Supply and fixing of 20 watt. holder type CFL lamp for the installed angle holder .[Make-CG/Philips/Bajaj]	Nos	19		
16	Supply and fixing of 1200 mm sweep AC ceiling fan with star 5 rated connecting wire and all accessories refer to catalouge No - [MAKE- USHA ,MODEL-ATOM , /CROMPTON,MODEL-EMPOWER 50 /KHAITAN MODEL – NEWTECetc. including hanging and connections as per instruction of Electrical Engineer-in-charge.	Nos	2		

17	Supply and fixing of 300 mm sweep exhaust fan with connecting wire and all accessories refer to catalouge No- Khaitan [Model-Euro] / Usha[Model-Turbojet Dlx] / Cromton [Model-Tranair/Transair reversable] including fixing and connections as per instruction of Electrical Engineer-in-charge	Nos	1		
18	Supply and fixing of earthing including 38 mm. dia. 3 mtr. long G.I pipe[Heavy Duty].The pipe shall have 12 mm. dia. perforated holes at 15 cm centre to centre up to 2.5 mtrs height from the bottom and fitted with a 38 mm. dia. G.I flange at the top with provision of holes for making connection of earth continuity wire,complete with masonry work for earth pit chamber.The earth pit shall have an alternative layer of 105 mm. charcoal and 50 mm. salt up to a depth of 465 mm. and rest shall be filled with charcoal to a further depth of 2035 mm. The earth pit should maintain a minium clearance 1.5 mtr. from building & 2 mtr. in between two earth pit and as per instruction of Electrical Engineer-in-charge.	Nos	1		
19	Supply and fixing of sub earthing with No-8 bare copper wire as earth Continuity wire from Main pannel board to earth electrode inside the wall/ground to a depth of 50 mm. and make good of the wall/ground including all connections.	Rft	60		
20	Supply and installation of 1.5Tr. Split type Air Conditioner (5 Star) of reputed brand with supply and fixing of 5 KVA ,130-280 Volt voltage range wall/floor mounted stabiliser including all accessories,fastner angle copper piping up to 15ft & connections as per instruction of Electrical Engineer-in-charge MAKE of A.C. – CARRIER KURVE, /MAKE – BLUE STAR, CODE-3HW18TB , MAKE OF STABILIZER-JYOTI/SHAKTI/ AUTOTEK	Nos	1		

L 30 SEATED MENBARRACK 1& 2

1	<p>Semi Concealed wiring to different points with ISI marked 1.5 sq.mm(current carrying capacity min. 13 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm.dia. Extra super quality pvc / polythene pipe including supply & fixing of 6A, 250V. flush type switch mounted on 3 mm. thick bakelite cover on required size iron board duly painted & fixed inside/on the wall including supply of ceiling rose / angle holder etc. mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted or RJ box (ceiling) fixed inside/on the wall with 1.0 sq.mm(current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in- charge. [Make- (a)Switch, ceiling rose, angle holder, bell push switch, batten holder etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>				
(a)	Angle Holder Point (DG-2Nos.& AC-4Nos.)	Nos	4		
(b)	Tube Light Point	Nos	4		

2	<p>Semi Concealed wiring to Security light point at 18' height from ground level/ top corners of the building with ISI marked 1.5 sq.mm,(current carrying capacity min. 13 Amps.) 650/1100 volt. pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply & fixing of 6 Amp. / 16 Amp. ,250V. flush type switch mounted on 3 mm.thick bakelite cover on required size iron board duly painted & fixed at ground floor lobby inside/on the wall including supply of ceiling rose mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted fixed inside/on the wall with 1.0 sq.mm(current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in- charge. [Make- (a)Switch, ceiling rose etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark] (DG-1 Nos & AC-1 Nos)</p>	Nos	4		
---	--	-----	---	--	--

<p>3</p>	<p>Semi Concealed wiring to ceiling fan point with ISI marked 1.5 sq.mm(current carrying capacity min. 13 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply & fixing of 6A,250V. flush type switch with step type electronic regulator mounted on 3 mm. thick bakelite cover on required size iron board duly painted & fixed inside/on the wall including supply of ceiling rose mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted or RJ box (ceiling) fixed inside/on the wall with 1.0 sq.mm (current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge. [Make- (a)Switch, ceiling rose etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	<p>Nos</p>	<p>4</p>		
<p>4</p>	<p>Semi Concealed wiring to 5 pin 6 Amp. socket point with ISI marked 1.5 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply & fixing of 5 pin 6 Amp. 250V. flush type socket & switch mounted on 3 mm. thick bakelite cover on required size iron board / existing board duly painted & fixed inside/on the wall with 1.0 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge. [Make- (a)Switch, Socket etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	<p>Nos</p>	<p>3</p>		

5	Semi Concealed wiring to submain with two runs of ISI marked 1.5 sq.mm , 650 / 1100 volt. Pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc /polythene pipe with 1.0 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire For B.D.B. to S.B. including all connections as per instruction of Electrical Engineer-in- charge. [Make-(a)Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]	Mtr	25		
6	Supply and fixing of 8 way BDB consists of 1 No. 40 Amp. DP MCB & 6 Nos. of 20Amp. SPMCB including all accessories and connections.[Make-(a)MCB- Legrand/ Schnider/L&T/ ABB , (b) all other accessories ISI mark]	Set	1		
7	Supply and fixing of 6 way BDB consists of 1 No. 32 Amp. DP MCB & 4 Nos. of 16 Amp. SPMCB including all accessories and connections.[Make-(a)MCB- Legrand/ Schnider/L&T/ ABB , (b) all other accessories ISI mark] (For DG Control)	Set	1		
8	Supply,laying & testing of 2 core,16 sq.mm PVC insulated , PVC sheathed aluminium armoured power cable of 1100 volt grade through under ground / surface as per the site requirement including all accessories and connections with making good the damages caused and as per direction of Engineer-in-charge from 63 Amp. Feddar Pillar Box at to Medical Ward [Make- (a) Cable- Finolex/ Havells , (b) all other materials ISI mark] (For AC and DG Supply)	Mtr	400		

9	Supply & fixing of 4 x24 wt. T5 energy saving light fitting with bulb,choke,cover, G.I. Bracket, Clamp & Nut Bolt connecting wire all accessories refer to catalouge No- CROMPTON CODE – T5SHO424 EB IP 65/MAKE-HPL-CODE-HPLT5STAL424 / PHILIPSincluding fixing and connections as per instruction of Electrical Engineer-in-charge.	Nos	2		
10	Supply and fixing of 1 x 36 wt. CFL / PLL single bar street light fittings with acrylic cover, connecting wire,GI bracket, clamp,nut bolt and all accessories refer to catalouge No- refer to catalouge No- Crompton[Model-SFE 1614 EB] / Bajaj [Model no- BJSLF 1440 MSLPF, Code-161597] /Philips including fixing and connections as per instruction of Electrical Engineer-in-charge. (For DG)	Nos	2		
11	Supply and fixing of 1 x 40 wt. patty type tube light fittings complete set with lamp , connecting wire and all accessories refer to catalouge No - MAKE – CROMPTON CODE – DJBN1314EB/MAKE-PHILIPS – MODEL-TARANG/CODE-TMC090 /HPL-CODE-HCPE2136 including fixing and connections as per instruction of Electrical Engineer-in-charge..	Nos	6		
12	Supply and fixing of 20 watt. holder type CFL lamp for the installed angle holder .[Make-CG/Philips/Bajaj]	Nos	6		
13	Supply and fixing of 1200 mm sweep AC ceiling fan with star 5 rated connecting wire and all accessories refer to catalouge No - [MAKE- USHA ,MODEL-ATOM , /CROMPTON,MODEL-EMPOWER 50 /KHAITAN MODEL – NEWTECetc. including hanging and connections as per instruction of Electrical Engineer-in-charge.	Nos	4		

14	<p>Supply and fixing of earthing including 38 mm. dia. 3 mtr. long G.I pipe[Heavy Duty].The pipe shall have 12 mm. dia. perforated holes at 15 cm centre to centre up to 2.5 mtrs height from the bottom and fitted with a 38 mm. dia. G.I flange at the top with provision of holes for making connection of earth continuity wire,complete with masonry work for earth pit chamber.The earth pit shall have an alternative layer of 105 mm. charcoal and 50 mm. salt up to a depth of 465 mm. and rest shall be filled with charcoal to a further depth of 2035 mm. The earth pit should maintain a minium clearance 1.5 mtr. from building & 2 mtr. in between two earth pit and as per instruction of Electrical Engineer-in-charge.</p>	Nos	1		
15	<p>Supply and fixing of sub earthing with No-8 bare copper wire as earth Continuity wire from Main pannel board to earth electrode inside the wall/ground to a depth of 50 mm. and make good of the wall/ground including all connections.</p>	Rft	60		
M LEGAL AID AND CONFERENCE HALL					

1	<p>Semi Concealed wiring to different points with ISI marked 1.5 sq.mm(current carrying capacity min. 13 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm.dia. Extra super quality pvc / polythene pipe including supply & fixing of 6A, 250V. flush type switch mounted on 3 mm. thick bakelite cover on required size iron board duly painted & fixed inside/on the wall including supply of ceiling rose / angle holder etc. mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted or RJ box (ceiling) fixed inside/on the wall with 1.0 sq.mm(current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in- charge. [Make- (a)Switch, ceiling rose, angle holder, bell push switch, batten holder etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>				
(a)	Angle Holder Point (DG-3 Nos.& AC-2 Nos.)	Nos	5		
(b)	Tube Light Point	Nos	4		

2	<p>Semi Concealed wiring to ceiling fan point with ISI marked 1.5 sq.mm(current carrying capacity min. 13 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply & fixing of 6A,250V. flush type switch with step type electronic regulator mounted on 3 mm. thick bakelite cover on required size iron board duly painted & fixed inside/on the wall including supply of ceiling rose mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted or RJ box (ceiling) fixed inside/on the wall with 1.0 sq.mm (current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge. [Make- (a)Switch, ceiling rose etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	Nos	6		
3	<p>Semi Concealed wiring to 5 pin 6 Amp. socket point with ISI marked 1.5 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply & fixing of 5 pin 6 Amp. 250V. flush type socket & switch mounted on 3 mm. thick bakelite cover on required size iron board / existing board duly painted & fixed inside/on the wall with 1.0 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge. [Make- (a)Switch , Socket etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	Nos	6		

<p>4</p>	<p>Semi Concealed wiring to power point [16 Amp.] with ISI marked 6.0 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply & fixing of 5 pin 16 Amp. 250V. flush type socket, switch, separate/combine) mounted on 3 mm.thick bakelite cover on required size iron board duly painted & fixed inside/on the wall with 1.5 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire from 40 Amp SPMCB at BDB to 15 Amp Socket Point including all connections as per instruction of Electrical Engineer-in-charge. [Make- (a)Switch etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	<p>Nos</p>	<p>1</p>		
<p>5</p>	<p>Semi Concealed wiring to submain with two runs of ISI marked 1.5 sq.mm , 650 / 1100 volt. Pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc /polythene pipe with 1.0 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire For B.D.B. to S.B. including all connections as per instruction of Electrical Engineer-in- charge. [Make- (a)Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	<p>Mtr</p>	<p>50</p>		

6	Semi Concealed wiring to submain with two runs of ISI marked 4.0 sq.mm , 650 / 1100 volt. Pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc /polythene pipe with 1.5 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire from Feedar Pillar Box to BDB & from BDB to 15 Amp Socket Point including all connections as per instruction of Electrical Engineer-in- charge.[Make-(a)Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]	Mtr	25		
7	Supply,laying & testing of 3.5 core,25 sq.mm PVC insulated , PVC sheathed aluminium armoured power cable of 1100 volt grade through under ground / surface as per the site requirement including all accessories and connections with making good the damages caused and as per direction of Engineer-in-charge from Changeover to 40 Amp. Feedar Pillar Box.	Mtr	80		
8	Supply,laying & testing of 3.5 core,35 sq.mm PVC insulated , PVC sheathed aluminium armoured power cable of 1100 volt grade through under ground / surface as per the site requirement including all accessories and connections with making good the damages caused and as per direction of Engineer-in-charge from 200 Amp. Panel to 63 Amp. Feedar Pillar Box.	Mtr	80		
9	Supply and fixing of 1 x 40 wt. patty type tube light fittings complete set with lamp , connecting wire and all accessories refer to catalouge No - MAKE – CROMPTON CODE – DJBN1314EB/MAKE-PHILIPS – MODEL-TARANG/CODE-TMC090 /HPL-CODE-HCPE2136 including fixing and connections as per instruction of Electrical Engineer-in-charge..	Nos	6		
10	Supply and fixing of 20 watt. holder type CFL lamp for the installed angle holder .[Make-CG/Philips/Bajaj]	Nos	9		

11	Supply and fixing of 1200 mm sweep AC ceiling fan with star 5 rated connecting wire and all accessories refer to catalouge No - [MAKE- USHA ,MODEL-ATOM , /CROMPTON,MODEL-EMPOWER 50 /KHAITAN MODEL – NEWTECetc. including hanging and connections as per instruction of Electrical Engineer-in-charge.	Nos	7		
12	Supply and fixing of 8 way BDB consists of 1 No. 40 Amp. DP MCB & 1 Nos. of 32Amp. SPMCB & 5 Nos of 20 Amp. SPMCB including all accessories and connections.[Make-(a)MCB- Legrand/ Schnider/L&T/ ABB , (b) all other accessories ISI mark]	Set	1		
13	Supply and fixing of 6 way BDB consists of 1 No. 32 Amp. DP MCB & 4 Nos. of 16 Amp. SPMCB including all accessories and connections.[Make-(a)MCB- Legrand/ Schnider/L&T/ ABB , (b) all other accessories ISI mark] (For DG Control)	Set	1		
14	Supply and fixing of Feedar Pillar Box having 01 No. 63 Amp. TPNMCB & 3 Nos. 150 Amp Cut-out & 25 x 6 Busbar 4 Nos. & 2 Pole 40 Amp. Isolater & 40 Amp. 4 Pole Isolater 1 no. (Each 2 Pole Isolater for each Block) ,INDICATING LAMP WITH CONTROLLING SWITCH - 01 SET etc. including all accessories and connections as per instruction of Electrical Engineer-in- charge.[Make-(a)MCB /MCCB - Legrand/ Schnider/L&T/ ABB, (b)Volt meter, Ammeter-AE/CAPPA, (d) all other accessories ISI mark]	Set	1		

15	<p>Supply and fixing of Feedar Pillar Box having 1 No. 40 Amp TPNMCB & 3 Nos. 63 Amp. Cut-out & 25 x 3 Busbar 4 Nos. 2 Pole 32 Amp. Isolater 5 Nos. (Each 2 Pole Isolater for each Block) , INDICATING LAMP WITH CONTROLLING SWITCH - 01 SET etc. including all accessories and connections as per instruction of Electrical Engineer-in-charge.[Make-(a)MCB /MCCB - Legrand/ Schnider/L&T/ ABB, (b)Volt meter, Ammeter-AE/CAPPA, (d) all other accessories ISI mark]</p>	Set	1		
16	<p>Supply and fixing of earthing including 38 mm. dia. 3 mtr. long G.I pipe[Heavy Duty].The pipe shall have 12 mm. dia. perforated holes at 15 cm centre to centre up to 2.5 mtrs height from the bottom and fitted with a 38 mm. dia. G.I flange at the top with provision of holes for making connection of earth continuity wire,complete with masonry work for earth pit chamber.The earth pit shall have an alternative layer of 105 mm. charcoal and 50 mm. salt up to a depth of 465 mm. and rest shall be filled with charcoal to a further depth of 2035 mm. The earth pit should maintain a minium clearance 1.5 mtr. from building & 2 mtr. in between two earth pit and as per instruction of Electrical Engineer-in-charge.</p>	Nos	2		
17	<p>Supply and fixing of sub earthing with No-8 bare copper wire as earth Continuity wire from Main pannel board to earth electrode inside the wall/ground to a depth of 50 mm. and make good of the wall/ground including all connections.</p>	Rft	60		

N MALEWARD 2

1	<p>Semi Concealed wiring to different points with ISI marked 1.5 sq.mm(current carrying capacity min. 13 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm.dia. Extra super quality pvc / polythene pipe including supply & fixing of 6A, 250V. flush type switch mounted on 3 mm. thick bakelite cover on required size iron board duly painted & fixed inside/on the wall including supply of ceiling rose / angle holder etc. mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted or RJ box (ceiling) fixed inside/on the wall with 1.0 sq.mm(current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in- charge. [Make- (a)Switch, ceiling rose, angle holder, bell push switch, batten holder etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>				
(a)	Angle Holder Point (DG-2Nos.& AC-6Nos.)	Nos	5		
(b)	Tube Light Point	Nos	7		

2	<p>Semi Concealed wiring to Security light point at 18' height from ground level/ top corners of the building with ISI marked 1.5 sq.mm,(current carrying capacity min. 13 Amps.) 650/1100 volt. pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply & fixing of 6 Amp. / 16 Amp. ,250V. flush type switch mounted on 3 mm.thick bakelite cover on required size iron board duly painted & fixed at ground floor lobby inside/on the wall including supply of ceiling rose mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted fixed inside/on the wall with 1.0 sq.mm(current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in- charge. [Make- (a)Switch, ceiling rose etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark] (DG-1 Nos & AC-1 Nos)</p>	Nos	2		
---	--	-----	---	--	--

<p>3</p>	<p>Semi Concealed wiring to exhaust fan point with ISI marked 1.5 sq.mm(current carrying capacity min. 13 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc /polythene pipe including supply & fixing of 6A,250V. flush type switch mounted on 3 mm. thick bakelite cover on required size iron board duly painted & fixed inside/on the wall including supply of ceiling rose mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted or RJ box (ceiling) fixed inside/on the wall with 1.0 sq.mm(current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge.[Make-(a)Switch, ceiling rose etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	<p>Nos</p>	<p>1</p>		
-----------------	--	------------	----------	--	--

4	<p>Semi Concealed wiring to ceiling fan point with ISI marked 1.5 sq.mm(current carrying capacity min. 13 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply & fixing of 6A,250V. flush type switch with step type electronic regulator mounted on 3 mm. thick bakelite cover on required size iron board duly painted & fixed inside/on the wall including supply of ceiling rose mounted on 3 mm. thick bakelite cover on appropriate size iron board duly painted or RJ box (ceiling) fixed inside/on the wall with 1.0 sq.mm (current carrying capacity min. 11 Amps.) 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge. [Make- (a)Switch, ceiling rose etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	Nos	8		
5	<p>Semi Concealed wiring to 5 pin 6 Amp. socket point with ISI marked 1.5 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc / polythene pipe including supply & fixing of 5 pin 6 Amp. 250V. flush type socket & switch mounted on 3 mm. thick bakelite cover on required size iron board / existing board duly painted & fixed inside/on the wall with 1.0 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire including all connections as per instruction of Electrical Engineer-in-charge. [Make- (a)Switch, Socket etc– Anchor Deluxe/ Anchor Penta/Great White /HPL ,(b) Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]</p>	Nos	2		

6	Semi Concealed wiring to submain with two runs of ISI marked 1.5 sq.mm , 650 / 1100 volt. Pvc insulated single core (stranded) unsheathed copper conductor in 19 mm. dia. extra super quality pvc /polythene pipe with 1.0 sq.mm 650/1100 volt pvc insulated single core (stranded) unsheathed copper conductor as earth continuity wire For B.D.B. to S.B. including all connections as per instruction of Electrical Engineer-in- charge. [Make-(a)Wires - Finolex/RR/Great White/HPL/HAVELLS (c) all other materials ISI mark]	Mtr	25		
7	Supply and fixing of 8 way BDB consists of 1 No. 40 Amp. DP MCB & 6 Nos. of 20Amp. SPMCB including all accessories and connections.[Make-(a)MCB- Legrand/ Schnider/L&T/ ABB , (b) all other accessories ISI mark]	Set	1		
8	Supply and fixing of 6 way BDB consists of 1 No. 32 Amp. DP MCB & 4 Nos. of 16 Amp. SPMCB including all accessories and connections.[Make-(a)MCB- Legrand/ Schnider/L&T/ ABB , (b) all other accessories ISI mark] (For DG Control)	Set	1		
9	Supply,laying & testing of 2 core,16 sq.mm PVC insulated , PVC sheathed aluminium armoured power cable of 1100 volt grade through under ground / surface as per the site requirement including all accessories and connections with making good the damages caused and as per direction of Engineer-in-charge from 63 Amp. Feddar Pillar Box at Kitchen to Medical Ward [Make- (a) Cable- Finolex/ Havells , (b) all other materials ISI mark] (For AC Supply)	Mtr	40		

10	Supply,laying & testing of 2 core,10 sq.mm PVC insulated , PVC sheathed aluminium armoured power cable of 1100 volt grade through under ground / surface as per the site requirement including all accessories and connections with making good the damages caused and as per direction of Engineer-in-charge from 32 Amp. Feedar Pillar Box at Kitchen to Medical Ward [Make- (a) Cable- Finolex/ Havells , (b) all other materials ISI mark] (For DG Supply)	Mtr	40		
11	Supply & fixing of 4 x24 wt. T5 energy saving light fitting with bulb,choke,cover, G.I. Bracket, Clamp & Nut Bolt connecting wire all accessories refer to catalouge No- CROMPTON CODE – T5SHO424 EB IP 65/MAKE-HPL-CODE-HPLT5STAL424 / PHILIPSincluding fixing and connections as per instruction of Electrical Engineer-in-charge.	Nos	2		
12	Supply and fixing of 1 x 40 wt. patty type tube light fittings complete set with lamp , connecting wire and all accessories refer to catalouge No - MAKE – CROMPTON CODE – DJBN1314EB/MAKE-PHILIPS – MODEL-TARANG/CODE-TMC090 /HPL-CODE-HCPE2136 including fixing and connections as per instruction of Electrical Engineer-in-charge..	Nos	9		
13	Supply and fixing of 20 watt. holder type CFL lamp for the installed angle holder .[Make-CG/Philips/Bajaj]	Nos	4		
14	Supply and fixing of 1200 mm sweep AC ceiling fan with star 5 rated connecting wire and all accessories refer to catalouge No - [MAKE- USHA ,MODEL-ATOM , /CROMPTON,MODEL-EMPOWER 50 /KHAITAN MODEL – NEWTECetc. including hanging and connections as per instruction of Electrical Engineer-in-charge.	Nos	8		

15	Supply and fixing of earthing including 38 mm. dia. 3 mtr. long G.I pipe[Heavy Duty].The pipe shall have 12 mm. dia. perforated holes at 15 cm centre to centre up to 2.5 mtrs height from the bottom and fitted with a 38 mm. dia. G.I flange at the top with provision of holes for making connection of earth continuity wire,complete with masonry work for earth pit chamber.The earth pit shall have an alternative layer of 105 mm. charcoal and 50 mm. salt up to a depth of 465 mm. and rest shall be filled with charcoal to a further depth of 2035 mm. The earth pit should maintain a minium clearance 1.5 mtr. from building & 2 mtr. in between two earth pit and as per instruction of Electrical Engineer-in-charge.	Nos	1		
16	Supply and fixing of sub earthing with No-8 bare copper wire as earth Continuity wire from Main pannel board to earth electrode inside the wall/ground to a depth of 50 mm. and make good of the wall/ground including all connections.	Rft	60		
O	AREA ILLUMINATION				
1	Supply,laying & testing of 2 core,16 sq.mm PVC insulated , PVC sheathed aluminium armoured power cable of 1100 volt grade through under ground / surface as per the site requirement including all accessories and connections with making good the damages caused and as per direction of Engineer-in-charge from 200 Amp Main Panel To 63 Amp Panel and 63 Amp Panel to out side LT POLE [Make- (a) Cable- Finolex/ Havells , (b) all other materials ISI mark] (For AC Supply)	Mtr	130		
2	Supply & fixing of 4 x24 wt. T5 energy saving light fitting with bulb,choke,cover, G.I. Bracket, Clamp & Nut Bolt connecting wire all accessories refer to catalouge No-CROMPTON CODE – T5SHO424 EB IP 65/MAKE-HPL-CODE-HPLT5STAL424 / PHILIPSincluding fixing and connections as per instruction of Electrical Engineer-in-charge.	Nos	30		

3	Supply and fixing of 2 core 4 sq.mm Al. service wire with all accessories including fixing and connections .[Make- Joshi / Multicab] for Service connection to the Toilet	mtr	100		
4	Supply and fixing of 63 Amp Double Pole Main Panel having 1 No 63 Amp DPMCB ,2 Nos 32DPMCB and 2 Nos 32 Amp DP switch,Bus Bar Includeing all aecessaories and connection.	Nos	1		

TOTAL

Seal & Signature of the Contractor

Sd/-
Asst. Project Manager (Elect.)

Sd/-
APM Elect (Hqr.)