THEODISHASTATEPOLICEHOUSING&WELFARECORPORATIONLTD. JANAPATH, BHOINAGAR, BHUBANESWAR-22.

[Electrical Division]

Ph:0674-2541545,2542921,Fax:0674-2541543

E-mail: jmelectricalophwc@gmail.com,Website:www.ophwc.nic.in

QUOTATION FORMAT FOR WORK SL.NO :- 03

NAME OF THE WORK :-EXECUTION OF EXTERNAL ELECTRIFICATION WORK FOR POWER SUPPLY TO WATCH TOWER NO- 3 AT B.T.I, BURLA IN THE DISTRICT OF SAMBALAPUR.

	QUOTATION CALL REFERENCE	NO: - 55 /J	IM / ELEC	CT / OPHWC/ 202	0-21
NAME & ADDRESS OF THE FIRM					
	SCHEDUI	LE OF WO	RKS	_	
SL.NO	DESCRIPTION OF WORK	UNIT	QNTY	ESTIMATED COST	
				RATE IN (RS)	AMOUNT IN (RS)
	P	ART-A	1	I	Τ
1	8 Mtr. Long 200Kg PSC pole	No	2	2000.0	4,000.00
A	TOTAL MATERIAL COST IN RS				4,000.00
В	Stock, storage and insurance (@3% on A)				120.00
С	TOTAL RS.				4,120.00
D	T&P @ 2% of C				82.40
Е	Contigency @ 3% of C				123.60
F	Transportation @ 7.5% of C				309.00
G	Erection charges @ 20% of C				824.00
	Total Rs.Part-A				5,459.00
	P	ART-B			
2	Cost of 1ph 35mm2 AB Cableon 8mtrX 200Kg LT PSC Pole for LT line(30 mtr.Span) (excluding Pole Cost)	Km	0.06	159425.00	9,565.50
A	SUB TOTAL				9,565.50
В	Stock,storage and insurance (@3% on A)				286.97
С	TOTAL RS.				9,852.47
D	T&P @ 2% of C				197.05

Е	Contigency @ 3% of C			295.57		
F	Transportation @ 7.5% of C			738.93		
G	Erection charges @ 10% on all other materials			985.25		
	Total Rs.Part-B			12,069.27		
	Total Rs.(A+B)			17,528.27		
	TOTAL ESTIMATE COST			17,528.00		
EXCESS	LESS (Please Tick)		%			
	Quoted Amount in Figure	•				
	Quoted Amount in words					
N:B- The Estimated cost is exclusive of GST.						

Signature of Tenderer with seal

Sd/-**Asst. Project Manager (Elect)**

Sd/-Asst. Project Manager (Elect) (Hqr)

Sd/-Joint Manager(Elect)