

**Tender Inviting Authority: JOINT MANAGER [ELECTRICAL DIVISION] ,
THE ODISHA STATE POLICE HOUSING & WELFARE CORPORATION LTD,**

PRICE BID FOR THE WORK UNDER S.L. NO - 02 AS PER IFB

**Name of work :- SUPPLY, INSTALLATION, TESTING & COMMISSIONING OF AREA ILLUMINATION WORK AT
VULNERABLE POLICE POST AT MUNIGUDA POLICE STATION IN THE DIST OF RAYAGADA.**

BID REF NO.- 48 /JM/ ELECT/OPHWC/2020-21

NAME AND ADDRESS OF THE FIRM	
-------------------------------------	--

SCHEDULE OF WORKS

Sl. No.	Description of work	Qty.	Unit	Estimated Rate	AMOUNT Rs.
1	Supply and fixing of 120 WT LED FLOOD Street light fitting comprises of pressure die cast aluminium housing powder coated silver grey and toughened glass,surge arrester 1 No & 100lum/wt Protection IP66 with bulb,choke,cover,G.I bracket & nut bolt connecting wire all accessories(Make-BAJAJ/HAVELLS/HPL)	Nos	20	12,420.00	248,400.00
2	Supply, erection & stringing of 1-phase 2-wire L.T line with (1X35 + 1 x25) mm ² AB cable over 8mtr long PSC Pole along the road. (30 Mtr Span).	KM	0.25	171,959.96	42,989.99
3	Supply and fixing of 63AMP DPMCB-1NO ,63 AMP .240V CUTOFF-2NOS METER SPACE WITH LOCKING ARRANGEMENT,METER CUT OUT,COPPER BUS BAR <(>&<)> INDICATOR including all accessories and connections As per instruction of electrical engineer -in-charge.[Make-(a)MCB /MCCB - Legrand/Schnider/L&T/ ABB, (b)Volt meter, Ammeter-AE/CAPPA, (d) all other accessories ISI mark]	Set	1	8,027.00	8,027.00
4	Supply and laying of 16 sq.mm 2 core PVC Al. Arm Cable of 1.1 KV grade ISI Marked direct in ground including excavation , sand cushioning ,protective covering and refilling the trench etc. as required. (sl no-5.1.1)(Make cable-FINOLEX/ HAVELLS/ POLYCAB)	Mtr	80	237.20	18,976.00
5	Supply & Fixing of 40 mm dia 3 mtr long GI pipe including fixing and connections as per instruction of Electrical Engineer-in-charge.	No	1	531.25	531.25
6	Supply and fixing of earthing with G.I. earthing pipe 3 mtr long 40 mm dia ISI marked including accessories and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc with charcoal and salt as reqd. (csr sr.no- 3.2)	NO.	2	2,148.75	4,297.50

7	Providing and fixing 8 SWG (4mm) dia copper wire on surface or in recess for loop earthing as required. (csr sr.no- 3.18)	Rft	30	22.84	685.20
8	Supply and fixing of 4.0 sqmm 2 core PVC Aluminium service wire including all accessories and connections.(make-Joshi/Multicab)	Mtr	60	37.17	2,230.20
	Total Estimated Cost				326,137.14
SAY RS.					326,137.00
EXCESS	<input type="checkbox"/>	LESS	<input type="checkbox"/>	Please Tick) _____ %	
Quoted Amount in Figure					
Quoted Amount in words					

N.B-The Estimate Cost is Exclusive of G.S.T i.e. @ 12%

Signature of Tenderer with seal

**Sd/-
Asst. Project Manager (Elect.)**

**Sd/-
Asst. Project Manager Elect.(Hqr)**

**Sd/-
Joint Manager (Elect.)**