### THE ODISHA STATE POLICE HOUSING & WELFARE CORPORATION LTD. JANAPATH, BHOINAGAR, BHUBANESWAR – 22. [Electrical Division] Ph: 0674-2541545, 2542921, Fax: 0674-254154 E-mail: jmelectricalophwc@gmail.com, Website: <u>www.ophwc.nic.in</u>

## BID REFERENCE NO: -26 /JM / ELECT / OPHWC/ 2019-20

Name of the Bidder :-

OPHWC

### PRICE BID FOR

## [GROUP-A] MALKANGIRI DISTRICT DESIGN, SUPPLY, INSTALLATION, TESTING & COMMISSIONING OF 08 KW. OFF-GRID SOLAR PV SYSTEM (GROUND MOUNTED) WITH 6 HR. POWER BACK UP AND COMPREHENSIVE MAINTENANCE CONTRACT FOR A PERIOD OF 05(FIVE) YEARS AT 28 LOCATIONS IN THE DISTRICT OF MALKANGIRI.

NAME OF THE LOCATIONS				
A1	COB location at Salimi in the district of Malkangiri.	A15.	COB location at Kudumuguma OP in the district of Malkangiri.	
A2	COB location at Pandripani in the district of Malkangiri.	A16.	COB location at Govindpalli in the district of Malkangiri.	
A3	COB location at Kiyang in the district of Malkangiri.	A17.	COB location at Chintelwada in the district of Malkangiri.	
A4	COB location at Mathili in the district of Malkangiri.	A18.	COB location at Paipalapadar in the district of Malkangiri.	
A5	COB location at New RO (MV 3) in the district of Malkangiri.	A19.	COB location at Janbai in the district of Malkangiri.	
A6	COB location at Kartanpalli in the district of Malkangiri.	A20.	COB location at Badapada in the district of Malkangiri.	
A7	COB location at Podia PS in the district of Malkangiri.	A21.	COB location at Badapadar in the district of Malkangiri.	
A8	COB location at MV-72 in the district of Malkangiri.	A22.	COB location at Tunel Camp in the district of Malkangiri.	
A9	MV-88 in the district of Malkangiri.	A23.	COB location at Jantapai in the district of Malkangiri.	
A10	COB location at MV-21 in the district of Malkangiri.	A24.	COB location at Chitrakonda in the district of Malkangiri.	
A11	COB location at Gomphakonda in the district of Malkangiri.	A25.	MV-79 (112 Bn HQ) in the district of Malkangiri.	
A12	COB location at Bodigeta in the district of Malkangiri.	A26.	Balimela (HQ 144 <sup>th</sup> Bn.) in the district of Malkangiri.	
A13	COB location at Khairput in the district of Malkangiri.	A27.	MV-3 (HQ 160 BN HQ) in the district of Malkangiri.	
A14	COB location at Dyke-III in the district of Malkangiri.	A28.	Chitrakonda (8 <sup>th</sup> BN HQ) in the district of Malkangiri.	

# NAME OF THE LOCATIONS

# SCHEDULE OF WORK FOR 01 NO. LOCATION

SL.NO	ITEMS	MAKE	SPECIFICATION	QUANTITY	QUOTED AMOUNT EXCLUSIVE OF GST FOR 01. NO. LOCATION
1	SOLAR PV PANEL	VIKRAM / WARREE / JAKSON/ MNRE APPROVED MAKE	325 Wp / 330 Wp / 335 Wp (72 CELL)	25NOS.	
2	SOLAR PCU	STATCON / CONSULE NEOWAT / STUDDER / OUTBACK / SWLECT / MNRE APPROVED MAKE	((8KW/10 KVA) 1PH. WITH REMOTE MONITORING	01 NO.	
3	SOLAR BATTERY	EXIDE/NED ENERGY/AMARA RAJA. BATTERIES SHALL HAVE TO BE APPROVED BY ERTL/CPRI/OTHER MNRE APPROVED TEST CENTRE	7.2 Vah/Wp, 2V, C10 BATTERY BANK WITH VRLA GEL TYPE TUBULAR MAINTENANCE FREE BATTERY	AS PER DESIGN	
4	ARRAY JUNCTION BOX DCDB-DCDB	MCB-LEGRAND / REPUTED IP-65 WITH DCSPD	AS PER DESIGN	01 NO.	
5	SINGLE PHASE ACDB WITH LOAD LIMITER UP TO 8 KW	MCB-LEGRAND / REPUTED IP-65 ACSPD	AS PER DESIGN	01 NO.	
6	HRC FUSE WITH BOX	125 A, 400 A [ L&T/REPUTED MAKE] IP-65	125 A, 400 A IP-65	01 JOB	
7	DC CABLE (PANEL TO INVERTER)	POLYCAB / HAVELLS/FINOLE X/SIECHEM	06 SQ. MM. DC SOLAR CABLE- UV-FRS AS PER COLOUR CODE	500 MTR.	
8	AC CABLE (INVERTER TO BATTERY)	POLYCAB /FINOLEX / HAVELLS	25 SQ. MM. 1C COPPER FLEXIBLE CABLE AS PER COLOUR CODE	20 MTR.	

9	AC CABLE (BATTERY)	POLYCAB/FINOLE X / HAVELLS	25 SQ. MM. 1C COPPER FLEXIBLE CABLE AS PER COLOUR CODE	10 MTR.
10	AC CABLE	POLYCAB/FINOLE X / HAVELLS	10 SQ.MM. 1C FRS-UV COPPER FLEXIBLE CABLE AS PER COLOUR CODE	100 MTR.
11	REQUIRED SIZE OF CABLE LUGS	REPUTED	06, 10, 16 & 25 SQ.MM.	AS PER DESIGN
12	MC-4 CONNECTO RS	REPUTED		AS PER REQUIRE MENT
13	STRUCTUR E FOR SOLAR MODULES INCLUDING ASSORTED SIZE OF NUT BOLTS AND ANCHOR BOLTS.	REPUTED	HOT DIP GALVANISE (50MM X 50MM X 3 MM-120 MICRON-PCC ANCHOR BOLT (8MM)-NUT BOLT 10 MM AS PER REQUIREMENT / ALUMINIUM MODULE MOUNTING STRUCTURE	01 SET ( AS PER DESIGN)
14	SCREW & WALL PLUG	REPUTED	SS-PLASTIC	50 NOS.
15	EARTHING	REPUTED	GI-CHEMICAL EAERTHING SET (1.5 MTR. GI ELECTRODE)	03 NOS.
16	LIGHTNING ARRESTER	REPUTED	CU- 1.3 M /13 MM	02 NOS.
17	GI STRIP - TYPE 19 MM X 03 MM/ LA	REPUTED	19 MM X 03 MM	10 MTR.
18	INSULATO R FOR GI STRIP	REPUTED	FLAT INSULATOR AND PLASTIC INSULATOR	60 NOS.
19	CABLE TIE	REPUTED	300 MM BLACK	100 NOS.

[GROUP-A] MALKANGIRI DISTRICT

[11]		ON SL.NO – [I] Rs.			
[1]	QUOTED AMOUNT FOR DESIGN & SUPPLY OF MATERIALS FOR 08 KW. OFF- GRID SOLAR PV SYSTEM (GROUND MOUNTED) WITH 6 HR. POWER BACK UP AND COMPREHENSIVE MAINTENANCE CONTRACT FOR A PERIOD OF 05(FIVE) YEARS AT 28 LOCATIONS IN THE DISTRICT OF MALKANGIRI EXCLUSIVE OF GST.				
25	ALL ELECTRICA L WIRING REQUIRED FOR POWER BACK UP TO THE CRITICAL LOADS OF THE DIFFERENT BUILDINGS	WIRE – POLYCAB/FINOLE X / HAVELLS MCB – LEGRAND /REPUTED SWITCH & SOCKET - ANCHOR (ROMA)	AS PER DESIGN	01 JOB [AS PER DESIGN]	
24	DANGER SIGN BOARD	REPUTED	AS PER DESIGN	02 NOS.	
23	FIRE EXTINGUIS HER (CO 2)	REPUTED	02 K.G.	01 NO.	
22	CABLE TRAY WITH COVER (PVC)	REPUTED	45 MM X 45MM	30 MTS.	
21	FLEXIBLE PIPE	REPUTED	25 SQ.MM.	AS PER REQUIRE MENT	
20	GI SADDLE AND C-CLAMP	REPUTED	25 SQ.MM.	50 NOS.	

[III]	QUOTED AMOUNT FOR INSTALLATION, TESTING & COMMISSIONING OF 08   KW. OFF-GRID SOLAR PV SYSTEM (GROUND MOUNTED) WITH 6 HR. POWER   BACK UP AND COMPREHENSIVE MAINTENANCE CONTRACT FOR A PERIOD OF   05(FIVE) YEARS AT 28 LOCATIONS IN THE DISTRICT OF MALKANGIRI   EXCLUSIVE OF GST.   Rs
[ <b>IV</b> ]	GST @ 18% ON SL.NO - [III] Rs
	TOTAL QUOTED AMOUNT EXCLUSIVE OF GST = [I] + [III]
[V]	Rs
	IN FIGURE :-
	TOTAL QUOTED AMOUNT INCLUSIVE OF GST = [I]+[II]+[III]+[IV]
[VI]	Rs
	IN FIGURE :-

Signature with seal of the Bidder.

Sd/-Sd/-Sd/-Sd/-Asst. Project Manager (Elect) Asst. Project Manager (Elect)(Hqr)Consultant (Elect)Joint Manager (Elect)