

**THE ODISHA STATE POLICE HOUSING & WELFARE CORPORATION LTD.**  
**JANAPATH, BHOINAGAR, BHUBANESWAR - 22**  
 [Electrical Division]  
 Ph: 0674-2541545, 2542921, Fax: 0674-2541543  
 E-mail: jmelectricalophwc@gmail.com, Website: [www.ophwc.nic.in](http://www.ophwc.nic.in)

**PRICE BID FOR THE WORK UNDER SL.NO :- 02 AS PER IFB**

**NAME OF THE WORK- SUPPLY, INSTALLATION, TESTING & COMMISSIONING OF LED SIGN BOARD AT COURT OF ADDITIONAL DISTRICT & SESSIONS JUDGE AND SENIOR CIVIL JUDGE AT ANANDAPUR IN THE DISTRICT OF KEONJHAR.**

**BID RE. NO :- 61/ JM/ ELECT/ OPHWC/ 2020-21**

**NAME & ADDRESS OF  
THE FIRM**

**SCHEDULE OF WORKS**

SL. NO	DESCRIPTION OF WORK	UNIT	QNTY	RATE (Rs.)	AMOUNT (Rs.)
1	<p><b>Supply, Installation, testing &amp; commissioning of LED Sign Board including all Accessories. Area of Signage (28.32'x12.73'=356.44 sq.ft)</b></p> <p><u>Letter Height, Style &amp; Dimensions</u>                      1<sup>st</sup> Line- ଅତିରିକ୍ତ ଜିଲ୍ଲା ଓ ଦୌରାଜଳ - Letter Height 30", Length 268"                      2nd Line ଏବଂ ବରିଷ୍ଠ ଦେଖାଣୀ ଅଦାଲତ Letter Height 30", Length 283"                      3<sup>rd</sup> Line ଆନନ୍ଦପୁର, କେନ୍ଦୁଝର Letter Height 22", Length 176"                      4th Line- COURT OF- Letter Height 15", Length 70"                      5th Line - ADDITIONAL DISTRICT &amp; SESSIONS JUDGE -Letter Height 15", Length 285"                      6th Line - AND SENIOR CIVIL JUDGE -Letter Height 15, Length 171"                      7th line - ANANDAPUR, KEONJHAR - Letter Height 15", Length 170"                      Logo - As per Design (7ft. X 4ft.)</p> <p><u>Specification for Letters:</u>                      3d letters with computerized laser cutting (3mm Imported)                      Letter risings 2" / 3" with PVC female structure                      LED Modules: 4000 numbers approx., IP 67 water and dust resistant for internal letter Illumination                      Power Supplies: 400 watt (18 no.)                      Area of Signage: 28' x 12.73' sq.ft= 356.44 sq.ft. @Rs.1676.37sq.ft</p>	Sq.ft	356.44	1676.37	597525.32

2A	<b>Structural work</b> M.S. Angle : 50X50X5 = 20 rft x 5 nos = 100 rft M.S. Angle : 50X50X5 = 18 rft x 5 nos = 90 rft M.S. Angle : 50X50X5 = 7 rft x 5 nos = 35 rft M.S. Angle : 50X50X5 = 5rft x 5 nos = 25 rft M.S. Angle : 50X50X5 = 3 rft x 5 nos = 15 rft For concrete Pillar = 1.5rft x 10 nos= 15rft Total = 280 rft = 85.36Rmt @ 3.80Kg/Rmt= 324.36 Kg @76.13/Kg	Kg	324.36	76.13	24693.52
2B	<b>MS Hollow Pipe Sections ( 2" x1") 50 x 25x 2.5 mm</b> 30 Rft x 17nos = 510 rft Total = 510 rft = 155.48 Rmt@ 3.24kg/Rmt= 503.75 Kg	Kg	503.75	76.13	38350.48
2 C	Nut Bolt and clamp & Labour Charges	Job	1	18242.85	18242.85
3A	<b>Cement Concrete Pillars ( 1'6" x 1'6" x 1'6" )= 10 Nos</b> 10 x 1'6" x1'6" x 1'6" = 33.75 Cft= 0.96Cum	Cum	0.96	4422.41	4245.51
3B	Shuttering to Columns 10 x 6 ft. x 1'6" = 90 sq.ft = 8.36sq.mtr	Sq.Mt r	8.36	713.56	5965.36
3 C	Labour Charges for Concrete Job	Job	1	8874.90	8874.90
4	Transportation Charges	Job	1	11833.20	11833.20
	TOTAL ESTIMATED COST IN FIGURE				709731.14
	SAY RS.				709731.00
EXCESS <input type="checkbox"/> LESS <input type="checkbox"/> (Please Tick) _____%					
Quoted Amount in Figure					
Quoted Amount in Word					

N.B. – The Estimate Cost is Exclusive of G.S.T. i.e. @ 12%

Signature of the Tenderer

Sd/-  
Asst. Project Manager (Elect.)

Sd/-  
Asst. Project Manager Elect. (Hqr)

Sd/-  
Joint Manager (Elect.)