

THEODISHASTATEPOLICEHOUSING&WELFARECORPORATIONLTD. <u>JANAPATH, BHOINAGAR,BHUBANESWAR-22.</u> [Electrical Division] Ph:0674-2541545,2542921,Fax:0674-254154 E-mail: pmelectricalophwc2021@gmail.com,Website:<u>www.ophwc.nic.in</u>

BID REFERENCE NO: - 82/PM/ELECT/OPHWC/2023-24

Name of the Bidder: -

PRICE BID NO- 01 AS PER IFB

NAME OF THE WORK DESIGN, SUPPLY, INSTALLATION, TESTING & COMMISSIONING OF **20 KWp**. (**2 x10 KWp**.) OFF-GRID SOLAR PV SYSTEM (GROUND/ROOF TOP) MOUNTED WITH 6 HR. POWER BACK UP AND COMPREHENSIVE MAINTENANCE CONTRACT FOR A PERIOD OF 05 FIVE YEARS (SIXTY MONTHS) AT COB, GARJANPALI IN THE DISTRICT OF NUAPADA.

SCHEDULE OF WORK FOR 01 SET (10 KWp.)

| SL.NO | ITEMS | MAKE | SPECIFICATION | QUANTITY |
|-------|----------------|---|--|--|
| 1 | SOLAR PV PANEL | VIKRAM / WARREE / TATA POWER SOLAR SYSTEMS / PANASONIC SOLAR | MINIMUM 500 Wp. OR ABOVE. (MONOCRYSTALLINE) | AS PER REQUIREMENT FOR 10 KWp. OFF- GRID SOLAR PV SYSTEM (GROUND/ROOF TOP) MOUNTED WITH 6 HR. POWER BACK UPTO 10 KW POWER LOAD |
| 2 | SOLAR P.C.U | LUMINOUS/ STATCON / MICROTEK / SU-KAM POWER SYSTEMS | SINGLE PHASE, 120 VOLT,10 KW/ 12.5KVAWITH REMOTE MONITORING SYSTEM. | -DO- |
| 3 | SOLAR BATTERY | EXIDE/ OKAYA / LUMINOUS (BATTERIES SHALL HAVE TO APPROVED BY ERTL/CPRI/OTHER MNRE APPROVED TEST CENTRE) | 7.2 Vah/Wp, 12V, C10, MINMUM 150 AH OR ABOVE LMLA BATTERYBANK . | -DO- |

| r | | | | |
|----|---|--------------------------------|--|------|
| 4 | D.C DISTRIBUTION BOX (D.C.D.B) | MCB-LEGRAND / L & T | AS PER REQUIREMENT | -DO- |
| 5 | A.C DISTRIBUTION BOX (A.C.D.B) | MCB-LEGRAND / L & T | AS PER REQUIREMENT | -DO- |
| 6 | 100 AMP. HRC FUSE WITH ENCLOSURE | L&T/ ABB | AS PER REQUIREMENT | -DO- |
| 7 | D.C CABLE (SOLAR PANEL TO D.C.D.B) | FINOLEX / POLYCAB / HAVELLS | 6 SQ. MM SINGLE CORE COPPER D.C SOLAR CABLE-UV-FRS AS PER COLOUR CODE | -DO- |
| 8 | D.C CABLE (D.C.D.B TO P.C.U, P.C.U TO BATTERY & BATTERY TO P.C.U) | FINOLEX / POLYCAB / HAVELLS | 25 SQ. MM SINGLE CORE COPPER D.C SOLAR CABLE-UV-FRS AS PER COLOUR CODE | -DO- |
| 9 | A.C CABLE (P.C.U TO A.C.D.B&A.C.D.B TO LOAD) | FINOLEX / POLYCAB / HAVELLS | 10 SQ.MM. SINGLE CORECOPPER A.C CABLE-UV-FRS AS PER COLOUR CODE | -DO- |
| 10 | CABLE LUGS | REPUTED | 6, 10, & 25 SQ.MM. | -DO- |
| 11 | MC-4 CONNECTORS | REPUTED | AS PER REQUIREMENT | -DO- |
| 12 | STRUCTURE FOR SOLAR MODULES INCLUDING ASSORTED SIZE NUT BOLTS AND ANCHOR BOLTS. | REPUTED | HOT DIP GALVANISE IRON/ALUMINIUM MOUNTING STRUCTURE WILL HAVE ANGLE OF INCLINATION AS PER THE SITE CONDITION. | -DO- |
| 13 | SCREW & WALL PLUG | REPUTED | SS-PLASTIC | -DO- |
| 14 | EARTHING | ABB/ STAR-X/ UNIVERSIAL | CHEMICAL EAERTHING | -DO- |
| 15 | LIGHTNING ARRESTER | REPUTED | CU- 1.3 M /13 MM | -DO- |
| 16 | HOT DIP G.I STRIP | REPUTED | 19 MM X 3 MM | -DO- |
| 17 | INSULATOR FOR G.I STRIP | REPUTED | FLAT INSULATOR AND PLASTIC INSULATOR | -DO- |
| 18 | CABLE TIE | REPUTED | 300 MM BLACK | -DO- |
| 19 | G.I SADDLE AND C-CLAMP | REPUTED | 25 SQ.MM. | -DO- |
| 20 | FLEXIBLE PIPE | REPUTED | 25 SQ.MM. | -DO- |
| 21 | CABLE TRAY WITH COVER (PVC) | REPUTED | 45 MM X 45MM | -DO- |
| 22 | FIRE EXTINGUISHER (CO ₂) | CEASE FIRE/ FIRE SHIELD/UFS | CO ₂ -2 K.G. | -DO- |
| 23 | DANGER SIGN BOARD | REPUTED | AS PER REQUIREMENT | -DO- |

| 24 | ALL ELECTRICAL WIRINGS& ACCESSORIES REQUIRED FOR POWER BACK UP TO 10 KW POWER LOAD OF | WIRE - FINOLEX/ POLYCAB/HAVELLS MCB - LEGRAND / L & T SWITCH & SOCKET - | AS PER REQUIREMENT | -DO- | | |
|--|---|--|--------------------|------|--|--|
| | DIFFERENT BUILDINGS | ANCHOR (ROMA) | | | | |
| TOTAL | Rs.24,10,714.20 | | | | | |
| - | Rs.24107.14 | | | | | |
| TC | Rs.24,34,821.34 | | | | | |
| (| Rs.24,34,821.00 | | | | | |
| TOTAL ESTIMATED COST FOR TWO SETS(2 x 10 KWp.) IN WARD- TWENTY FOUR LAKH THIRTY FOUR THOUSAND EIGHT HUNDRED TWENTY ONE ONLY. | | | | | | |
| QUOTED AMOUNT % EXCESS OR % LESS THAN THE ESTIMATED COST OF Rs.24,34,821.00 | | | | | | |
| QUOTEED AMOUNT IN FIGURE – Rs. | | | | | | |
| QUOTEED AMOUNT IN WARD – | | | | | | |

N:B- The Estimated cost is exclusive of GST @ 12 %.

Signature with seal of the Bidder.

Sd/-A.P.M (Elect.) Sd/-D.M (Elect.), I/C. Sd/-Project Manager (Elect.)