

THE ODISHA STATE POLICE HOUSING & WELFARE CORPORATION LTD.
JANAPATH, BHOINAGAR, BHUBANESWAR - 22
[Electrical Division]
Ph: 0674-2541545, 2542921, Fax: 0674-2541543
E-mail :- pmelectricalophwc2021@gmail.com, Website: www.ophwc.nic.in

PRICE BID FOR THE WORK UNDER SL. NO :- 01 AS PER IFB

NAME OF THE WORK :- EXECUTION OF AC WIRING IN CONFERENCE HALLS OF PG DEPARTMENT OF EDUCATION, PHYSICS, COMPUTERS SCIENCE, BUSINESS MANAGEMENT, SOCIAL SCIENCE, POPULATION STUDIES, BS & BT & ENVIROMENT SCIENCE AT F.M., UNIVERSITY, BALASORE.

BID REF NO :- 45/PM/ELECT/OPHWC/2023-24

NAME & ADDRESS OF THE FIRM	
---------------------------------------	--

SCHEDULE OF WORKS

Sl. No.	Description of work	Unit	Qty.	Estimated Cost in Rs.	
				RATE IN RS.	AMOUNT IN RS.
1	40000988 Point wiring for 15/16 amp socket outlet (MODULAR) with 4.0sq.mm FR PVC insulated single core multistrand copper conductor ISI marked in recess 20 mm dia non metallic PVC flexible conduit with 15/16 Amp, 250 V modular type switch & socket , phenolic laminated sheet suitable size ISI marked MS Box & earthing Point with 1 x 1.5 sq.mm FR PVC insulated single core multistrand copper conductor for loop earthing etc . (Make of wire Finolex / Anchor / Havells/ V guard) Make-switch/Socket-Legrand /Wipro-North West /Anchor-Panasonic/ havells)(Make of PVC pipe-AKG/NORPACK)	NO	30	983.89	₹ 29,516.70
2	40001003 Recessed wiring to submain in 2 x 4 sqmm FR PVC insulated single core multistarnd copper conductor of ISI marked confirming to IS-694/1990 in 20 mm dia non metallic heavy duty flexible conduit 1.6 mm thick along with 1 x 1.5 sqmm FR PVC insulated single core multistrand copper conductor as earth wire as required (Make of wire Finolex / Anchor / Havells/ V guard) CSR SL .No- 1.8.3)(Make of PVC pipe-AKG/NORPACK)	MTR	900	163.53	₹ 147,177.00

3	40001015 Recessed wiring to submain in 4 x 10 sqmm FR PVC insulated single core multistrand copper conductor of ISI marked confirming to IS-694/1990 in 32 mm dia non metallic heavy duty flexible conduit 1.6 mm thick along with 2 x 4 sqmm FR PVC insulated single core multistrand copper conductor as earth wire as required (Make of wire Finolex / Anchor / Havells/ V guard) CSR SL .No- 1.8.11)(Make of PVC pipe- AKG/NORPACK)	MTR	560	416.75	₹ 233,380.00
4	40001295 Supply and fixing of 4 way mcb Box (4+12) with 63 amp 4P Isolator/ 4P MCB & 12 nos 20 amp SPMCB with sheet steel encloser , distribution board, on surface/ recess, complete with tinned copper bus bar , neutral bus bar, earth bar, din bar , detachable gland plate, interconnection , phosphate and power painted including earthing etc as required. Make-MCB- (Legrand/L&T/ABB/SCHNIDER)	SET	8	4320.9	₹ 34,567.20
	Total Rs.				444,640.90
	Total Estimated Cost				444,640.90
	Total Estimated Cost in Figures				444,641.00
EXCESS	<input type="checkbox"/> LESS <input type="checkbox"/> (Please Tick)			_____ %	
	Quoted Amount in Figure				
	Quoted Amount in words				

N:B- The Estimated cost is exclusive of GST .

Signature of Tenderer with seal

Sd/-
Asst. Project Manager (Elect)

Sd/-
Asst. Project Manager (Elect) (Hqr)

Sd/-
Project Manager(Elect.)