

# THEODISHASTATEPOLICEHOUSING&WELFARECORPORATIONLTD. JANAPATH, BHOINAGAR,BHUBANESWAR-22.

#### [Electrical Division]

Ph:0674-2541545,2542921,Fax:0674-254154

E-mail: pmelectricalophwc2021@gmail.com,Website:www.ophwc.nic.in BID REFERENCE NO: - 82/PM/ELECT/OPHWC/2023-24

Name of the Bidder: -

### PRICE BID NO-10 AS PER IFB

#### NAME OF THE WORK

DESIGN, SUPPLY, INSTALLATION, TESTING & COMMISSIONING OF **08 KWp**. OFF-GRID SOLAR PV SYSTEM (GROUND/ROOF TOP) MOUNTED WITH 6 HR. POWER BACK UP AND COMPREHENSIVE MAINTENANCE CONTRACT FOR A PERIOD OF 05 FIVE YEARS (SIXTY MONTHS) AT COB, BHAOSIL IN THE DISTRICT OF NUAPADA.

## **SCHEDULE OF WORKS**

SL.NO	ITEMS	MAKE	SPECIFICATION	QUANTITY
1	SOLAR PV PANEL	VIKRAM / WARREE / TATA POWER SOLAR SYSTEMS / PANASONIC SOLAR	MINIMUM 500 Wp. OR ABOVE. (MONOCRYSTALLINE)	AS PER REQUIREMENT FOR 08 KWp. OFF- GRID SOLAR PV SYSTEM (GROUND/ROOF TOP) MOUNTED WITH 6 HR. POWER BACK UPTO 08 KW POWER LOAD.
2	SOLAR P.C.U	LUMINOUS/ STATCON / MICROTEK / SU-KAM POWER SYSTEMS	SINGLE PHASE, 120 VOLT,08 KW/ 10KVAWITH REMOTE MONITORING SYSTEM.	-DO-
3	SOLAR BATTERY	EXIDE/ OKAYA / LUMINOUS  (BATTERIES SHALL HAVE TO APPROVED BY ERTL/CPRI/OTHER MNRE APPROVED TEST CENTRE)	7.2 Vah/Wp, 12V, C10, MINMUM 150 AH OR ABOVE LMLA BATTERYBANK .	-DO-

-DO-
-DO-
-DO-

WIR REQ BAC POW	ELECTRICAL INGS& ACCESSORIES QUIRED FOR POWER CK UP TO 10 KW VER LOAD OF FERENT BUILDINGS	WIRE - FINOLEX/ POLYCAB/HAVELLS MCB - LEGRAND / L & T SWITCH & SOCKET - ANCHOR (ROMA)	AS PER REQUIREMENT	-DO-				
TOTAL ESTI	Rs.9,64,285.68							
	Rs.9642.85							
	Rs.9,73,928.53							
Or say	Rs.9,73,929.00							
TOTAL ESTIMATED COST IN WARD- NINE LAKH SEVENTY THREE THOUSAND NINE HUNDRED TWENTY NINE ONLY.								
QUOTED AMOUNT % EXCESS OR % LESS THAN THE ESTIMATED COST OF <b>Rs.9,73,929.00</b>								
QUOTEED AMOUNT IN FIGURE - Rs.								
QUOTEED AMOUNT IN WARD –								
N. D. Till, F. C. and J. C. COST. C. 12 of								

**N:B-** The Estimated cost is exclusive of GST @ 12 %.

Signature with seal of the Bidder.

Sd/- Sd/- Sd/- Sd/- A.P.M (Elect.) D.M (Elect.), I/C. Project Manager (Elect.)