

THE ODISHA STATE POLICE HOUSING & WELFARE CORPORATION LTD.**JANAPATH, BHOINAGAR, BHUBANESWAR - 22****[Electrical Division]****Ph: 0674-2541545, 2542921, Fax: 0674-2541543****E-mail: jmelectricalophwc@gmail.com, Website: www.ophwc.nic.in****PRICE BID FOR THE WORK UNDER S.L. NO :- 02 AS PER IFB****NAME OF THE WORK :-SUPPLY, INSTALLATION, TESTING & COMMISSIONING OF AREA ILLUMINATION WORK AT G. UDAYAGIRI POLICE STATION (ADDITIONAL FORTIFICATION OF VULNERABLE POLICE POST) IN THE DISTRICT OF KANDHAMAL.****BID REF. NO :-51/JM/ ELECT/OPHWC/2020-21****NAME
&
ADDRE
SS OF
THE
FIRM****SCHEDULE OF WORKS**

SL.NO	DESCRIPTION OF WORK	QNTY	UNIT	RATE (Rs)	AMOUNT (Rs)
1	Supply and fixing of 90 WT LED Street light fitting comprises of pressure die cast aluminium housing powder coated silver grey and toughened glass,surge arrester 1 No & 100lum/wt Protection IP66 with bulb,choke,cover,G.I bracket & nut bolt connecting wire all accessories (Make-CROMPTON/PHILIPS/WIPRO)	Nos.	9	10,376.45	93,388.05
2	Supply and fixing of 120 WT LED FLOOD Street light fitting comprises of pressure die cast aluminium housing powder coated silver grey and toughened glass,surge arrester 1 No & 100lum/wt Protection IP66 with bulb,choke,cover,G.I bracket & nut bolt connecting wire all accessories (Make-CROMPTON/PHILIPS/WIPRO)	Nos.	22	13,676.95	300,892.90
3	Supply & fixing of outdoor/indoor type 63A DPMCB panel having I/C-63 A DPMCB-01 No & 63 Amp 2P Change Over,Outgoing -02 Nos 32 Amp DPMCB & 02 nos 32 A DP switch with powder coating all accessories & connectionMake a)MCB/MCCB- legrand/schnider/abb/c&s/havells/HPL,L&T,(b)Voltmeter/Ametre-AE/CAPPA	Nos.	2	20,125.00	40,250.00

4	Supply and laying of 16 sq.mm 2 core PVC Al. Arm Cable of 1.1 KV grade ISI Marked direct in ground including excavation , sand cushioning ,protective covering and refilling the trench etc. as required. (sl no- 5.1.1)(Make cable-Finolex/Havells/Polycab)	Mtr	110	256.59	28,224.90
5	Supply and fixing of 4.0 sqmm 2 core PVC Aluminium service wire including all accessories and connections.(make-Joshi/Multicab)	Mtr	160	40.20	6,432.00
6	Supply & Fixing of 40 mm dia 3 mtr long GI pipe including fixing and connections as per instruction of Electrical Engineer-in-charge.	Nos.	4	580.29	2,321.16
7	Supply and fixing of earthing with G.I. earthing pipe 3 mtr long 40 mm dia ISI marked including accessories and providing masonry enclosure with cover plate having locking arrangement and watring pipe etc with charcoal and salt as reqd. (csr sr.no- 3.2)	Nos.	2	2,421.76	4,843.52
8	Supply & fixing of Sub-earthing with no-8 bare copper wire etc. including all accessories and connections as per specification.	Rft	60	26.66	1,599.60
	Total Estimated Cost				477,952.13
	Say				477,952.00
EXCESS <input type="checkbox"/> LESS <input type="checkbox"/> (Please Tick) _____%					
Quoted Amount in Figure					
Quoted Amount in word					

N.B-The Estimate Cost is Exclusive of G.S.T i.e. @ 12%

Signature of Tenderer with seal

Sd/-
Asst. Project Manager (Elect)

Sd/-
Asst. Project Manager (Elect) (Hqr)

Sd/-
Joint Manager (Elect)