THE ODISHA STATE POLICE HOUSING & WELFARE CORPORATION LTD. JANAPATH, BHOINAGAR, BHUBANESWAR - 22 [Electrical Division] Ph: 0674-2541545, 2542921, Fax: 0674-2541543

E-mail :- pmelectricalophwc2021@gmail.com, Website: www.ophwc.nic.in

PRICE BID FOR THE WORK UNDER SL. NO :- 03 AS PER IFB

NAME OF THE WORK :- EXECUTION OF EXTERNAL ELECTRIFICATION WORK FOR POWER SUPPLY TO 300 BEDED GIRLS HOSTEL AT KALAHANDI UNIVERSITY IN THE DISTRICT OF KALAHANDI.

BID REF NO :- 90/PM/ELECT/OPHWC/2023-24

NAME & ADDRESS **OF THE** FIRM

FIRM									
SCHEDULE OF WORKS									
				Estimated Cost in Rs.					
	Description of work								
Sl. No.		Unit	Qty.	RATE IN RS.	AMOUNT IN RS.				
1	9 Mtr. Long 300 KG PSC Pole	No	8	3900.00	31200.00				
2	11 Mtr. Long 150X150 mm RS Joist Pole for 11 KV Line	No	4	32160.70	128642.80				
3	11/.04 KV 63 KVA Transformer(Star- 1,BIS/EEL-2)	No	1	112450.00	112450.00				
4	Construction of 11/0.4 Plinth mounted 63 KVA S/S on 9 Mtr. Long 300 KG PSC Pole with double disc arrengement and 5 Nos. GI Flat earthing alongwith LT Distribution box with MCCB arrangement.	No	1	181772.17	181772.17				
5	Construction of 3 Ph 3W 11 KV Line using 11 Mtr. Long 150x150 mm Joist Pole for pin point and 2 Nos. single pole cut points with 11 KV 100 sq. mm single core insulated covered conductor and alongwith double disc arrangement .(except cost of pole)	Km	0.15	530323.00	79548.45				
6	Cable ties	No	12.00	836.55	10038.60				
7	Insulated piercing Clamp	No	12.00	1931.60	23179.20				
8	End termination Jointing Kit	No	6.00	3153.15	18918.90				
9	11 KV single pole cut point on 11 Mtr. Long RS Joist Pole	No	1.0	24514.88	24514.88				
10	LT 3 Ph 5 W LT Line with 50 Sq. mm AB Cable on 9 Mtr. Long 300 KG PSC Pole.(except cost of pole)	Km	0.2	241205.90	36180.89				
А	TOTAL MATERIAL COST IN RS				646445.89				

В	Stock, storage and insurance (@3% on A)				19393.38
c	TOTAL RS.				665839.26
	T&P @ 2% of C				
D					13316.79
E	Contigency @ 3% of C				19975.18
F	Transportation @ 7.5% of C				49937.94
	Erection charges of Joist Pole and				
G	Transformer @ 5%				12416.28
Н	Erection charges of PSc Pole@ 20%				6427.20
	Erection charges for other materials@				
I	10%				38537.77
	Total Rs.Part-A				806,450.42
11	Plinth	No	1	27542.40	27,542.40
12	Concrete materials for stay anchor plate	No	6	1652.54	9915.24
13	Padding and Concreting materials for				
	support	No	12	2837.90	34054.80
14	Cost of Fencing with metal spreading	No	1	104661.02	104661.02
	Total Rs.Part-B				176173.46
	Total Estimated Cost				982,623.88
	Total Estimated Cost in Figures				982,624.00
EXCESS	LESS Please Tick)			%	
	Quoted Amount in Figure				
	Quoted Amount in word				

N:B- The Estimated cost is exclusive of GST.

Signature of Tenderer with seal

Sd/-Asst. Project Manager (Elect) Sd/-D.M (Elect) I/C

Sd/-Project Manager(Elect)