

THE ODISHA STATE POLICE HOUSING & WELFARE CORPORATION LTD.
JANAPATH, BHOINAGAR, BHUBANESWAR - 22
[Electrical Division]
Ph: 0674-2541545, 2542921, Fax: 0674-2541543
E-mail :- pmelectricalophwc2021@gmail.com, Website: www.ophwc.nic.in

PRICE BID FOR THE WORK UNDER SL. NO :- 05 AS PER IFB

NAME OF THE WORK :- EXECUTION OF EXTERNAL ELECTRIFICATION & AREA ILLUMINATION WORK AND INSTALLATION OF LIGHTNING PROTECTION SYSTEM AT COB, NAGESH (NEAR VILLAGE PATALPARHA PS-GOLAMUNDA) IN THE DISTRICT OF KALAHANDLI.

BID REF NO :- 83/PM/ELECT/OPHWC/2023-24

NAME & ADDRESS OF THE FIRM	
---------------------------------------	--

SCHEDULE OF WORKS

Sl. No.	Description of work	Unit	Qty.	Estimated Cost in Rs.	
				RATE IN RS.	AMOUNT IN RS.
PART-A	EXTERNAL ELECTRIFICATION				
1	9 Mtr. Long 300 KG PSC Pole	No	4	3900.00	15600.00
2	9 Mtr. Long 150x150 mm RS Joist Pole(30.6 Kg/Mtr.)	No	10	23271.30	232713.00
3	11 Mtr. Long 150x150 mm RS Joist Pole(34.6 Kg/Mtr.)	No	19	32160.70	611053.30
4	11/.04 KV 63 KVA Transformer(Star-1,BIS/EEL-2)	No	1	112450.00	112450.00
5	Construction of 11/0.4 DP mounted 63 KVA S/S with double disc arrangement and 5 Nos. GI Flat earthing alongwith LT Distribution box with MCCB arrangement .	No	1	181772.17	181772.17
6	Construction of 3 Ph 3W 11 KV Line on 11 Mtr. Long 150x150 mm RS Joist Pole for pin point and 2 Nos. single pole cut points with double disc arrangement with 100 sq. mm single core insulated covered conductor.(except cost of pole)	Km	0.72	530323.00	381832.56
7	Cable ties	Nos	18.00	836.55	15057.90
8	Insulated Piercing Clamp	Nos	6.00	1931.60	11589.60
9	End termination kit	Nos	6.00	3153.15	18918.90

10	LT 3 Ph 5 W LT Line with 50 Sq. mm AB Cable on 9 Mtr. Long RS Joist Pole(Except cost of pole)	Km	0.3	241205.90	72361.77
11	Accessories for 11 KV Line DP using 11 Mtr. Long RS Joist pole for tapping arrangement of 11 KV Line	No	1.0	49537.80	49537.80
12	Accessories for 11 KV intermediate 9 mtr. Long PSC Pole(Except cost of pole)	No	1.0	2421.36	2421.36
A	TOTAL MATERIAL COST IN RS				1705308.36
B	Stock,storage and insurance (@3% on A)				51159.25
C	TOTAL RS.				1756467.61
D	T&P @ 2% of C				35129.35
E	Contingency @ 3% of C				52694.03
F	Transportation @ 7.5% of C				131735.07
G	Erection charges of Joist Pole and Transformer @ 5%				49245.14
H	Erection charges of PSc Pole@ 20%				3213.60
I	Erection charges for other materials@ 10%				75549.68
	Total Rs.Part-A				2,104,034.48
13	Concrete materials for stay anchor plate	No	12	1652.54	19830.48
14	Padding and Concreting materials for support	No	33	2837.90	93650.70
15	Cost of Fencing with metal spreading	No	1	104661.02	104661.02
16	Total Rs.Part-B				218142.20
	TOTAL RS.(PART-A)				2,322,176.68
PART-B	AREA ILLUMINATION				
1	40001030 Supply and laying of 16 sq.mm 2 core PVC Al. Arm Cable of 1.1 KV grade ISI Marked direct in ground including excavation , sand cushioning , protective covering and refilling the trench etc. as required. (sl no- 5.1.1)(Make Cable-Finolex/ Havells/Polycab/KEI)	MTR	100	264.25	26425.00
2	40001126 providing and fixing 8 SWG(4mm)dia copper wire on surface or in recess for loop earthing as required (sl no-3.18)	RFT	80	27.89	2231.20
3	40001906 Supply and fixing of 2.5sqmm service wire along with G.I wire for support of service wire including all accessories and connections	MTR	150	29.34	4401.00

4	40002124 Supply & fixing of outdoor/indoor type 63A DPMCB panel having I/C-63 A DPMCB-01 No & 63 Amp 2P Change Over/rotary switch ,Outgoing -02 Nos 32 Amp DPMCB & 02 nos 32 A DP switch with powder coating all accessories & connectionMake a)MCB/MCCB-legrand/schnider/abb/,L&T/Anchor/Panasonic (b)Voltmeter/Ametre-AE/CAPPA	NO	2	20125	40250.00
5	40002201 Supply & fixing of 200x150mmx60mm(nominal) size pvc(SINTEX) looping end box with hinged cover having one no.20 amp rating moulded fuse base &holder, 4amp NS type fuse and 4way connector to be used in the bottom of street light pole for cable termination as per electrical engg -in -charge and consoltant and complite as per electrical engg -in -charge and consultation.	NO	49	1100	53900.00
6	40008291 Supply and fixing of Earthing with GI earth pipe 3 meter long 40 mm dia Heavy Duty TATA make including accessories and providing masonry enclosure with cover plate having locking arrangement and water pipe etc with charcoal and salt as required.(Minimum 1.5 mtr distance from building & 3 mtr distance from earthing to earthing)	NO	2	3483.1	6966.20

7	40008405 Supply & fixing of 90 Wt. LED Street light fitting comprises of Pressure die cast Aluminium housing powder coated in silver grey and toughened glass, Surge Arrester 1 No & 100lum/wt, Protection IP66 having LM 79 LM 80 tested including bulb,choke,cover,G.I bracket,clamp & nut bolt connecting wire with all accessories . (Make-CROMPTON(MODEL NO-TRP-412-90-57-SL-LM-NSG)/PHILIPS(MODEL NO-BRP033 LED90S 90W 9000LM)/WIPRO(MODEL NO-LR08-102-XXX-57-XX)	NO	22	7504.8	165105.60
8	40008415 Supply & fixing of 120 Wt. LED FLOOD light fitting comprises of Pressure die cast Aluminium housing powder coated in silver grey and toughened glass, Surge Arrester 1 No & 100lum/wt, Protection IP66 having LM 79 LM 80 tested including bulb,choke,cover,G.I bracket,clamp & nut bolt connecting wire with all accessories and as per instruction of Electrical Engineer-in-charge . (Make-CROMPTON(MODEL NO-TFS-504-120-57-60D-SL-GL-NSG)/PHILIPS(MODEL NO-BVP142 LED100S 110W 11000)/WIPRO(MODEL NO-LF40-132-060-57-XX)	NO	27	10995.4	296875.80
9	40009048 Supply, erection & stringing of 1-phase 2-wire L.T line with (1X35 + 1 x25) mm ² AB cable over 8mtr long joist Pole along the road. (30 Mtr Span).	MTR	580	619.53	359327.40
TOTAL RS.-PART-B					955,482.20

PART-C	LIGHTNING PROTECTION SYSTEM				
1	<p>40002086 Air-Terminal Supply, Installation, Testing & Commissioning of Early Streamer Emission (ESE-30))type Lightning Air Terminal. Supporting Mast The mounting pole used to support the lightning air terminal shall be minimum length of 05 Mtr. , non corrosive and made up of medium class GI / SS pipe of 1.5" diameter having base plate at bottom for securely fixing the mast on roof top. The mounting pole and supports shall be securely fixed with the brackets and PVC insulated metallic guy wires to withstand the maximum wind velocity of that area. Protection Radius :- 48 Mtr Make :- ABB / STROMKING All the work should be carried out as per the specified specifications and instruction of the Engineer-in-Charge.</p>	NO	2	99250.00	198500.00
2	<p>40002089 Lightning Strike Counter Supply, Installation, Testing & Commissioning of non-electronic & non-resettable (Not require any external power supply) type lightning strike counter to count the lightning stroke having display with IP-67 enclosure including all accessories and connection..(6/7 digit) Make :- ABB / STROMKING All the work should be carried out as per the specified specifications and instruction of the Engineer-in-Charge. Engineer-in-Charge.</p>	NO	2	27250.00	54500.00
3	<p>40002095 Supply, Installation, Testing & Commissioning of maintenance free chemical earthing having enhancing chemical compound with 3 Mtr. Long copper bonded steel rod and suitable termination clamp including all accessories. Make :- ABB / STAR-X / UNIVERSAL All the work should be carried out as per the specified specifications and instruction of the Engineer-in-Charge.</p>	NO	5	16650.00	83250.00

4	<p>40002098 Supply, connection & Testing of sub earthing with 16 Sq.mm single core multi stranded copper flexible wire from surge protection device (SPD) panel to earth electrode & Main panel board to SPD panel including all accessories, cable socketing and connections. Make :- FINOLEX / ANCHOR / HAVELLS All the work should be carried out as per the specified specifications and instruction of the Engineer-in-Charge</p>	MTR	18	154.73	2785.14
5	<p>40002101 Supply, Installation, Testing & Commissioning of indoor type wall mounted Surge protection device (SPD) panel made of 2 mm thick CRCA sheet, dust and vermin proof duly powder coated having the following arrangement & complete factory wired by 16 Sq.mm single core multi stranded copper flexible wire. [A] Type 1+2 AC Surge Protection Device (SPD) (TP+N) (50 KA) - 01 Set [B] 63 Amp. HRC fuse with link – 03 Nos [C] 100 Amp. 4 pole stud connector – 01 No Make of SPD & HRC Fuse :- HAVELLS / L&T / LEGRAND Make of Wire :- FINOLEX / ANCHOR / HAVELLS All the work should be carried out as per the specified specifications and instruction of the Engineer-in-Charge.</p>	NO	1	18665.00	18665.00
6	<p>40002720 Supply and laying of 70sqmm single core FR PVC insulated unseathed copper conductor for voltage grade 1100 volt as per IS-694 in sur face/underground as required(sl no-5.5.2)(Make-KEI/FINOLEX/HAVELLS)</p>	MTR	60	1041.47	62488.20

7	40003593 Supply & Erection of 12 mtr long Heavy gauge Tata MS stepped pole(6mtrx4inch and 6 mtr x 4 inch) with 2ft x2ft x 10mm MS Base plate and 30 cm x 30cm x6mm MS Top plate including fabrication,painting with 1 coat red oxide and 2 coat aluminium paint/12 mtr long heavy gauge G.I stepped pole with 4nos complete stay set for support of pole coupling and conercting along with all accessories complete as required and as per electrical engineer-in-Charge.	SET	2	44714.99	89429.98
TOTAL RS.(PART-C)					509,618.32
Total Cost(PART-A+PART-B+PART-C)					3787277.20
Cess @1%					37872.77
Total Estimated Cost					3825149.97
Total Estimated Cost in Figures					3,825,150.00
EXCESS	<input type="checkbox"/> LESS <input type="checkbox"/> Please Tick)	_____ %			
Quoted Amount in Figure					
Quoted Amount in word					

N:B- The Estimated cost is exclusive of GST .

Signature of Tenderer with seal

Sd/-
Asst. Project Manager (Elect)

Sd/-
D.M I/C (Elect)

Sd/-
Project Manager(Elect)