THE ODISHA STATE POLICE HOUSING & WELFARE CORPORATION LTD. JANAPATH, BHOINAGAR, BHUBANESWAR - 22

[Electrical Division]

Ph: 0674-2541545, 2542921, Fax: 0674-2541543

E-mail:-pmelectricalophwc2021@gmail.com, Website: www.ophwc.nic.in

PRICE BID FOR THE WORK UNDER SL. NO:- 04 AS PER IFB

NAME OF THE WORK :- EXECUTION OF EXTERNAL ELECTRIFICATION WORK FOR POWER SUPPLY TO 6-F TYPE QUARTERS AT LOISINGHA FIRE STATION IN THE DISTRICT OF BOLANGIR.

BID REF NO :- 85/PM/ELECT/OPHWC/2023-24

NAME &
ADDRESS
OF THE
FIRM

SCHEDULE OF WORKS

SI. No.	Description of work	Unit	Qty.	Estimated Cost in Rs.	
				RATE IN RS.	AMOUNT IN RS.
1	116x100 mm RS Joist (9 Mtr. Long)(23				
	Kg/Mtr)	No	4	17491.50	69966.00
2	Cost of 63 KVA S/S (Star-1,BIS/EEL-2)	No	1	112450.00	112450.00
3	Accessories for construction of DP mounted S/S on existing 9 Mtr. Long 300 KG PSC Pole with double Disc arrangement for 63 KVA Tfr. With Busbar arrangement.	No	1	134700.00	134700.00
4	LT 3 Ph 5W with 50 sq. mm(3x50+1x35+1x16) AB cable on 9 Mtr. Long Joist Pole with all acessories.	Km	0.12	449256.00	
5	LT stay set complete	Set	4	676.00	2704.00
6	7/12 SWG GI stay wire, Grade-2	Kg	24	97.50	2340.00
7	LT stay clamp	Pair	4	143.00	572.00
8	LT stay set Insulator	No	4	39.00	156.00
9	Concreting of stay	No	4	1,300.00	5200.00
А	TOTAL MATERIAL COST IN RS				381998.72
В	Stock,storage and insurance (@3% on A)				11459.96
С	TOTAL RS.				393458.68
D	T&P @ 2% of C				7869.17
E	Contigency @ 3% of C				11803.76
F	Transportation @ 7.5% of C				29509.40

	Erection charges of Transformer @ 5% of				
G	trnsformer and joist pole				9394.42
Н	Erection charges of PSc Pole@ 20%				
I	Erection charges for other materials@ 10%				20557.12
	Total Rs.Part-A				472592.56
10	Dismantling cost of 25 KVA S/S	No	1	4750.00	4750.00
	Total Estimated Cost				477342.56
	Total Estimated Cost in Figures				4,77,343.00
EXCESS	LESS Please Tick)			%	
	Quoted Amount in Figure				
	Quoted Amount in word				

N:B- The Estimated cost is exclusive of GST.

Signature of Tenderer with seal

Sd/-Asst. Project Manager (Elect) Sd/-D.M (Elect) I/C

Sd/Project Manager(Elect.)