

THE ODISHA STATE POLICE HOUSING & WELFARE CORPORATION LTD.
JANAPATH, BHOINAGAR, BHUBANESWAR - 22
[Electrical Division]
Ph: 0674-2541545, 2542921, Fax: 0674-2541543
E-mail :- pmelectricalophwc2021@gmail.com, Website: www.ophwc.nic.in

PRICE BID FOR THE WORK UNDER SL. NO :- 04 AS PER IFB

NAME OF THE WORK :- SUPPLY, INSTALLATION, TESTING & COMMISSIONING OF AREA ILLUMINATION WORK AT CAPF DIMIRIGUDA IN THE DIST. OF RAYAGADA.

BID REF NO :- 31/PM/ELECT/OPHWC/2021-22

**NAME &
ADDRESS
OF THE
FIRM**

SCHEDULE OF WORKS

Sl. No.	Description of work	Unit	Qty.	Estimated Cost in Rs.	
				RATE IN RS.	AMOUNT IN RS.
1	Supply & fixing of 120 Wt. LED FLOOD light fitting comprises of Pressure die cast Aluminium housing powder coated in silver grey and toughened glass, Surge Arrester 1 No <(>&<)> 100lum/wt, Protection IP66 having LM 79 LM 80 tested including bulb,choke,cover,G.I bracket,clamp <(>&<)> nut bolt connecting wire with all accessories and as per instruction of Electrical Engineer-in-charge . (Make-HAVELLS/ WIPRO/PHILIPS/ CROMPTON/ PANASONIC)	Nos	30	8,083.35	₹ 2,42,500.50
2	Supply & fixing of 70/72 Wt. LED Street light fitting comprises of Pressure die cast Aluminium housing powder coated in silver grey and toughened glass, Surge Arrester 1 No <(>&<)> 100lum/wt, Protection IP66 having LM 79 LM 80 tested including bulb,choke,cover,G.I bracket,clamp <(>&<)> nut bolt connecting wire with all accessories and as per instruction of Electrical Engineer-in-charge . (Make-HAVELLS/ WIPRO/PHILIPS/ CROMPTON/ PANASONIC)	Nos	25	5,209.50	₹ 1,30,237.50

3	Supply and laying of 16 sq.mm 2 core PVC Al. Arm Cable of 1.1 KV grade ISI Marked direct in ground including excavation , sand cushioning ,protective covering and refilling the trench etc. as required. (sl no-5.1.1)(Make cable-Finolex / Havells/Polycab/KEI	Mtr	160	257.21	₹ 41,153.60
4	Supply & fixing of outdoor/indoor type 63A DPMCB panel having I/C-63 A DPMCB-01 No & 63 Amp 2P Change Over,Outgoing -02 Nos 32 Amp DPMCB & 02 nos 32 A DP switch with powder coating all accessories & connection.[make-(a)MCB /MCCB - Legrand/ L&T/ ABB, (b)volt meter, ammeter-AE/IMP, (d) all other accessories ISI mark]	Set	2	20,125.00	₹ 40,250.00
5	Supply and fixing of 4 sqmm 2 core PVC Aluminium service wire including all accessories and connections.(make-Joshi/Multicab)	Mtr	165	40.20	₹ 6,633.00
6	Supply & Fixing of 40 mm dia 3 mtr long GI pipe including fixing and connections as per instruction of Electrical Engineer-in-charge.	Nos	2	580.29	1,160.58
7	Supply and fixing of earthing with G.I. earthing pipe 3 mtr long 40 mm dia ISI marked including accessories and providing masonry enclosure with cover plate having locking arrangement and watring pipe etc with charcoal and salt as reqd. (csr sr.no- 3.2)	NO.	2	₹ 2,428.66	4,857.32
8	Providing and fixing 8 SWG (4mm) dia copper wire on surface or in recess for loop earthing as required. (csr sr.no- 3.18)	Rft	60	26.75	1,605.00
	Total Estimated Cost				468397.50
	Total Estimated Cost in Figures				468398.00
EXCESS	<input type="checkbox"/> LESS <input type="checkbox"/> (Please Tick)				_____%

Quoted Amount in Figure	
Quoted Amount in words	

N:B- The Estimated cost is exclusive of GST @12%.

Signature of Tenderer with seal

**Sd/-
Asst. Project Manager[Elect.]**

**Sd/-
Project Manager(Elect.)**

**Sd/-
APM (Elect.) Hqr.**