

THE ODISHA STATE POLICE HOUSING & WELFARE CORPORATION LTD.
JANAPATH, BHOINAGAR, BHUBANESWAR - 22
[Electrical Division]
Ph: 0674-2541545, 2542921, Fax: 0674-2541543
E-mail :- pmelectricalophwc2021@gmail.com, Website: www.ophwc.nic.in

PRICE BID FOR THE WORK UNDER SL. NO :- 05 AS PER IFB

NAME OF THE WORK :- EXECUTION OF AREA ILLUMINATION WORK OF JAGDALPUR OUT POST IN THE DIST. OF RAYAGADA.

BID REF NO :- 11/PM/ELECT/OPHWC/2023-24

NAME & ADDRESS OF THE FIRM					
SCHEDULE OF WORKS					
Sl. No.	Description of work	Unit	Qty.	Estimated Cost in Rs.	
				RATE IN RS.	AMOUNT IN RS.
PART-A	AREA ILLUMINATION				
1	40001030 Supply and laying of 16 sq.mm 2 core PVC Al. Arm Cable of 1.1 KV grade ISI Marked direct in ground including excavation , sand cushioning , protective covering and refilling the trench etc. as required. (sl no- 5.1.1)(Make Cable- Finolex/ Havells/Polycab/KEI)	MTR	80	261.76	20940.80
1	40001126 providing and fixing 8 SWG(4mm)dia copper wire on surface or in recess for loop earthing as required (sl no- 3.18)	NO	50	27.49	1374.50
2	40001319 Supply and fixing of 4sqmm service wire along with G.I wire for support of service wire including all accessories and connections from each quarters to energy meter(Make-Joshi/Multicab)	RFT	90	40.20	3618.00
3	40001906 Supply and fixing of 2.5sqmm service wire along with G.I wire for support of service wire including all accessories and connections Ground Floor	MTR	90	29.34	2640.60

4	40002095 Supply, Installation, Testing & Commissioning of maintenance free chemical earthing having enhancing chemical compound with 3 Mtr. Long copper bonded steel rod and suitable termination clamp including all accessories. Make :- ABB / STAR-X / UNIVERSAL All the work should be carried out as per the specified specifications and instruction of the Engineer-in-Charge.	MTR	1	16650.00	16650.00
5	40002124 Supply & fixing of outdoor/indoor type 63A DPMCB panel having I/C-63 A DPMCB-01 No & 63 Amp 2P Change Over,Outgoing -02 Nos 32 Amp DPMCB & 02 nos 32 A DP switch with powder coating all accessories & connectionMake a)MCB/MCCB-legrand/schnider/abb/,L &T/Anchor/Panasonic (b)Voltmeter/Ametre-AE/CAPPA	NO	1	20125.00	20125.00
8	40002126 Supply & Fixing of 40 mm dia 3 mtr long GI pipe including fixing and connections as per instruction of Electrical Engineer-in-charge.	NO	2	580.29	1160.58
9	40002328 Supply & fixing of 70/72 Wt. LED FLOOD light fitting comprises of Pressure die cast Aluminium housing powder coated in silver grey and toughened glass, Surge Arrester 1 No & 100lum/wt, Protection IP66 having LM 79 LM 80 tested including bulb,choke,cover,G.I bracket,clamp & nut bolt connecting wire with all accessories and as per instruction of Electrical Engineer-in-charge . (Make-HAVELLS/ WIPRO/ PHILIPS/ CROMPTON/ PANASONIC)	NO	20	5681.00	113620.00
	Total Rs.				1,80,129.48
	Total Estimated Cost				1,80,129.48
	Total Estimated Cost in Figures				1,80,129.00

EXCESS	<input type="checkbox"/>	LESS	<input type="checkbox"/>	(Please Tick)	_____ %
Quoted Amount in Figure					
Quoted Amount in words					

N:B- The Estimated cost is exclusive of GST .

Signature of Tenderer with seal

Sd/-
Asst. Project Manager[Elect.]

Sd/-
APM (Elect.) Hqr.

Sd/-
Project Manager(Elect.)