

THE ODISHA STATE POLICE HOUSING & WELFARE CORPORATION LTD.

JANAPATH, BHOINAGAR, BHUBANESWAR - 22

[Electrical Division]

Ph: 0674-2541545, 2542921, Fax: 0674-2541543

E-mail :- pmelectricalophwc2021@gmail.com, Website: www.ophwc.nic.in

PRICE BID FOR THE WORK UNDER SL. NO :- 03 AS PER IFB

NAME OF THE WORK :- EXECUTION OF EXTERNAL ELECTRIFICATION WORK FOR POWER SUPPLY TO COB AT LOBENGARH IN THE DISTRICT OF KALAHANDI.

BID REF NO :- 94/PM/ELECT/OPHWC/2022-23

NAME & ADDRESS OF THE FIRM	
---------------------------------------	--

SCHEDULE OF WORKS

Sl. No.	Description of work	Unit	Qty.	Estimated Cost in Rs.	
				RATE IN RS.	AMOUNT IN RS.
1	9 Mtr. Long 300 KG PSC pole for 11 KV Line	No	5	3540.00	17700.00
2	8 Mtr. Long 200 KG PSC pole	No	21	2360.00	49560.00
3	11/04 KV 63 KVA Transformer(Star-1,BIS/EEL-2)	No	1	102070.00	102070.00
4	Construction of DP mounted , 11/0.4 KV S/S using 9 Mtr. Long 300 KG PSC Pole with double disk arrangement and 5 Nos. GI Flat earthing alongwith LT Distribution box with MCCB arrangement for 63 KVA Transformer.	No	1	118155.74	118155.74
5	Accessories for 11 Mtr. Long 300 KG PSC Pole for tapping arrangement of 11 KV Line(Except cost of Pole)	No	1	17547.31	17547.31
6	11 KV Line on 9 Mtr. Long 300 KG PSC Pole with 55 sq. mm AAAC conductor and 2 Nos. single pole cutpoint with double disc arrangement(except cost of pole)(60 Mtr. Span)	Km	0.15	232111.66	34816.75
7	LT 3 Ph 5W line with 50 Sq. mm AB Cable on 8 Mtr. PSC Pole(Except cost of pole)	Km	0.6	407786.76	244672.06
A	TOTAL MATERIAL COST IN RS				584521.86
B	Stock,storage and insurance (@3% on A)				17535.66
C	TOTAL RS.				602057.51
D	T&P @ 2% of C				12041.15
E	Contingency @ 3% of C				18061.73
F	Transportation @ 7.5% of C				45154.31

G	Erection charges of Transformer @ 5%				5256.61
H	Erection charges of PSc Pole@ 20% of C				13855.56
I	Erection charges for other materials@ 10%				42764.76
	Total Rs.Part-A				739191.63
8	Metal spreading	No	1	11800.00	11800.00
9	Boundary Wall with provision of gate	No	1	63059.20	63059.20
	Total Rs.Part-B				74859.20
	TOTAL MATERIAL COST IN RS.				814050.83
	Total Estimated Cost				814050.83
	Total Estimated Cost in Figures				8,14,051.00
EXCESS	<input type="checkbox"/> LESS <input type="checkbox"/> Please Tick)			_____%	
	Quoted Amount in Figure				
	Quoted Amount in word				

N:B- The Estimated cost is exclusive of GST .

Signature of Tenderer with seal

**Sd/-
Asst. Project Manager (Elect)**

**Sd/-
Asst. Project Manager (Elect) (Hqr)**

**Sd/-
Project Manager(Elect)**