

THE ODISHA STATE POLICE HOUSING & WELFARE CORPORATION LTD.
JANAPATH, BHOINAGAR, BHUBANESWAR - 22
[Electrical Division]
Ph: 0674-2541545, 2542921, Fax: 0674-2541543
E-mail :- pmelectricalophwc2021@gmail.com, Website: www.ophwc.nic.in

PRICE BID FOR THE WORK UNDER SL. NO :- 08 AS PER IFB

NAME OF THE WORK :- INSTALLATION OF FIRE EXTINGUISHERS AT 100 SEATED BOYS HOSTEL BUILDING, KMRS, BISAMKATAK IN THE DISTRICT OF RAYAGADA.

BID REF NO :- 66/PM/ELECT/OPHWC/2023-24

**NAME &
ADDRESS
OF THE
FIRM**

SCHEDULE OF WORKS

Sl. No.	Description of work	Unit	Qty.	Estimated Cost in Rs.	
				RATE IN RS.	AMOUNT IN RS.
PART-A	FIRE EXTINGUISHERS				
1	Supply installation testing and commissioning of Clean Agent 2 ltrs capacity Fire Extinguisher with initial charge complete with wall fixing bracket. The extinguisher shall conform to IS 940 and have certification mark engraved. (Make-CEASEFIRE/KANEX/FIRE SHIELD/UFS)	NOS	6	8949.30	53695.80
2	Supply installation testing and commissioning of CO2 4.5kg capacity Fire Extinguisher made from seamless steel cylinder with initial charge complete with wall fixing bracket. The extinguisher shall conform to IS 2878 and have certification mark engraved. (Make-CEASEFIRE/KANEX/FIRE SHIELD/UFS)	NOS	10	7210.50	72105.00

3	Supply and installation testing and commissioning of DCP 6kg capacity Fire Extinguisher with brass forging cap, 120 Gms CO2 gas cartridge inner container, hose and plain nozzle supplied with initial charge complete with wall fixing bracket. The extinguisher shall conform to IS 2171 and have certificate mark engraved.(Make-CEASEFIRE/KANEX/FIRE SHIELD/UFS)	NOS	5	3795.00	18975.00
4	Supply installation testing and commissioning of Mechanical foam type 9 ltrs capacity Fire Extinguisher (AFFFConcentrate) with upright operation with air induction nozzle, 60Gms CO2 gas cartridge supplied with initial charge complete with wall fixing bracket. The extinguisher shall conform to IS 10204 and have certification mark engraved(Make-CEASEFIRE/KANEX/FIRE SHIELD/UFS)	NO	1	4082.50	4082.50
5	Bucket stand to store 3 Nos. of Bucket also having alumium sheet above the stand to prevent the sand from Rain/Sunset.	NO	1	3243.00	3243.00
Total Estimated Cost					152,101.30
Total Estimated Cost in Figures					152,101.00
EXCESS	<input type="checkbox"/> LESS <input type="checkbox"/> (Please Tick)	_____ %			
Quoted Amount in Figure					
Quoted Amount in words					

N:B- The Estimated cost is exclusive of GST .

Signature of Tenderer with seal

Sd/-
Asst. Project Manager [Elect.]

Sd/-
APM (Elect.) Hqr.

Sd/-
Project Manager (Elect.)