

**THE ODISHA STATE POLICE HOUSING & WELFARE CORPORATION LTD.**

**JANAPATH, BHOINAGAR, BHUBANESWAR - 22**

[Electrical Division]

Ph: 0674-2541545, 2542921, Fax: 0674-2541543

E-mail :- pmelectricalophwc2021@gmail.com, Website: www.ophwc.nic.in

**PRICE BID FOR THE WORK UNDER SL. NO :- 03 AS PER IFB**

**NAME OF THE WORK :- SUPPLY, INSTALLATION, TESTING AND COMMISSIONING OF LIGHTNING PROTECTION SYSTEM AND FIRE FIGHTING SYSTEM AT JATANI POLICE STATION,UPD,BHUBANESWAR.**

**BID REF NO :- 73/PM/ELECT/OPHWC/2022-23**

<b>NAME &amp; ADDRESS OF THE FIRM</b>	
---------------------------------------	--

**SCHEDULE OF WORKS**

Sl. No.	Description of work	Unit	Qty.	Estimated Cost in Rs.	
				RATE IN RS.	AMOUNT IN RS.
<b>PART-A</b>	<b>LIGHTENING PROTECTION SYSTEM</b>				
1	<p><u><b>Air-Terminal</b></u> Supply, Installation, Testing &amp; Commissioning of Early Streamer Emission (ESE-30) type lightning Air terminal.</p> <p><u><b>Supporting Mast</b></u> The mounting pole used to support the lightning air terminal shall be minimum length of 05 Mtr. , non corrosive and made up of medium class GI / SS pipe of 1.5" diameter having base plate at bottom for securely fixing the mast on roof top. The mounting pole and supports shall be securely fixed with the brackets and PVC insulated metallic guy wires to withstand the maximum wind velocity of that area.</p> <p><u><b>Protection Radius :- 48 Mtr.</b></u> <b>Make :- ABB / STROMKING</b> All the work should be carried out as per the specified specifications and instruction of the Engineer-in-Charge.</p>	No	1	99,250.00	99,250.00
2	<p><u><b>Lightning Strike Counter</b></u> Supply, Installation, Testing &amp; Commissioning of non-electronic &amp; non-resettable (Not require any external power supply) type lightning strike counter to count the lightning stroke having display with IP-67 enclosure including all accessories and connection..(6/7 digit)</p> <p><b>Make :- ABB / STROMKING</b> All the work should be carried out as per the specified specifications and instruction of the Engineer-in-Charge.</p>	No	1	27,250.00	27,250.00
3	<p>Suupply and Laying of 70 sq. mm single core FR PVC inulated unshathed copper conductor for voltage grade 1100 volt as per IS-694 in surface/Underground as required.(Sl. No.-5.5.2)(Make-KEI/FINOLEX/HAVELLS)</p>	Mtr	60	1,036.88	62,212.80
4	<p>Supply, Installation, Testing &amp; Commissioning of maintenance free chemical earthing having enhancing chemical compound with 3 Mtr. Long copper bonded steel rod and suitable termination clamp including all accessories.</p> <p><b>Make :- ABB / STAR-X / UNIVERSAL</b> All the work should be carried out as per the specified specifications and instruction of the Engineer-in-Charge.</p>	No	3	16,650.00	49,950.00

4	Supply, connection & Testing of sub earthing with 16 Sq.mm single core multi stranded copper flexible wire from surge protection device (SPD) panel to earth electrode & Main panel board to SPD panel including all accessories, cable socketing and connections. <b>Make :- FINOLEX / ANCHOR / HAVELLS</b> All the work should be carried out as per the specified specifications and instruction of the Engineer-in-Charge.	Mtr	18	154.73	2,785.14
5	Supply, Installation, Testing & Commissioning of indoor type wall mounted <b>Surge protection device (SPD)</b> panel made of 2 mm thick CRCA sheet, dust and vermin proof duly powder coated having the following arrangement & complete factory wired by 16 Sq.mm single core multi stranded copper flexible wire. [A] Type 1+2 AC Surge Protection Device (SPD) (TP+N) (50 KA) - 01 Set [B] 63 Amp. HRC fuse with link – 03 Nos [C] 100 Amp. 4 pole stud connector – 01 No Make of SPD & HRC Fuse :- HAVELLS / L&T / LEGRAND <b>Make of Wire :- FINOLEX / ANCHOR / HAVELLS</b> All the work should be carried out as per the specified specifications and instruction of the Engineer-in-Charge.	No	1	18,665.00	18,665.00
<b>Total Rs.</b>					<b>260112.94</b>
PART-B	<b>FIRE EXTINGUISHERS(MAKE-UFS/FIRE SHIELD/CEASE FIRE)</b>				
1	Supply installation testing and commissioning of CO2 4.5kg capacity Fire Extinguisher made from seamless steel cylinder with initial charge complete with wall fixing bracket. The extinguisher shall conform to IS 2878 and have certification mark engraved.	Each	10	6270.00	62700.00
2	Supply and Fixing stored pressure portable (powder type) ABC-6.0 kg Fire Extinguisher including all accessories as per latest IS with wall bracket and raw plug.	Each	10	3300.00	33000.00
<b>Total Rs.</b>					<b>95700.00</b>
<b>Total Estimated Cost</b>					<b>355812.94</b>
<b>Total Estimated Cost in Figures</b>					<b>3,55,813.00</b>
EXCESS	<input type="checkbox"/> LESS <input type="checkbox"/> (Please Tick)	_____ %			
Quoted Amount in Figure					
Quoted Amount in words					

N:B- The Estimated cost is exclusive of GST .

Signature of Tenderer with seal

Sd/-  
Asst. Project Manager (Elect)

Sd/-  
Asst. Project Manager (Elect) (Hqr)

Sd/-  
Project Manager(Elect.)