THE ODISHA STATE POLICE HOUSING & WELFARE CORPORATION LTD. JANAPATH, BHOINAGAR, BHUBANESWAR - 22 [Electrical Division]

Ph: 0674-2541545, 2542921, Fax: 0674-2541543

E-mail :- pmelectricalophwc2021@gmail.com, Website: www.ophwc.nic.in

PRICE BID FOR THE WORK UNDER SL. NO :- 08 AS PER IFB

NAME OF THE WORK :- EXECUTION OF EXTERNAL ELECTRIFICATION WORK FOR POWER SUPPLY TO SADAR POLICE STATION AND STAFF QUARTERS AT BHAWANIPATNA IN THE DISTRICT OF KALAHANDI.

BID REF NO :- 90/PM/ELECT/OPHWC/2023-24

NAME & ADDRESS OF THE FIRM

FIRM									
SCHEDULE OF WORKS									
				Estimated Cost in Rs.					
Sl. No.	Description of work	Unit	Qty.	RATE IN RS.	AMOUNT IN RS.				
1	9 Mtr. Long 300 KG PSC Pole	No	14	3900.00	54600.00				
2	11 Mtr. Long 150X150 mm RS Joist Pole for 11 KV Line	No	1	32160.70	32160.70				
3	11/.04 KV 100 KVA Transformer(Star- 1,BIS/EEL-2)	No	1	152100.00	152100.00				
4	Construction of 11/0.4 Plinth mounted 100 KVA S/S on 9 Mtr. Long 300 KG PSC Pole with double disc arrengement and 5 Nos. GI Flat earthing alongwith LT Distribution box with MCCB arrangement.	No	1	183233.76	183233.76				
5	Construction of 3 Ph 3W 11 KV Line using 11 Mtr. Long 150x150 mm Joist Pole for pin point and 2 Nos. single pole cut points with 11 KV 100 sq. mm single core insulated covered conductor and alongwith double disc arrangement .(except cost of pole)	Km	0.05	530323.00	26516.15				
6	Cable ties	No	6.00	836.55	5019.30				
7	Insulated piercing Clamp	No	6.00	1931.60	11589.60				
8	End termination Jointing Kit	No	6.00	3153.15	18918.90				
9	11 KV single pole cut point on 11 Mtr. Long RS Joist Pole	No	1.0	24514.88	24514.88				
10	LT 3 Ph 5 W LT Line with 50 Sq. mm AB Cable on 9 Mtr. Long 300 KG PSC Pole.(except cost of pole)	Km	0.4	241205.90	96482.36				
А	TOTAL MATERIAL COST IN RS				605135.65				

			1		
В	Stock, storage and insurance (@3% on A)				18154.07
С	TOTAL RS.				623289.72
D	T&P @ 2% of C				12465.79
E	Contigency @ 3% of C				18698.69
F	Transportation @ 7.5% of C				46746.73
	Erection charges of Joist Pole and				
G	Transformer @ 5%				9489.43
н	Erection charges of PSc Pole@ 20%				11247.60
	Erection charges for other materials@				
I	10%				37726.32
	Total Rs.Part-A				759,664.28
11	Plinth	No	1	27542.40	27,542.40
12	Concrete materials for stay anchor plate	No	6	1652.54	9915.24
13	Padding and Concreting materials for				
	support	No	15	2837.90	42568.50
14	Cost of Fencing with metal spreading	No	1	104661.02	104661.02
	Total Rs.Part-B				184687.16
	Total Estimated Cost				944,351.44
	Total Estimated Cost in Figures				944,351.00
EXCESS	LESS Please Tick)			%	
	Quoted Amount in Figure				
	Quoted Amount in word				

N:B- The Estimated cost is exclusive of GST.

Signature of Tenderer with seal

Sd/-Asst. Project Manager (Elect) Sd/-D.M (Elect) I/C

Sd/-Project Manager(Elect)